

REVISIONS			
REV.	DESCRIPTION	DATE	APPROVED
	INITIAL RELEASE		



2	1 Ea.	Right Hand Support Plate (MIRROR OF LEFT SUPPORT PLATE)		6061-T6 Al
1	1 Ea.	Left Hand Support Plate		6061-T6 Al
ITEM NO.	QTY	PART NO.	DESCRIPTION	MATERIAL SPECIFICATION
BILL OF MATERIALS				
UNLESS OTHERWISE SPECIFIED TOLERANCES ARE:		APPROVALS DATE Monterey Bay Aquarium Research Institute 		
1 PLACE DIM ±.1/16	2 PLACE DIM ±.02	3 PLACE DIM ±.005	ANGLES ±1°	DRAWN F. Shane 15Feb07 ENGINEER F. Shane 15Feb07 CHECKED PROJECT NO. 200001 PROJECT Greenhouse Gases III SIZE B DWG. NO. 1003441.DWG SCALE NONE CAD FILE: Project Library\200001 Greenhouse GasesIII SHEET 1 OF 1
1. DIMENSIONS ARE IN INCHES 2. DIMENSION LIMITS HELD AFTER PLATING. 3. REMOVE BURRS AND SHARP EDGES .015 MAX. 4. MACHINED FILLET RADII .0150-.030. 5. MACHINED DIAMETERS ON A COMMON CENTERLINE CONCENTRIC WITHIN .005 6. PERPENDICULARITY & PARALLELISM OF MACHINED SURFACES .002 PER INCH. MAX .012 INCHES FOR SINGLE SURFACE.		7700 Sandholdt RD. Moss Landing, CA 95039 PH: (408) 775-1700		
DO NOT SCALE DRAWING		WEIGHT 0.78# ea.		

Note 7. Bead blast all surfaces, then Hard Black Anodize in Accordance with MIL-A-8625F TYPE III (.001" Thick).