

MOLYKOTE(R) 55 O-RING GREASE

Version	Revision Date:	SDS Number:	Date of last issue: 09/24/2015
1.6	02/12/2016	623335-00007	Date of first issue: 10/09/2014

SECTION 1. IDENTIFICATION

Product name : MOLYKOTE(R) 55 O-RING GREASE

Product code : 000000000001889826

Manufacturer or supplier's details

Company name of supplier : Dow Corning Corporation

Address : South Saginaw Road
Midland Michigan 48686

Telephone : (989) 496-6000

Emergency telephone : 24 Hour Emergency Telephone : (989) 496-5900
CHEMTREC : (800) 424-9300**Recommended use of the chemical and restrictions on use**

Recommended use : Lubricants and lubricant additives

SECTION 2. HAZARDS IDENTIFICATION

GHS Classification

Skin sensitization : Category 1

GHS label elements

Hazard pictograms :



Signal Word : Warning

Hazard Statements : H317 May cause an allergic skin reaction.

Precautionary Statements : **Prevention:**
P261 Avoid breathing dust/ fume/ gas/ mist/ vapors/ spray.
P272 Contaminated work clothing must not be allowed out of the workplace.
P280 Wear protective gloves.

Response:
P302 + P352 IF ON SKIN: Wash with plenty of soap and water.
P333 + P313 If skin irritation or rash occurs: Get medical advice/ attention.
P363 Wash contaminated clothing before reuse.

Disposal:
P501 Dispose of contents/ container to an approved waste disposal plant.

MOLYKOTE(R) 55 O-RING GREASE

Version 1.6 Revision Date: 02/12/2016 SDS Number: 623335-00007 Date of last issue: 09/24/2015
Date of first issue: 10/09/2014

Other hazards

None known.

SECTION 3. COMPOSITION/INFORMATION ON INGREDIENTS

Substance / Mixture : Mixture
Chemical nature : Silicone grease

Hazardous ingredients

Chemical name	CAS-No.	Concentration (% w/w)
Lithium stearate	4485-12-5	≥ 20 - < 30
Dihydro-3-(tetrapropenyl)furan-2,5-dione	26544-38-7	≥ 0.1 - < 1

SECTION 4. FIRST AID MEASURES

General advice : In the case of accident or if you feel unwell, seek medical advice immediately.
When symptoms persist or in all cases of doubt seek medical advice.

If inhaled : If inhaled, remove to fresh air.
Get medical attention if symptoms occur.

In case of skin contact : In case of contact, immediately flush skin with soap and plenty of water.
Remove contaminated clothing and shoes.
Get medical attention.
Wash clothing before reuse.
Thoroughly clean shoes before reuse.

In case of eye contact : Flush eyes with water as a precaution.
Get medical attention if irritation develops and persists.

If swallowed : If swallowed, DO NOT induce vomiting.
Get medical attention if symptoms occur.
Rinse mouth thoroughly with water.

Most important symptoms and effects, both acute and delayed : May cause an allergic skin reaction.

Protection of first-aiders : First Aid responders should pay attention to self-protection, and use the recommended personal protective equipment when the potential for exposure exists.

Notes to physician : Treat symptomatically and supportively.

SECTION 5. FIRE-FIGHTING MEASURES

Suitable extinguishing media : Water spray

MOLYKOTE(R) 55 O-RING GREASE

Version 1.6	Revision Date: 02/12/2016	SDS Number: 623335-00007	Date of last issue: 09/24/2015 Date of first issue: 10/09/2014
----------------	------------------------------	-----------------------------	---

Alcohol-resistant foam
Carbon dioxide (CO₂)
Dry chemical

- | | |
|--|---|
| Unsuitable extinguishing media | : None known. |
| Specific hazards during fire fighting | : Exposure to combustion products may be a hazard to health. |
| Hazardous combustion products | : Carbon oxides
Silicon oxides
Formaldehyde
Metal oxides |
| Specific extinguishing methods | : Use extinguishing measures that are appropriate to local circumstances and the surrounding environment.
Use water spray to cool unopened containers.
Remove undamaged containers from fire area if it is safe to do so.
Evacuate area. |
| Special protective equipment for fire-fighters | : In the event of fire, wear self-contained breathing apparatus.
Use personal protective equipment. |

SECTION 6. ACCIDENTAL RELEASE MEASURES

- | | |
|---|---|
| Personal precautions, protective equipment and emergency procedures | : Use personal protective equipment.
Follow safe handling advice and personal protective equipment recommendations. |
| Environmental precautions | : Discharge into the environment must be avoided.
Prevent further leakage or spillage if safe to do so.
Retain and dispose of contaminated wash water.
Local authorities should be advised if significant spillages cannot be contained. |
| Methods and materials for containment and cleaning up | : Soak up with inert absorbent material.
For large spills, provide diking or other appropriate containment to keep material from spreading. If diked material can be pumped, store recovered material in appropriate container.
Clean up remaining materials from spill with suitable absorbent.
Local or national regulations may apply to releases and disposal of this material, as well as those materials and items employed in the cleanup of releases. You will need to determine which regulations are applicable.
Sections 13 and 15 of this SDS provide information regarding certain local or national requirements. |

SECTION 7. HANDLING AND STORAGE

- | | |
|--------------------|---|
| Technical measures | : See Engineering measures under EXPOSURE |
|--------------------|---|

MOLYKOTE(R) 55 O-RING GREASE

Version 1.6 Revision Date: 02/12/2016 SDS Number: 623335-00007 Date of last issue: 09/24/2015
Date of first issue: 10/09/2014

CONTROLS/PERSONAL PROTECTION section.

- Local/Total ventilation : Use only with adequate ventilation.
- Advice on safe handling : Do not get on skin or clothing.
Do not swallow.
Avoid contact with eyes.
Handle in accordance with good industrial hygiene and safety practice.
Take care to prevent spills, waste and minimize release to the environment.
- Conditions for safe storage : Keep in properly labeled containers.
Store in accordance with the particular national regulations.
- Materials to avoid : Do not store with the following product types:
Strong oxidizing agents

SECTION 8. EXPOSURE CONTROLS/PERSONAL PROTECTION

Ingredients with workplace control parameters

Ingredients	CAS-No.	Value type (Form of exposure)	Control parameters / Permissible concentration	Basis
Lithium stearate	4485-12-5	TWA	10 mg/m3	ACGIH

Hazardous components without workplace control parameters

Ingredients	CAS-No.
Dihydro-3-(tetrapropenyl)furan-2,5-dione	26544-38-7

- Engineering measures : Processing may form hazardous compounds (see section 10).
Ensure adequate ventilation, especially in confined areas.
Minimize workplace exposure concentrations.

Personal protective equipment

- Respiratory protection : General and local exhaust ventilation is recommended to maintain vapor exposures below recommended limits. Where concentrations are above recommended limits or are unknown, appropriate respiratory protection should be worn. Follow OSHA respirator regulations (29 CFR 1910.134) and use NIOSH/MSHA approved respirators. Protection provided by air purifying respirators against exposure to any hazardous chemical is limited. Use a positive pressure air supplied respirator if there is any potential for uncontrolled release, exposure levels are unknown, or any other circumstance where air purifying respirators may not provide adequate protection.

- Hand protection
Material : Impervious gloves

MOLYKOTE(R) 55 O-RING GREASE

Version 1.6	Revision Date: 02/12/2016	SDS Number: 623335-00007	Date of last issue: 09/24/2015 Date of first issue: 10/09/2014
----------------	------------------------------	-----------------------------	---

- | | |
|--------------------------|---|
| Remarks | : Choose gloves to protect hands against chemicals depending on the concentration specific to place of work. Breakthrough time is not determined for the product. Change gloves often! For special applications, we recommend clarifying the resistance to chemicals of the aforementioned protective gloves with the glove manufacturer. Wash hands before breaks and at the end of workday. |
| Eye protection | : Wear the following personal protective equipment:
Safety glasses |
| Skin and body protection | : Select appropriate protective clothing based on chemical resistance data and an assessment of the local exposure potential.
Skin contact must be avoided by using impervious protective clothing (gloves, aprons, boots, etc). |
| Hygiene measures | : Ensure that eye flushing systems and safety showers are located close to the working place.
When using do not eat, drink or smoke.
Wash contaminated clothing before re-use.
These precautions are for room temperature handling. Use at elevated temperature or aerosol/spray applications may require added precautions. |

SECTION 9. PHYSICAL AND CHEMICAL PROPERTIES

- | | |
|---|---|
| Appearance | : Grease |
| Color | : white |
| Odor | : slight |
| Odor Threshold | : No data available |
| pH | : Not applicable |
| Melting point/freezing point | : No data available |
| Initial boiling point and boiling range | : Not applicable |
| Flash point | : > 101.1 °C
Method: closed cup |
| Evaporation rate | : Not applicable |
| Flammability (solid, gas) | : Not classified as a flammability hazard |
| Upper explosion limit | : No data available |
| Lower explosion limit | : No data available |

MOLYKOTE(R) 55 O-RING GREASE

Version 1.6	Revision Date: 02/12/2016	SDS Number: 623335-00007	Date of last issue: 09/24/2015 Date of first issue: 10/09/2014
----------------	------------------------------	-----------------------------	---

Vapor pressure	: Not applicable
Relative vapor density	: No data available
Relative density	: 1.1
Solubility(ies) Water solubility	: No data available
Partition coefficient: n-octanol/water	: No data available
Autoignition temperature	: No data available
Decomposition temperature	: No data available
Viscosity Viscosity, dynamic	: Not applicable
Explosive properties	: Not explosive
Oxidizing properties	: The substance or mixture is not classified as oxidizing.
Molecular weight	: No data available

SECTION 10. STABILITY AND REACTIVITY

Reactivity	: Not classified as a reactivity hazard.
Chemical stability	: Stable under normal conditions.
Possibility of hazardous reactions	: Use at elevated temperatures may form highly hazardous compounds. Can react with strong oxidizing agents. Hazardous decomposition products will be formed at elevated temperatures.
Conditions to avoid	: None known.
Incompatible materials	: Oxidizing agents
Hazardous decomposition products Thermal decomposition	: Benzene Formaldehyde

SECTION 11. TOXICOLOGICAL INFORMATION**Information on likely routes of exposure**

Skin contact
Ingestion
Eye contact

Acute toxicity

MOLYKOTE(R) 55 O-RING GREASE

Version	Revision Date:	SDS Number:	Date of last issue: 09/24/2015
1.6	02/12/2016	623335-00007	Date of first issue: 10/09/2014

Not classified based on available information.

Ingredients:**Lithium stearate:**

Acute oral toxicity : LD50 (Rat): > 5,000 mg/kg

Acute dermal toxicity : LD50 (Rat): > 2,000 mg/kg
Method: OECD Test Guideline 402
Assessment: The substance or mixture has no acute dermal toxicity
Remarks: Based on data from similar materials

Dihydro-3-(tetrapropenyl)furan-2,5-dione:

Acute oral toxicity : LD50 (Rat): 2,900 mg/kg

Acute inhalation toxicity : Acute toxicity estimate: 5.5 mg/l
Exposure time: 4 h
Test atmosphere: dust/mist
Method: Expert judgment

Skin corrosion/irritation

Not classified based on available information.

Product:

Species: Rabbit
Result: No skin irritation
Remarks: Based on test data

Ingredients:**Lithium stearate:**

Species: Rabbit
Result: No skin irritation
Remarks: Based on data from similar materials

Dihydro-3-(tetrapropenyl)furan-2,5-dione:

Species: Rabbit
Result: No skin irritation

Serious eye damage/eye irritation

Not classified based on available information.

Ingredients:**Lithium stearate:**

Species: Rabbit
Result: No eye irritation
Method: OECD Test Guideline 405
Remarks: Based on data from similar materials

Dihydro-3-(tetrapropenyl)furan-2,5-dione:

Species: Rabbit
Result: Irritation to eyes, reversing within 21 days

MOLYKOTE(R) 55 O-RING GREASE

Version	Revision Date:	SDS Number:	Date of last issue: 09/24/2015
1.6	02/12/2016	623335-00007	Date of first issue: 10/09/2014

Respiratory or skin sensitization

Skin sensitization: May cause an allergic skin reaction.

Respiratory sensitization: Not classified based on available information.

Ingredients:**Lithium stearate:**

Test Type: Local lymph node assay (LLNA)

Routes of exposure: Skin contact

Species: Mouse

Method: OECD Test Guideline 429

Result: negative

Dihydro-3-(tetrapropenyl)furan-2,5-dione:

Test Type: Maximization Test

Routes of exposure: Skin contact

Species: Guinea pig

Result: positive

Remarks: Based on data from similar materials

Assessment: Probability or evidence of high skin sensitization rate in humans

Germ cell mutagenicity

Not classified based on available information.

Ingredients:**Lithium stearate:**

Genotoxicity in vitro

: Test Type: Bacterial reverse mutation assay (AMES)

Method: OECD Test Guideline 471

Result: negative

Remarks: Based on data from similar materials

Dihydro-3-(tetrapropenyl)furan-2,5-dione:

Genotoxicity in vitro

: Test Type: Bacterial reverse mutation assay (AMES)

Method: OECD Test Guideline 471

Result: negative

Remarks: Based on data from similar materials

Carcinogenicity

Not classified based on available information.

Ingredients:**Lithium stearate:**

Species: Mouse

Application Route: Skin contact

Exposure time: 104 weeks

Result: negative

Remarks: Based on data from similar materials

IARC

No ingredient of this product present at levels greater than or equal to 0.1% is identified as probable, possible or confirmed human carcinogen by IARC.

OSHA

No ingredient of this product present at levels greater than or equal to 0.1% is identified as a carcinogen or potential carcino-

MOLYKOTE(R) 55 O-RING GREASE

Version	Revision Date:	SDS Number:	Date of last issue: 09/24/2015
1.6	02/12/2016	623335-00007	Date of first issue: 10/09/2014

gen by OSHA.

NTP

No ingredient of this product present at levels greater than or equal to 0.1% is identified as a known or anticipated carcinogen by NTP.

Reproductive toxicity

Not classified based on available information.

Ingredients:**Lithium stearate:**

Effects on fertility

: Test Type: Combined repeated dose toxicity study with the reproduction/developmental toxicity screening test
Species: Rat
Application Route: Skin contact
Result: negative
Remarks: Based on data from similar materials

Effects on fetal development

: Test Type: Combined repeated dose toxicity study with the reproduction/developmental toxicity screening test
Species: Rat
Application Route: Skin contact
Result: negative
Remarks: Based on data from similar materials

Dihydro-3-(tetrapropenyl)furan-2,5-dione:

Effects on fertility

: Test Type: Two-generation reproduction toxicity study
Species: Rat
Application Route: Ingestion
Result: negative
Remarks: Based on data from similar materials

Effects on fetal development

: Test Type: Reproduction/Developmental toxicity screening test
Species: Rat
Application Route: Ingestion
Result: negative
Remarks: Based on data from similar materials

STOT-single exposure

Not classified based on available information.

STOT-repeated exposure

Not classified based on available information.

Repeated dose toxicity**Ingredients:****Lithium stearate:**

Species: Rat

NOAEL: 88 mg/kg

Application Route: Ingestion

Exposure time: 90 Days

Remarks: Based on data from similar materials

MOLYKOTE(R) 55 O-RING GREASE

Version	Revision Date:	SDS Number:	Date of last issue: 09/24/2015
1.6	02/12/2016	623335-00007	Date of first issue: 10/09/2014

Species: Rat
NOAEL: 1,089.75 mg/kg
Application Route: Skin contact
Exposure time: > 43 Days
Remarks: Based on data from similar materials

Dihydro-3-(tetrapropenyl)furan-2,5-dione:

Species: Rat
NOAEL: 50 mg/kg
LOAEL: 150 mg/kg
Application Route: Ingestion
Exposure time: 54 Days
Remarks: Based on data from similar materials

Aspiration toxicity

Not classified based on available information.

SECTION 12. ECOLOGICAL INFORMATION**Ecotoxicity****Ingredients:****Lithium stearate:**

Toxicity to fish	: LL50 (Oncorhynchus mykiss (rainbow trout)): > 100 mg/l Exposure time: 96 h Test substance: Water Accommodated Fraction Method: OECD Test Guideline 203 Remarks: Based on data from similar materials
Toxicity to daphnia and other aquatic invertebrates	: EC50 (Daphnia magna (Water flea)): > 100 mg/l Exposure time: 48 h Test substance: Water Accommodated Fraction Method: OECD Test Guideline 202 Remarks: Based on data from similar materials
Toxicity to algae	: EC50 (Pseudokirchneriella subcapitata (green algae)): > 100 mg/l Exposure time: 72 h Test substance: Water Accommodated Fraction Method: OECD Test Guideline 201 Remarks: Based on data from similar materials
Toxicity to bacteria	: NOEC: 13 mg/l Exposure time: 28 d Remarks: Based on data from similar materials

Dihydro-3-(tetrapropenyl)furan-2,5-dione:

Toxicity to fish	: LC50 (Oncorhynchus mykiss (rainbow trout)): > 100 mg/l Exposure time: 96 h
Toxicity to daphnia and other aquatic invertebrates	: EC0 (Daphnia magna (Water flea)): 100 mg/l Exposure time: 48 h Method: OECD Test Guideline 202

MOLYKOTE(R) 55 O-RING GREASE

Version 1.6	Revision Date: 02/12/2016	SDS Number: 623335-00007	Date of last issue: 09/24/2015 Date of first issue: 10/09/2014
----------------	------------------------------	-----------------------------	---

Remarks: Based on data from similar materials

Toxicity to algae : EC50 (Pseudokirchneriella subcapitata (green algae)): 110 mg/l
Exposure time: 96 h

NOEC (Pseudokirchneriella subcapitata (green algae)): 33 mg/l
Exposure time: 96 h

Toxicity to bacteria : EC50: 800 mg/l
Exposure time: 3 h
Method: OECD Test Guideline 209

Persistence and degradability**Ingredients:****Lithium stearate:**

Biodegradability : Result: Readily biodegradable.
Biodegradation: 78 %
Exposure time: 28 d
Method: OECD Test Guideline 301C
Remarks: Based on data from similar materials

Dihydro-3-(tetrapropenyl)furan-2,5-dione:

Biodegradability : Result: Not readily biodegradable.
Biodegradation: 9.9 %
Exposure time: 28 d
Method: OECD Test Guideline 301D

Bioaccumulative potential**Ingredients:****Lithium stearate:**

Bioaccumulation : Species: Fish
Bioconcentration factor (BCF): 0.12
Remarks: Based on data from similar materials

Dihydro-3-(tetrapropenyl)furan-2,5-dione:

Partition coefficient: n-octanol/water : log Pow: > 4.39

Mobility in soil

No data available

Other adverse effects

No data available

SECTION 13. DISPOSAL CONSIDERATIONS**Disposal methods**

Resource Conservation and : This product has been evaluated for RCRA characteristics

MOLYKOTE(R) 55 O-RING GREASE

Version 1.6	Revision Date: 02/12/2016	SDS Number: 623335-00007	Date of last issue: 09/24/2015 Date of first issue: 10/09/2014
----------------	------------------------------	-----------------------------	---

Recovery Act (RCRA)	and does not meet the criteria of hazardous waste if discarded in its purchased form.
Waste from residues	: Dispose of in accordance with local regulations.
Contaminated packaging	: Empty containers should be taken to an approved waste handling site for recycling or disposal. If not otherwise specified: Dispose of as unused product.

SECTION 14. TRANSPORT INFORMATION**International Regulation****UNRTDG**

Not regulated as a dangerous good

IATA-DGR

Not regulated as a dangerous good

IMDG-Code

Not regulated as a dangerous good

Transport in bulk according to Annex II of MARPOL 73/78 and the IBC Code

Not applicable for product as supplied.

Domestic regulation**49 CFR**

Not regulated as a dangerous good

SECTION 15. REGULATORY INFORMATION**EPCRA - Emergency Planning and Community Right-to-Know****CERCLA Reportable Quantity**

This material does not contain any components with a CERCLA RQ.

SARA 304 Extremely Hazardous Substances Reportable Quantity

This material does not contain any components with a section 304 EHS RQ.

SARA 311/312 Hazards : Acute Health Hazard**SARA 302** : No chemicals in this material are subject to the reporting requirements of SARA Title III, Section 302.**SARA 313** : This material does not contain any chemical components with known CAS numbers that exceed the threshold (De Minimis) reporting levels established by SARA Title III, Section 313.**US State Regulations****Pennsylvania Right To Know**

Dimethyl, phenylmethyl siloxane, trimethyl- 63148-52-7 50 - 70 %

MOLYKOTE(R) 55 O-RING GREASE

Version 1.6	Revision Date: 02/12/2016	SDS Number: 623335-00007	Date of last issue: 09/24/2015 Date of first issue: 10/09/2014
----------------	------------------------------	-----------------------------	---

terminated		
Lithium stearate	4485-12-5	20 - 30 %
Di(2-ethylhexyl) sebacate	122-62-3	10 - 20 %

New Jersey Right To Know

Dimethyl, phenylmethyl siloxane, trimethyl-terminated	63148-52-7	50 - 70 %
Lithium stearate	4485-12-5	20 - 30 %
Di(2-ethylhexyl) sebacate	122-62-3	10 - 20 %

California Prop. 65

This product does not contain any chemicals known to the State of California to cause cancer, birth, or any other reproductive defects.

The ingredients of this product are reported in the following inventories:

NZIoC	: All ingredients listed or exempt.
REACH	: All ingredients (pre-)registered or exempt.
TSCA	: All chemical substances in this material are included on or exempted from listing on the TSCA Inventory of Chemical Substances.
PICCS	: All ingredients listed or exempt.
KECI	: All ingredients listed, exempt or notified.
ENCS/ISHL	: All components are listed on ENCS/ISHL or exempted from inventory listing.
IECSC	: All ingredients listed or exempt.
AICS	: All ingredients listed or exempt.
DSL	: All chemical substances in this product comply with the CEPA 1999 and NSNR and are on or exempt from listing on the Canadian Domestic Substances List (DSL).
TCSI	: All ingredients listed or exempt.


MOLYKOTE(R) 55 O-RING GREASE

Version 1.6 Revision Date: 02/12/2016 SDS Number: 623335-00007 Date of last issue: 09/24/2015
 Date of first issue: 10/09/2014

SECTION 16. OTHER INFORMATION

Further information

NFPA:



HMIS III:

HEALTH	2
FLAMMABILITY	1
PHYSICAL HAZARD	0

0 = not significant, 1 = Slight,
 2 = Moderate, 3 = High
 4 = Extreme, * = Chronic

Full text of other abbreviations

ACGIH : USA. ACGIH Threshold Limit Values (TLV)
 ACGIH / TWA : 8-hour, time-weighted average

AICS - Australian Inventory of Chemical Substances; ASTM - American Society for the Testing of Materials; bw - Body weight; CERCLA - Comprehensive Environmental Response, Compensation, and Liability Act; CMR - Carcinogen, Mutagen or Reproductive Toxicant; DIN - Standard of the German Institute for Standardisation; DOT - Department of Transportation; DSL - Domestic Substances List (Canada); ECx - Concentration associated with x% response; EHS - Extremely Hazardous Substance; ELx - Loading rate associated with x% response; EmS - Emergency Schedule; ENCS - Existing and New Chemical Substances (Japan); ErCx - Concentration associated with x% growth rate response; ERG - Emergency Response Guide; GHS - Globally Harmonized System; GLP - Good Laboratory Practice; HMIS - Hazardous Materials Identification System; IARC - International Agency for Research on Cancer; IATA - International Air Transport Association; IBC - International Code for the Construction and Equipment of Ships carrying Dangerous Chemicals in Bulk; IC50 - Half maximal inhibitory concentration; ICAO - International Civil Aviation Organization; IECSC - Inventory of Existing Chemical Substances in China; IMDG - International Maritime Dangerous Goods; IMO - International Maritime Organization; ISHL - Industrial Safety and Health Law (Japan); ISO - International Organisation for Standardization; KECI - Korea Existing Chemicals Inventory; LC50 - Lethal Concentration to 50 % of a test population; LD50 - Lethal Dose to 50% of a test population (Median Lethal Dose); MARPOL - International Convention for the Prevention of Pollution from Ships; MSHA - Mine Safety and Health Administration; n.o.s. - Not Otherwise Specified; NFPA - National Fire Protection Association; NO(A)EC - No Observed (Adverse) Effect Concentration; NO(A)EL - No Observed (Adverse) Effect Level; NOELR - No Observable Effect Loading Rate; NTP - National Toxicology Program; NZIoC - New Zealand Inventory of Chemicals; OECD - Organization for Economic Co-operation and Development; OPPTS - Office of Chemical Safety and Pollution Prevention; PBT - Persistent, Bioaccumulative and Toxic substance; PICCS - Philippines Inventory of Chemicals and Chemical Substances; (Q)SAR - (Quantitative) Structure Activity Relationship; RCRA - Resource Conservation and Recovery Act; REACH - Regulation (EC) No 1907/2006 of the European Parliament and of the Council concerning the Registration, Evaluation, Authorisation and Restriction of Chemicals; RQ - Reportable Quantity; SADT - Self-Accelerating Decomposition Temperature; SARA - Superfund Amendments and Reauthorization Act; SDS - Safety Data Sheet; TCSI - Taiwan Chemical Sub-

MOLYKOTE(R) 55 O-RING GREASE

Version	Revision Date:	SDS Number:	Date of last issue: 09/24/2015
1.6	02/12/2016	623335-00007	Date of first issue: 10/09/2014

stance Inventory; TSCA - Toxic Substances Control Act (United States); UN - United Nations; UNRTDG - United Nations Recommendations on the Transport of Dangerous Goods; vPvB - Very Persistent and Very Bioaccumulative

Sources of key data used to compile the Material Safety Data Sheet : Internal technical data, data from raw material SDSs, OECD eChem Portal search results and European Chemicals Agency, <http://echa.europa.eu/>

Revision Date : 02/12/2016

Items where changes have been made to the previous version are highlighted in the body of this document by two vertical lines.

The information provided in this Safety Data Sheet is correct to the best of our knowledge, information and belief at the date of its publication. The information is designed only as a guidance for safe handling, use, processing, storage, transportation, disposal and release and shall not be considered a warranty or quality specification of any type. The information provided relates only to the specific material identified at the top of this SDS and may not be valid when the SDS material is used in combination with any other materials or in any process, unless specified in the text. Material users should review the information and recommendations in the specific context of their intended manner of handling, use, processing and storage, including an assessment of the appropriateness of the SDS material in the user's end product, if applicable.

US / Z8