



Material Safety Data Sheet

Copyright, 2009, 3M Company. All rights reserved. Copying and/or downloading of this information for the purpose of properly utilizing 3M products is allowed provided that: (1) the information is copied in full with no changes unless prior written agreement is obtained from 3M, and (2) neither the copy nor the original is resold or otherwise distributed with the intention of earning a profit thereon.

SECTION 1: PRODUCT AND COMPANY IDENTIFICATION

PRODUCT NAME: SCOTCHKOTE BRAND ELECTRICAL COATING

MANUFACTURER: 3M

DIVISION: Electrical Markets Division

ADDRESS: 3M Center
St. Paul, MN 55144-1000

EMERGENCY PHONE: 1-800-364-3577 or (651) 737-6501 (24 hours)

Issue Date: 02/06/2009

Supersedes Date: 02/06/2009

Document Group: 10-2644-2

Product Use:

Intended Use: MOISTURE PROOFING FOR WIRE CONNECTIONS

SECTION 2: INGREDIENTS

<u>Ingredient</u>	<u>C.A.S. No.</u>	<u>% by Wt</u>
ACETONE	67-64-1	40 - 45
METHYL ETHYL KETONE	78-93-3	10 - 15
ACRYLONITRILE-BUTADIENE POLYMER	9003-18-3	10 - 15
TOLUENE	108-88-3	10 - 15
PHENOL-FORMALDEHYDE RESIN	25085-50-1	5 - 10
GLYCEROL ESTERS OF ROSIN ACIDS	8050-31-5	5 - 10
ZINC OXIDE	1314-13-2	1 - 2
SALICYLIC ACID	69-72-7	1 - 2
ANTIOXIDANT	68411-46-1	0.1 - 1

Minute quantities of the substances listed below may be emitted during Normal Use:

Substance
Hydrocarbons

Condition
Normal Use

SECTION 3: HAZARDS IDENTIFICATION

3.1 EMERGENCY OVERVIEW

Odor, Color, Grade: Brown, solvent odor

General Physical Form: Liquid

Immediate health, physical, and environmental hazards: Flammable liquid and vapor. Closed containers exposed to heat from fire may build pressure and explode. Vapors may travel long distances along the ground or floor to an ignition source and flash back. May cause target organ effects. Contains a chemical or chemicals which can cause birth defects or other reproductive harm.

3.2 POTENTIAL HEALTH EFFECTS

Eye Contact:

Moderate Eye Irritation: Signs/symptoms may include redness, swelling, pain, tearing, and blurred or hazy vision.

Skin Contact:

Moderate Skin Irritation: Signs/symptoms may include localized redness, swelling, itching, and dryness.

May be absorbed through skin and cause target organ effects.

Inhalation:

May be harmful if inhaled.

Upper Respiratory Tract Irritation: Signs/symptoms may include cough, sneezing, nasal discharge, headache, hoarseness, and nose and throat pain.

Respiratory Tract Irritation: Signs/symptoms may include cough, sneezing, nasal discharge, headache, hoarseness, and nose and throat pain.

May be absorbed following inhalation and cause target organ effects.

Ingestion:

Gastrointestinal Irritation: Signs/symptoms may include abdominal pain, nausea, diarrhea and vomiting.

Gastrointestinal Irritation: Signs/symptoms may include abdominal pain, stomach upset, nausea, vomiting and diarrhea.

May be absorbed following ingestion and cause target organ effects.

Target Organ Effects:

Central Nervous System (CNS) Depression: Signs/symptoms may include headache, dizziness, drowsiness, incoordination, nausea, slowed reaction time, slurred speech, giddiness, and unconsciousness.

Neurological Effects: Signs/symptoms may include personality changes, lack of coordination, sensory loss, tingling or numbness of the extremities, weakness, tremors, and/or changes in blood pressure and heart rate.

Prolonged or repeated exposure may cause:

Liver Effects: Signs/symptoms may include loss of appetite, weight loss, fatigue, weakness, abdominal tenderness and jaundice.

Central Neuropathy: Signs/symptoms may include irritability, memory impairment, personality changes, sleep disorders, and decreased ability to concentrate.

Neurological Effects: Signs/symptoms may include personality changes, lack of coordination, sensory loss, tingling or numbness of the extremities, weakness and tremors.

Contains a chemical or chemicals which can cause birth defects or other reproductive harm.

SECTION 4: FIRST AID MEASURES

4.1 FIRST AID PROCEDURES

The following first aid recommendations are based on an assumption that appropriate personal and industrial hygiene practices are followed.

Eye Contact: Flush eyes with large amounts of water. If signs/symptoms persist, get medical attention.

Skin Contact: Remove contaminated clothing and shoes. Immediately flush skin with large amounts of water. Get medical attention. Wash contaminated clothing and clean shoes before reuse.

Inhalation: Remove person to fresh air. If signs/symptoms develop, get medical attention.

If Swallowed: Do not induce vomiting. Give victim two glasses of water. Never give anything by mouth to an unconscious person. Get immediate medical attention.

SECTION 5: FIRE FIGHTING MEASURES

5.1 FLAMMABLE PROPERTIES

Autoignition temperature

No Data Available

Flash Point

0.0 °F [*Test Method:* Closed Cup] [*Details:* MITS data]

OSHA Flammability Classification:

Class IB Flammable Liquid

5.2 EXTINGUISHING MEDIA

Use fire extinguishers with class B extinguishing agents (e.g., dry chemical, carbon dioxide).

5.3 PROTECTION OF FIRE FIGHTERS

Special Fire Fighting Procedures: Water may not effectively extinguish fire; however, it should be used to keep fire-exposed containers and surfaces cool and prevent explosive rupture. Wear full protective equipment (Bunker Gear) and a self-contained breathing apparatus (SCBA).

Unusual Fire and Explosion Hazards: Flammable liquid and vapor. Closed containers exposed to heat from fire may build pressure and explode. Extremely flammable liquid and vapor. Vapors may travel long distances along the ground or floor to an ignition source and flash back.

Note: See STABILITY AND REACTIVITY (SECTION 10) for hazardous combustion and thermal decomposition information.

SECTION 6: ACCIDENTAL RELEASE MEASURES

Accidental Release Measures: Refer to other sections of this MSDS for information regarding physical and health hazards,

respiratory protection, ventilation, and personal protective equipment. Call 3M-HELPS line (1-800-364-3577) for more information on handling and managing the spill. Evacuate unprotected and untrained personnel from hazard area. The spill should be cleaned up by qualified personnel. Remove all ignition sources such as flames, smoking materials, and electrical spark sources. Use only non-sparking tools. Ventilate the area with fresh air. For large spill, or spills in confined spaces, provide mechanical ventilation to disperse or exhaust vapors, in accordance with good industrial hygiene practice. Warning! A motor could be an ignition source and could cause flammable gases or vapors in the spill area to burn or explode. Contain spill. For larger spills, cover drains and build dikes to prevent entry into sewer systems or bodies of water. Cover spill area with a fire-extinguishing foam. An aqueous film forming foam (AFFF) is recommended. Working from around the edges of the spill inward, cover with bentonite, vermiculite, or commercially available inorganic absorbent material. Mix in sufficient absorbent until it appears dry. Remember, adding an absorbent material does not remove a toxic, corrosivity or flammability hazard. Collect as much of the spilled material as possible using non-sparking tools. Clean up residue with an appropriate solvent selected by a qualified and authorized person. Ventilate the area with fresh air. Read and follow safety precautions on the solvent label and MSDS. Collect the resulting residue containing solution. Place in a metal container approved for transportation by appropriate authorities. Seal the container. Dispose of collected material as soon as possible.

In the event of a release of this material, the user should determine if the release qualifies as reportable according to local, state, and federal regulations.

SECTION 7: HANDLING AND STORAGE

7.1 HANDLING

Avoid eye contact. Do not eat, drink or smoke when using this product. Wash exposed areas thoroughly with soap and water. Contents may be under pressure, open carefully. Keep away from heat, sparks, open flame, pilot lights and other sources of ignition. Ground containers securely when transferring contents. Wear low static or properly grounded shoes. Do not pierce or burn container, even after use. No smoking while handling this material. Do not spray near flames or sources of ignition. Avoid breathing of vapors, mists or spray. Avoid prolonged or repeated skin contact. Avoid static discharge. Avoid eye contact with vapors, mists, or spray. Keep out of the reach of children. Be sure that any people in the area follow the precautions. Attach a copy of the precautions to any other container to which this product may be transferred. Avoid prolonged breathing of vapors. Avoid eye and skin contact. Keep container closed when not in use. If work area conditions prevent compliance with any of the above precautions, do not use the product. Keep out of the reach of children. Avoid contact with oxidizing agents.

7.2 STORAGE

Store in a cool place. Store away from acids. Store away from heat. Store out of direct sunlight. Keep container in well-ventilated area. Keep container tightly closed. Store away from oxidizing agents.

SECTION 8: EXPOSURE CONTROLS/PERSONAL PROTECTION

8.1 ENGINEERING CONTROLS

Provide local exhaust ventilation at transfer points. Provide appropriate local exhaust ventilation on open containers. Use general dilution ventilation and/or local exhaust ventilation to control airborne exposures to below Occupational Exposure Limits and/or control mist, vapor, or spray. If ventilation is not adequate, use respiratory protection equipment.

8.2 PERSONAL PROTECTIVE EQUIPMENT (PPE)

8.2.1 Eye/Face Protection

Avoid eye contact with vapors, mists, or spray.

The following eye protection(s) are recommended: Indirect Vented Goggles.

8.2.2 Skin Protection

Avoid skin contact.

Select and use gloves and/or protective clothing to prevent skin contact based on the results of an exposure assessment. Consult with your glove and/or protective clothing manufacturer for selection of appropriate compatible materials.

Gloves made from the following material(s) are recommended: Fluoroelastomer (Viton).

8.2.3 Respiratory Protection

Avoid breathing of vapors, mists or spray.

Select one of the following NIOSH approved respirators based on airborne concentration of contaminants and in accordance with OSHA regulations: Half facepiece or fullface air-purifying respirator with organic vapor cartridges and P95 particulate prefilters. Consult the current 3M Respiratory Selection Guide for additional information or call 1-800-243-4630 for 3M technical assistance.

8.2.4 Prevention of Swallowing

Do not eat, drink or smoke when using this product. Wash exposed areas thoroughly with soap and water.

8.3 EXPOSURE GUIDELINES

<u>Ingredient</u>	<u>Authority</u>	<u>Type</u>	<u>Limit</u>	<u>Additional Information</u>
ACETONE	ACGIH	TWA	500 ppm	Table A4
ACETONE	ACGIH	STEL	750 ppm	Table A4
ACETONE	OSHA	TWA, Vacated	750 ppm	
ACETONE	OSHA	TWA	1000 ppm	Table Z-1
ACETONE	OSHA	STEL, Vacated	1000 ppm	
METHYL ETHYL KETONE	ACGIH	TWA	200 ppm	
METHYL ETHYL KETONE	ACGIH	STEL	300 ppm	
METHYL ETHYL KETONE	OSHA	TWA	200 ppm	Table Z-1A
METHYL ETHYL KETONE	OSHA	STEL	300 ppm	Table Z-1A
TOLUENE	ACGIH	TWA	20 ppm	Table A4
TOLUENE	CMRG	STEL	75 ppm	Skin Notation*
TOLUENE	OSHA	TWA, Vacated	100 ppm	
TOLUENE	OSHA	STEL, Vacated	150 ppm	
TOLUENE	OSHA	TWA	200 ppm	Table Z-2
TOLUENE	OSHA	CEIL	300 ppm	Table Z-2
ZINC OXIDE	ACGIH	TWA, respirable	2 mg/m3	
ZINC OXIDE	ACGIH	STEL	10 mg/m3	
ZINC OXIDE	OSHA	TWA, as fume	5 mg/m3	Table Z-1
ZINC OXIDE	OSHA	TWA, respirable	5 mg/m3	Table Z-1
ZINC OXIDE	OSHA	STEL, Vacated, as fume	10 mg/m3	
ZINC OXIDE	OSHA	TWA, Vacated, as dust	10 mg/m3	
ZINC OXIDE	OSHA	TWA, as total dust	15 mg/m3	Table Z-1

* Substance(s) refer to the potential contribution to the overall exposure by the cutaneous route including mucous membrane and eye, either by airborne or, more particularly, by direct contact with the substance. Vehicles can alter skin absorption.

VAC Vacated PEL: Vacated Permissible Exposure Limits [PEL] are enforced as the OSHA PEL in some states. Check with your local regulatory agency.

SOURCE OF EXPOSURE LIMIT DATA:

ACGIH: American Conference of Governmental Industrial Hygienists

CMRG: Chemical Manufacturer Recommended Guideline

OSHA: Occupational Safety and Health Administration

AIHA: American Industrial Hygiene Association Workplace Environmental Exposure Level (WEEL)

SECTION 9: PHYSICAL AND CHEMICAL PROPERTIES

Odor, Color, Grade:	Brown, solvent odor
General Physical Form:	Liquid
Autoignition temperature	No Data Available
Flash Point	0.0 °F [Test Method: Closed Cup] [Details: MITS data]
Boiling point	>=95 °F [Details: MITS data]
Vapor Pressure	<=27 psia [@ 131.0000000000 °F] [Details: MITS data]
Specific Gravity	0.88 [Details: MITS data]
pH	Not Applicable
Melting point	No Data Available
Evaporation rate	No Data Available
Volatile Organic Compounds	Approximately 2.1 lb/gal [Details: SPECIFIC METHOD: calcd. per 3M]
Percent volatile	30 [Details: CONDITIONS: 75]
VOC Less H2O & Exempt Solvents	Approximately 251 g/l [Details: SPECIFIC METHOD: Calcd. per 3M]
Viscosity	325 centipoise [@ 73.4000000000 °F] [Details: MITS data]

SECTION 10: STABILITY AND REACTIVITY

Stability: Stable.

Materials and Conditions to Avoid: None known

Hazardous Polymerization: Hazardous polymerization will not occur.

Hazardous Decomposition or By-Products

<u>Substance</u>	<u>Condition</u>
Amine Compounds	Not Specified
Carbon monoxide	During Combustion
Carbon dioxide	During Combustion
Oxides of Nitrogen	During Combustion

SECTION 11: TOXICOLOGICAL INFORMATION

Please contact the address listed on the first page of the MSDS for Toxicological Information on this material and/or its components.

SECTION 12: ECOLOGICAL INFORMATION

ECOTOXICOLOGICAL INFORMATION

Not determined.

CHEMICAL FATE INFORMATION

Not determined.

SECTION 13: DISPOSAL CONSIDERATIONS

Waste Disposal Method: Incinerate in a permitted hazardous waste incinerator. As a disposal alternative, dispose of waste product in a permitted hazardous waste facility.

EPA Hazardous Waste Number (RCRA): D001 (Ignitable), D035 (Methyl ethyl ketone)

Since regulations vary, consult applicable regulations or authorities before disposal.

SECTION 14: TRANSPORT INFORMATION

Please contact the emergency numbers listed on the first page of the MSDS for Transportation Information for this material.

SECTION 15: REGULATORY INFORMATION

US FEDERAL REGULATIONS

Contact 3M for more information.

311/312 Hazard Categories:

Fire Hazard - Yes Pressure Hazard - No Reactivity Hazard - No Immediate Hazard - Yes Delayed Hazard - Yes

Section 313 Toxic Chemicals subject to the reporting requirements of that section and 40 CFR part 372 (EPCRA):

<u>Ingredient</u>	<u>C.A.S. No</u>	<u>% by Wt</u>
ZINC OXIDE (ZINC COMPOUNDS)	1314-13-2	1 - 2
TOLUENE	108-88-3	10 - 15
METHYL ETHYL KETONE	78-93-3	10 - 15

STATE REGULATIONS

Contact 3M for more information.

CALIFORNIA PROPOSITION 65

Ingredient
TOLUENE

C.A.S. No.
108-88-3

Classification
*Developmental Toxin

* WARNING: contains a chemical or chemicals which can cause birth defects or other reproductive harm.

CHEMICAL INVENTORIES

The components of this product are in compliance with the chemical notification requirements of TSCA.

All applicable chemical ingredients in this material are listed on the European Inventory of Existing Chemical Substances (EINECS), or are exempt polymers whose monomers are listed on EINECS.

Contact 3M for more information.

Additional Information: All ingredients on TSCA; EINECS; CDSL

INTERNATIONAL REGULATIONS

Contact 3M for more information.

This MSDS has been prepared to meet the U.S. OSHA Hazard Communication Standard, 29 CFR 1910.1200.

SECTION 16: OTHER INFORMATION**NFPA Hazard Classification**

Health: 2 **Flammability:** 3 **Reactivity:** 0 **Special Hazards:** None

National Fire Protection Association (NFPA) hazard ratings are designed for use by emergency response personnel to address the hazards that are presented by short-term, acute exposure to a material under conditions of fire, spill, or similar emergencies. Hazard ratings are primarily based on the inherent physical and toxic properties of the material but also include the toxic properties of combustion or decomposition products that are known to be generated in significant quantities.

Reason for Reissue: The MSDS has been revised because 3M has adopted the 16-section ANSI/ISO format. The potential hazards of the product have not changed. We encourage you to reread the MSDS and review the information.

Revision Changes:

Section 1: Product use information was modified.

Copyright was modified.

Section 3: Potential effects from inhalation information was modified.

Section 3: Potential effects from ingestion information was modified.

Section 3: Other health effects information was modified.

Section 2: Ingredient table was added.

Section 15: EPCRA 313 information was added.

Section 15: EPCRA 313 text was added.

Section 8: Exposure guidelines ingredient information was added.

Section 8: Exposure guidelines legend was added.

Section 8: Exposure guideline note was added.

Section 8: Exposure guidelines data source legend was added.

Section 15: California proposition 65 ingredient information was added.

Section 15: California proposition 65 heading was added.

DISCLAIMER: The information in this Material Safety Data Sheet (MSDS) is believed to be correct as of the date issued. 3M MAKES NO WARRANTIES, EXPRESSED OR IMPLIED, INCLUDING, BUT NOT LIMITED TO, ANY IMPLIED WARRANTY OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE OR COURSE OF PERFORMANCE OR USAGE OF TRADE. User is responsible for determining whether the 3M product is fit for a particular purpose and suitable for user's method of use or application. Given the variety of factors that can affect the use and application of a 3M product, some of which are uniquely within the user's knowledge and control, it is essential that the user evaluate the 3M product to determine whether it is fit for a particular purpose and suitable for user's method of use or application.

3M provides information in electronic form as a service to its customers. Due to the remote possibility that electronic transfer may have resulted in errors, omissions or alterations in this information, 3M makes no representations as to its completeness or accuracy. In addition, information obtained from a database may not be as current as the information in the MSDS available directly from 3M.

3M MSDSs are available at www.3M.com