







NOTES:

1. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS NOTED OTHERWISE, WITH IMPERIAL EQUIVALENTS IN PARENTHESES.
2. MATERIAL – DS30 SYNTECTIC FOAM.
DENSITY – 510 kg./m³.
VOLUME – 7.71 Litres.
3. BREAK ALL CORNERS AND SHARP EDGES.
4. NO POLYURETHANE ELASTOMER SKIN OR PAINT REQUIRED.
5. BASED ON CLIENT'S Drg. No. 1002159 – SHEET 8 OF 10 (DATED 10/24/03).
6. THE MAXIMUM OPERATING DEPTH IS 6000 M.S.W.
7. THE CALCULATED WEIGHT IN AIR IS 3.94 kg.
8. THE CALCULATED NETT BUOYANCY IN SEA-WATER IS 3.96 kg.

DIMENSIONS ON THIS DRAWING WILL BE TO THE FOLLOWING TOLERANCES UNLESS NOTED OTHERWISE		
DIMENSION RANGE	TOLERANCE	
0 – 999 mm.	±0.75 mm.	

REFERENCE DRAWINGS:

SYNTECTIC FOAM ASSEMBLY – C422673.

No.		DATE		REVISION		DRAWN		CHK'D		APPR'D	
01		10/12/03		FIRST ISSUE.							



GROUP LIMITED
STANLEY WAY, STANLEY, SKELMERSDALE,
LANCASHIRE, WN8 8EA, ENGLAND.
U.K. TELEPHONE : 01695 712000
U.K. FACSIMILE : 01695 712111

CLIENT **MONTEREY BAY AQUARIUM RESEARCH INSTITUTE.**
PROJECT **MULTIBEAM A.U.V.**

TITLE **TRANSUDCER BAY
SIDE BUOYANCY MODULES (PORT AND STARBOARD).**

SCALE 1:1.5	DRAWN BY MGR	SHEET SIZE A1	PROJECTION 
PROJECT No. W02377	DRAWING No. C 422680	ISSUE 01	