







NOTES:

1. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS NOTED OTHERWISE, WITH IMPERIAL EQUIVALENTS IN PARENTHESES.
2. MATERIAL – DS30 SYNTECTIC FOAM.
DENSITY – 510 kg/m³.
VOLUME – 15.1 Litres.
3. BREAK ALL CORNERS AND SHARP EDGES.
4. NO POLYURETHANE ELASTOMER SKIN OR PAINT REQUIRED.
5. BASED ON CLIENT'S Drg. No. 1002161 – SHEET 10 OF 10 (DATED 10/24/03).
6. THE MAXIMUM OPERATING DEPTH IS 6000 M.S.W.
7. THE CALCULATED WEIGHT IN AIR IS 7.7 kg.
8. THE CALCULATED NETT BUOYANCY IN SEA-WATER IS 7.8 kg.

DIMENSIONS ON THIS DRAWING WILL BE TO THE FOLLOWING TOLERANCES UNLESS NOTED OTHERWISE		
DIMENSION RANGE	TOLERANCE	
0 – 999 mm.	±0.75 mm.	

REFERENCE DRAWINGS:

SYNTECTIC FOAM ASSEMBLY – C422673.

01		10/12/03	FIRST ISSUE.				
No.	DATE	REVISION		DRAWN	CHK'D	APPR'D	
C R P GROUP LIMITED STANLEY WAY, STANLEY, SKELMERSDALE, LANCASHIRE, WN8 8EA, ENGLAND. U.K. TELEPHONE : 01695 712000 U.K. FACSIMILE : 01695 712111							

CLIENT MONTEREY BAY AQUARIUM RESEARCH INSTITUTE.
PROJECT MULTIBEAM A.U.V.

TITLE M.V.C. BAY
FORWARD UPPER FOAM.

SCALE 1:2	DRAWN BY MGR	SHEET SIZE A1	PROJECTION	ISSUE
PROJECT No. W02377	DRAWING No. C 422682			01