



ITT

Enidine



Wire Rope & HERM Isolators

[Login](#)[New Search](#)[Information/Support](#)

[Select Application](#) [Enter Inputs](#) [Show Solutions](#) [Solutions Details](#)


1 **2** **3** **4**



Solution

	Left Model	Right Model	Stabilizer
Model	WR16-206-06	WR16-206-06	None
Quantity	4	4	N/A
Configuration	45° Comp/Roll	45° Comp/Roll	N/A
Height (in)	3	3	N/A
Width (in)	3.63	3.63	N/A
Length (in)	7	7	N/A
Kv (lb/in) ?	2310	2310	N/A
Ks (lb/in) ?	1010	1010	N/A
Max Deflection (in)	1.8	1.8	N/A
Max Static Load (lb)	435	435	N/A

Files

[Catalog](#)[Catalog](#)[CREATE PDF](#)

Inputs

Configuration	45° Comp/Roll
Total Weight (lb)	800
Left CG	=
Right CG	=
Supported Load Width (in)	21
Supported Load Height (in)	21
Supported Load Length (in)	207
Min Freq. (Hz)	6
Max Freq. (Hz)	16

Performance Output

Fn (Hz)	15.0
Ao (g's)	N/A
Fs (Hz)	N/A
Dyn. Defl. (in)	N/A