

Inverse Operation Behavior

of the BTS6143D and members
of this product family

Automotive Power



Never stop thinking

1 Abstract

Note: The following information is given as a hint for the implementation of the device only and shall not be regarded as a description or warranty of a certain functionality, condition or quality of the device.

This Application Note provides information about the specific behavior of the BTS6143D and its family members for the special operation mode “inverse operation”.

The application note describes first the specific characteristics of the BTS6143D and its family members. It describes the special operation mode “inverse operation”. It outlines the behavior of the BTS6143D diagnosis and power stage and provides background information for the special behavior. Finally this application note provides further information regarding the impact of inverse operation effects and provides hints for possible counter measures on device and system level.

In the following all information is given and explained based on the product BTS6143D. However the outlined information is also valid for all family members which utilize the same features and therefore show the same behavior.

2 Introduction

The BTS6143D is a member of a very scalable and flexible family of high current high side switches. It provides embedded protection functions and diagnosis. The embedded device functionality targets an optimum compromise between application requirements and device capabilities.

2.1 Specific characteristics of the BTS6143D and its family members

The BTS6143D provides current sense functionality. A dedicated pin IS supports the monitoring of the load current whenever the device is commanded ON.

The current sense capability of the BTS6143D and its family members targets the monitoring of the load current across a very wide range. A special functionality has been implemented to extend the load current monitoring capability towards very low load current values. This additional functionality dramatically improves the load current monitoring capability at low load currents. However it can cause some side effects at non-normal operation conditions.

The implemented measure for improved load current monitoring utilizes a special functionality called “Gate-Rück-Regelung” (short GRR) or “Output voltage drop limitation” (short OVDL). The functionality output voltage drop limitation increases significantly the current sense capability and accuracy at low load currents. This is achieved by limiting the voltage drop across the power stage to a defined value of $+V_{ON(NL)}$ at low load currents (for details see also the individual product data sheet). However, OVDL is also root cause for the following explained side effects.

2.2 Inverse operation

The BTS6143D and its family members is used to switch the positive supply rail $+V_S$ of a battery feed to the load. **Figure 1** shows a typical application example.




Figure 1 Typical application example with normal operation conditions

Whenever the device is commanded ON by pulling the pin IN to ground, a positive current $+I_L$ is flowing from the pin VBB through the power stage out of the output pin OUT towards the load R_{Load} . This operation condition is the “normal operation condition” of the device.

Depending on the switched load type and specific application conditions a current flow opposite to the normal operation condition can occur. This condition is called “inverse operation condition”. The characteristic of any inverse operation condition is a positive supply voltage $+V_S$, but a load current $-I_L$ opposite to the normal load current direction. **Figure 2** shows a typical example.




Figure 2 Inverse operation condition example

During inverse operation the current $-I_L$ flows from the pin OUT to the pin VBB.

Inverse operation conditions can occur whenever the voltage at the pin OUT becomes higher than the voltage at the pin VBB. Examples for such conditions are:

- the device drives a load which can also operate as generator. A typical load is a motor load. Due to external conditions the motor is operated for a certain duration as a generator and supplies therefore a voltage higher than the battery voltage
(example1: front windshield wiper in a driving car where the wiper is partly driven by the air flow;
example2: battery voltage drop while secondary driven motor is still rotating due to its inertia)
- the device drives loads that can “store” energy. In such condition the stored energy can be fed back in case the supply voltage drops (example: OUT is buffered with a very high capacitor, V_S drops due to external conditions).

3 Inverse operation behavior

Although inverse operation is a non-normal operation condition it is not critical for the BTS6143D and its family members as long as the applied conditions remain within the maximum ratings (please refer also to the respective data sheet). The main life time relevant parameters during inverse operation condition are

- the maximum inverse current $|-I_L|$,
- the resulting maximum power losses $P_{\text{tot}} = I_L \cdot V_{\text{DS}} = f(I_L)$,
- the resulting junction temperature $T_j = P_{\text{tot}} \cdot R_{\text{th(JA)}}$ and
- the maximum voltages $+V_{\text{BB}}$.

The BTS6143D and its family members offers a very robust device performance in case of inverse operation condition.

3.1 Inverse operation behavior during OFF condition

Whenever the BTS6143D is OFF, an inverse current flow will be supported. Any inverse current will flow from the pin OUT to the pin VBB through the body diode of the DMOS power stage. The inverse current flow ($-I_L$ or $I_{L(\text{inv})}$) will cause a voltage drop $-V_{\text{DS}}$ (also named $-V_{\text{ON}}$, V_{inv} , $-V_{\text{ON(inv)}}$) which depends on the inverse current $I_{L(\text{inv})}$ and the junction temperature T_j . The respective values are outlined in the data sheet (see data sheet parameter e.g. $-V_{\text{ON(inv)}}$).

The diagnosis is disabled. During inverse operation condition no current except a small leakage current in the range of μA will be provided at the diagnosis pin IS.

3.2 Inverse operation behavior during ON condition

Whenever the BTS6143D is ON, an inverse current flow will be supported.

3.2.1 Dynamic inverse currents

Any transient inverse current condition will trigger the "Output voltage drop limitation" functionality. The "Output voltage drop limitation" functionality targets a minimum POSITIVE forward voltage drop of $+V_{\text{ON(NL)}}$ across the DMOS power stage. During inverse current condition this target will not be reached ($-V_{\text{ON(inv)}} < +V_{\text{ON(NL)}}$). Therefore the OVDL will result in an internal switch OFF of the DMOS power stage. The duration for this switch OFF depends on the preceding forward load current condition. The smaller the preceding forward load current condition, the shorter will be the internal switch off time. The maximum internal switch off time especially for preceding high load current conditions will be about the same time as the device switch off time (see data sheet parameter t_{OFF}).

3.2.1.1 Very short inverse pulses

As long as the transient inverse current condition occurs for a sufficient short duration which is much shorter than the internal switch off time (e.g. just a few μs) the voltage drop across the DMOS power stage will remain proportional to the load current. The DMOS power stage provides in such conditions still a sufficient conduction resistance $R_{\text{DS(ON)}} = f(\text{time})$. This sufficient conduction resistance causes a voltage drop of just $-V_{\text{DS(inv)}} = R_{\text{DS(ON)}} \cdot (-I_{L(\text{inv})})$. As soon as the inverse current condition transitions back to the forward condition the forward current will be supported.

The pin IS will provide during such short inverse current condition minimum a leakage current of $I_{\text{IS(LH)}}$ (see data sheet parameter $I_{\text{IS(LH)}}$) and will return to the sense current $I_{\text{IS}} = +I_L / K_{\text{ILIS}}$ considering the current sense settling times.

Figure 3 shows a typical scope screen shot of this situation.




Figure 3 transient inverse current condition for very short duration

Observation: It can be seen, that due to a variation in the supply voltage, an inverse current condition occurred for a certain duration (see CH3, 2nd and 3rd division). The duration was short enough to not cause the device to internally switch OFF. Therefore the output voltage follows the battery voltage before, during and after inverse operation. The sense reports during inverse operation no current and provides during normal forward load current condition a defined ratio of the load current.

3.2.1.2 Transient inverse currents

As soon as the inverse current condition lasts for a duration, where the internal switch OFF is reached, the resulting DMOS power stage voltage will increase from initially $-V_{DS(inv)} = R_{DS(ON)} \cdot (-I_{L(inv)})$ to finally $V_{DS(inv)} = V_{BodyDiode}$. The inverse current flow which flowed initially through the activated DMOS power stage ($R_{DS(ON)}$) will finally flow through the body diode of the DMOS power stage ($-V_{DS(inv)} = f(-I_{L(inv)})$). Such inverse current flow $-I_L$ through the body diode of the DMOS power stage will cause a voltage drop $-V_{DS}$ (also named $-V_{ON}$, V_{inv} , $-V_{ON(inv)}$) which depends on the inverse current $I_{L(inv)}$ and the junction temperature T_j . The respective values are outlined in the data sheet. As soon as the inverse current flows across the body diode of the DMOS a parasitic effect in the DMOS power stage causes a signalling of an “virtual” over temperature event towards the control logic. This “virtual” over-temperature signal causes the power stage to remain switched OFF until the “virtual” over-temperature signal is removed. During such inverse operation condition no current will be provided at the diagnosis pin IS except a small leakage current (see data sheet parameter $I_{IS(LH)}$). It is important to state, that the “virtual” over-temperature event can remain for a certain duration even after the transition from inverse load current back to normal forward mode (see data sheet parameter $t_{d(inv)}$). Only once the “virtual” over-temperature event is cleared, the power stage will switch ON.

The pin IS will provide during inverse current condition minimum a leakage current (see data sheet parameter $I_{IS(LH)}$). Whenever the voltage condition changes from inverse to normal forward mode, the pin IS will report the “virtual” over-temperature event until the “virtual” over-temperature event signal is cleared. Once the signal is cleared the power stage will switch ON and the pin IS will provide a defined sense current $I_{IS} = +I_L / K_{ILIS}$ considering the current sense settling time.

Figure 4 shows a typical scope screen shot of this situation.




Figure 4 transient inverse current condition

Observation: It can be seen, that due to a variation in the supply voltage, an inverse current condition occurred for a certain duration (see CH3, 2nd and 3rd division). Although the inverse load current reduces, it can be observed, that the negative drain source voltage increases its amplitude (see M1, in 2nd division) indicating the internal switch OFF. Once the power stage is internally switched OFF, a voltage drop across the power stage of about 600..700mV can be observed (see M1, in 2nd and 3rd division). As soon as the voltage conditions change from inverse to forward mode, the power stage remains OFF (see M1, in 3rd division). At a certain stage the status pin starts to report a fault condition (see CH4, 5th division). This fault conditions remains set until the “virtual” over-temperature signal is internally cleared (see CH4, 6th division). The clearance of the “virtual” over-temperature signal allows the automatic switch ON of the power stage again (see CH3 and M1, 7th division). As soon as the power stage is sufficiently switched ON and the drain source voltage drops below approximately 1V the sense starts to report the ratio of the load current again.

3.2.2 Permanent inverse currents

Any permanent inverse current condition will trigger the “Output voltage drop limitation” functionality. Therefore the power stage will remain internally switched OFF. The inverse current will flow from the pin OUT to the pin VBB through the body diode of the DMOS power stage. The inverse current flow $-I_L$ will cause a voltage drop $-V_{DS}$ (also named $-V_{ON}$, V_{inv} , $-V_{ON(inv)}$) which depends on the inverse current $I_{L(inv)}$ and the junction temperature T_j . The respective values are outlined in the data sheet (see data sheet parameter $-V_{ON(inv)}$).

The diagnosis is disabled. During inverse operation condition no current except a small leakage current will be provided at the diagnosis pin IS.

Since Infineon offers a wide range of different smart power high side switches there is a big choice for close matching alternatives available. In case further support is needed please contact your nearest Infineon representative or Field Application Engineering for further support.

5 Conclusion

Inverse operation is an exceptional operation condition that has to be covered in some applications. This application note provided further information regarding the effects that can be observed with the high current profet BTS6143D and its family members. Additionally information about counter measures or alternatives have been provided.

For further information you may contact <http://www.infineon.com/>

6 Revision History

Inverse Operation Behavior

Revision History: V1.1, 2008-03-31

Previous Version(s):

V1.0

Page	Subjects (major changes since last revision)
4	OVDL typo corrected
4	header in chapter 3.2.1 renamed from tranient inverse currents to dynamic inverse currents

Edition 2008-03-31

**Published by
Infineon Technologies AG
81726 Munich, Germany**

**© 2008 Infineon Technologies AG
All Rights Reserved.**

LEGAL DISCLAIMER

THE INFORMATION GIVEN IN THIS APPLICATION NOTE IS GIVEN AS A HINT FOR THE IMPLEMENTATION OF THE INFINEON TECHNOLOGIES COMPONENT ONLY AND SHALL NOT BE REGARDED AS ANY DESCRIPTION OR WARRANTY OF A CERTAIN FUNCTIONALITY, CONDITION OR QUALITY OF THE INFINEON TECHNOLOGIES COMPONENT. THE RECIPIENT OF THIS APPLICATION NOTE MUST VERIFY ANY FUNCTION DESCRIBED HEREIN IN THE REAL APPLICATION. INFINEON TECHNOLOGIES HEREBY DISCLAIMS ANY AND ALL WARRANTIES AND LIABILITIES OF ANY KIND (INCLUDING WITHOUT LIMITATION WARRANTIES OF NON-INFRINGEMENT OF INTELLECTUAL PROPERTY RIGHTS OF ANY THIRD PARTY) WITH RESPECT TO ANY AND ALL INFORMATION GIVEN IN THIS APPLICATION NOTE.

Information

For further information on technology, delivery terms and conditions and prices, please contact the nearest Infineon Technologies Office (www.infineon.com).

Warnings

Due to technical requirements, components may contain dangerous substances. For information on the types in question, please contact the nearest Infineon Technologies Office.

Infineon Technologies components may be used in life-support devices or systems only with the express written approval of Infineon Technologies, if a failure of such components can reasonably be expected to cause the failure of that life-support device or system or to affect the safety or effectiveness of that device or system. Life support devices or systems are intended to be implanted in the human body or to support and/or maintain and sustain and/or protect human life. If they fail, it is reasonable to assume that the health of the user or other persons may be endangered.