

In these environments only the best will do.

SELF-CONTAINED SUBMERSIBLE LED FLASHER

The XMBF-200 is an independently powered, self-contained surface flasher that is fully submersible to 200m. This state of the art flasher is part of the micro beacon line of products and contains the latest technology available. Our super-bright LED provides unparalleled visibility in even the worst conditions. The XMBF-200 is significantly smaller than other flashers meaning easier storage and deployment without any sacrifice in performance or operational visibility.

Key Features

- **Miniaturized design**
- **Microprocessor controlled, ultra-bright LED available in multiple colour options**
- **Long lasting operational life**
- **Multiple activation options: Reed switch, dip switch & solid state tilt switch for "turtling" applications**

The XMBF is designed to meet or exceed your operational requirements for a submersible flasher. Fully backed by a comprehensive warranty and excellent support you can be confident this is a tool you'll come back to time and time again. To arrange a demo or to learn more about our products please contact us at the numbers below.



Xeos Technologies Inc *Data Telemetry Specialists*

Xeos Technologies Inc.
2 Bluewater Road
Bedford, NS, Canada
B4B 1G7

Tel: 902.444.7650
Fax: 902.444.7651
sales@xeostech.com
www.xeostech.com



XMBF-200

XMBF-200

TECHNICAL SPECIFICATIONS*



Above: The XMBF-200 has been specifically designed to deliver operational superiority in virtually all applications. Whether you are looking for a submersed equipment flasher, a general purpose search and rescue tool, or for a specific application the XMBF platform will meet or exceed your expectations.



Its dramatically small size, yet powerful flasher and enhanced operational features, make the XMBF-200 a step ahead of traditional flasher products.

Who are we?

Xeos is a leading technology firm created by visionary engineers with a passion for excellence. Xeos prides itself on a pioneer mentality, always striving to create superior technological solutions to tracking and telemetry problems. For more information on our COTS and custom developments please contact us at the numbers below.

XMBF-200 Specifications

Electrical

Battery Supply:

- 7 x CR123A lithium batteries

Operational

Lifetime:

- 14 days, double burst every 4 seconds while in daylight off (default setting)

ON/OFF Controls:*

- Switch on board (for storage and shipping)
- Reed Switch for activating without opening the case.
- Solid State tilt switch- for upright activation and deactivation

** All options are switchable on the PCB*

Flash Options

- 1, 2 or 3 flashes
- 10 optional timer settings (1 - 30 seconds)

LED Technology

LED

- 3.9 watts, single emitter type

Luminous Flux

- Amber - 100 lumens (100 lm)
- White - 70 lumens (70 lm)

Mechanical

Dimensions:

- 37 cm L x 2.6 cm W (14.57" L x 1.05" W)

Weight:

- 252g - in water
- 397g - out of water

Material:

- Aluminum 6061

Paint:

- Marine Grade Powdercoat

End Cap:

- Screw-off, O-Ring Sealed

Lens:

- Polycarbonate

Environmental

Operating

Temperature:

- - 40°C to + 60°C

Depth Rating:

- Submersible to 656ft (200m)

