

# ICEqube

Cooling Solutions



# Qube Series

Vertical Mount Air Conditioners  
2,200 BTUH

Standard Features  
Options  
Technical Data  
Air Flow

The worlds smallest compressor based air conditioner! This unit can be used in multiples to provide precise BTU control, and produce 2200 BTUH depending on environmental conditions.



## Standard Features

- Digital temperature controller with alarm.
- Built-in condensate evaporator.
- Durable welded steel construction.
- Efficient, quiet, long lasting rotary compressor.
- Environment friendly HFC refrigerant.
- Easy pull-out filter.
- Right side heat discharge.
- Space saving aesthetic cabinet design.
- Designed to mount on side of enclosure while maintaining NEMA type 12, 3R, 4, or 4X integrity.



## Options & Accessories



- Stainless Steel
- Remote Controller Kit
- Replacement Filters
- Corrosive Packages
- Crankcase Heater

## Technical Data

2,200 BTUH

| Model    | UL Listed | BTU/Watts | Volts  | Max Amps | Max Temp °F/°C | Weight (lbs/Kg) | Dimensions (In/mm)                                   |
|----------|-----------|-----------|--------|----------|----------------|-----------------|------------------------------------------------------|
| IQ2200MM | Yes       | 2200/645  | 120/60 | 6.0      | 131/55c        | 32 / 14.5       | H 22.42" (159mm) x W 6.07" (154mm) x D 6.02" (153mm) |
| IQ2200MM | Yes       | 2200/645  | 230/60 | 3.5      | 131/55c        | 32 / 14.5       | H 22.42" (159mm) x W 6.07" (154mm) x D 6.02" (153mm) |
| IQ2200MM | No        | 2200/645  | 48VDC  | 9.0      | 131/55c        | 22 / 14.5       | H 22.42" (159mm) x W 6.07" (154mm) x D 6.02" (153mm) |

IQ2200MM Capacity Chart



Conditioned Enclosure Air Flow

Ambient Air Flow