

XMI Quickstart Guide



Read this entire document before taking any action

Before using the XMI

- Ensure the IMEI of your device is activated through your chosen Iridium provider and intended message recipients are added to its account ahead of deployment.

Power-Up

Battery Installation

The XMI automatically turns on once all batteries are installed and the endcap connected. The device must be turned off via magnet or battery removal.

Magnet

- Swipe the magnet **slowly** along the **top of the head** horizontally until the flashing **GREEN LED** (**CYAN** with XMI-2.0) on the top of the device remains solid. This LED will flash again while the device completes power-up.

Confirm Transmission

- Turn the device on and place it outside in view of as much of the sky as possible.
- The unit will transmit a power-up message, and transmit one GPS fix every 10 minutes at default settings within 5 minutes of power-up for one hour.
- Confirm that these messages are being received by your email and/or XeosOnline.

Operation

- When deploying the unit, power it up by swiping the magnet.
- Once the unit is confirmed to be on, it is ready to be deployed.
- Turn the XMI **OFF** using the same magnet method as turning **ON**, with the **RED LED** in place of the green.

