



SAFETY DATA SHEET

DDP SPECIALTY ELECTRONIC MATERIALS US 9, LLC

Product name: MOLYKOTE® 55 O-Ring Grease

Issue Date: 08/13/2024

Print Date: 11/06/2024

DDP SPECIALTY ELECTRONIC MATERIALS US 9, LLC encourages and expects you to read and understand the entire (M)SDS, as there is important information throughout the document. We expect you to follow the precautions identified in this document unless your use conditions would necessitate other appropriate methods or actions.

1. IDENTIFICATION

Product name: MOLYKOTE® 55 O-Ring Grease

Recommended use of the chemical and restrictions on use

Identified uses: Lubricants and lubricant additives

COMPANY IDENTIFICATION

DDP SPECIALTY ELECTRONIC MATERIALS
US 9, LLC
974 Centre Road
Wilmington DE 19805
UNITED STATES

Customer Information Number:

833-338-7668

SDSQuestion-NA@dupont.com

EMERGENCY TELEPHONE NUMBER

24-Hour Emergency Contact: 1-800-424-9300

Local Emergency Contact: 800-424-9300

2. HAZARDS IDENTIFICATION

Hazard classification

GHS classification in accordance with 29 CFR 1910.1200

Skin sensitisation - Category 1

Reproductive toxicity - Category 2

Label elements

Hazard pictograms



Signal word: **WARNING!**

Hazards

May cause an allergic skin reaction.

Suspected of damaging fertility or the unborn child.

Precautionary statements**Prevention**

Obtain special instructions before use.

Do not handle until all safety precautions have been read and understood.

Avoid breathing dust.

Contaminated work clothing must not be allowed out of the workplace.

Wear protective gloves/ protective clothing/ eye protection/ face protection.

Response

IF ON SKIN: Wash with plenty of soap and water.

IF exposed or concerned: Get medical advice/ attention.

If skin irritation or rash occurs: Get medical advice/ attention.

Wash contaminated clothing before reuse.

Storage

Store locked up.

Disposal

Dispose of contents/ container to an approved waste disposal plant.

Other hazards

No data available

3. COMPOSITION/INFORMATION ON INGREDIENTS

Chemical nature: Silicone grease.

This product is a mixture.

Component	CASRN	Concentration
Lithium stearate	4485-12-5	>= 20.0 - < 30.0 %
Octamethyl Cyclotetrasiloxane	556-67-2	>= 0.1 - < 1.0 %
2,5-Furandione, dihydro-3-(tetrapropenyl)-	26544-38-7	>= 0.1 - < 1.0 %

4. FIRST AID MEASURES

Description of first aid measures**General advice:**

First Aid responders should pay attention to self-protection and use the recommended protective clothing (chemical resistant gloves, splash protection). If potential for exposure exists refer to Section 8 for specific personal protective equipment.

Inhalation: Move person to fresh air; if effects occur, consult a physician.

Skin contact: Remove material from skin immediately by washing with soap and plenty of water. Remove contaminated clothing and shoes while washing. Seek medical attention if irritation persists. Wash clothing before reuse. Discard items which cannot be decontaminated, including leather articles such as shoes, belts and watchbands. Suitable emergency safety shower facility should be available in work area.

Eye contact: Flush eyes thoroughly with water for several minutes. Remove contact lenses after the initial 1-2 minutes and continue flushing for several additional minutes. If effects occur, consult a physician, preferably an ophthalmologist.

Ingestion: No emergency medical treatment necessary.

Most important symptoms and effects, both acute and delayed:

Aside from the information found under Description of first aid measures (above) and Indication of immediate medical attention and special treatment needed (below), any additional important symptoms and effects are described in Section 11: Toxicology Information.

Indication of any immediate medical attention and special treatment needed

Notes to physician: No specific antidote. Treatment of exposure should be directed at the control of symptoms and the clinical condition of the patient.

5. FIREFIGHTING MEASURES

Suitable extinguishing media: Water spray Alcohol-resistant foam Carbon dioxide (CO₂) Dry chemical

Unsuitable extinguishing media: None known.

Special hazards arising from the substance or mixture

Hazardous combustion products: Silicon oxides Carbon oxides

Unusual Fire and Explosion Hazards: Exposure to combustion products may be a hazard to health.

Advice for firefighters

Fire Fighting Procedures: Fire residues and contaminated fire extinguishing water must be disposed of in accordance with local regulations.

Use extinguishing measures that are appropriate to local circumstances and the surrounding environment. Use water spray to cool unopened containers. Collect contaminated fire extinguishing water separately. This must not be discharged into drains. Remove undamaged containers from fire area if it is safe to do so. Evacuate area.

Special protective equipment for firefighters: In the event of fire, wear self-contained breathing apparatus. Use personal protective equipment.

6. ACCIDENTAL RELEASE MEASURES

Personal precautions, protective equipment and emergency procedures: Use personal protective equipment. Follow safe handling advice and personal protective equipment recommendations.

Environmental precautions: Discharge into the environment must be avoided. Prevent further leakage or spillage if safe to do so. Retain and dispose of contaminated wash water. Local authorities should be advised if significant spillages cannot be contained.

Methods and materials for containment and cleaning up: Wipe up or scrape up and contain for salvage or disposal. Local or national regulations may apply to releases and disposal of this material, as well as those materials and items employed in the cleanup of releases. You will need to determine which regulations are applicable. For large spills, provide dyking or other appropriate containment to keep material from spreading. If dyked material can be pumped, Sections 13 and 15 of this SDS provide information regarding certain local or national requirements.
See sections: 7, 8, 11, 12 and 13.

7. HANDLING AND STORAGE

Precautions for safe handling: Do not get on skin or clothing. Do not swallow. Avoid contact with eyes. Take care to prevent spills, waste and minimize release to the environment. Handle in accordance with good industrial hygiene and safety practice.
Use only with adequate ventilation. See Engineering measures under EXPOSURE CONTROLS/PERSONAL PROTECTION section.

Advice on general occupational hygiene

Use good personal hygiene. Do not consume or store food in the work area. Wash hands before smoking or eating. Ensure that eye flushing systems and safety showers are located close to the working place.

Conditions for safe storage: Keep in properly labelled containers. Store in accordance with the particular national regulations.

Do not store with the following product types: Strong oxidizing agents.
Unsuitable materials for containers: None known.

8. EXPOSURE CONTROLS/PERSONAL PROTECTION

Control parameters

If exposure limits exist, they are listed below. If no exposure limits are displayed, then no values are applicable.

Component	Regulation	Type of listing	Value
Lithium stearate	CAL PEL	PEL	10 mg/m3
	ACGIH	TWA Inhalable particulate matter	10 mg/m3
	Further information: A4: Not classifiable as a human carcinogen		
	ACGIH	TWA Respirable particulate matter	3 mg/m3
	Further information: A4: Not classifiable as a human carcinogen		
Octamethyl Cyclotetrasiloxane	US WEEL	TWA	10 ppm

Exposure controls

Engineering measures: Use engineering controls to maintain airborne level below exposure limit requirements or guidelines. If there are no applicable exposure limit requirements or guidelines, use only with adequate ventilation. Local exhaust ventilation may be necessary for some operations.

Hygiene measures: Use good personal hygiene. Do not consume or store food in the work area. Wash hands before smoking or eating. Ensure that eye flushing systems and safety showers are located close to the working place.

Individual protection measures

Eye/face protection: Use safety glasses (with side shields).

Skin protection

Hand protection: Use gloves chemically resistant to this material. NOTICE: The selection of a specific glove for a particular application and duration of use in a workplace should also take into account all relevant workplace factors such as, but not limited to: Other chemicals which may be handled, physical requirements (cut/puncture protection, dexterity, thermal protection), potential body reactions to glove materials, as well as the instructions/specifications provided by the glove supplier.

Other protection: Use protective clothing chemically resistant to this material. Selection of specific items such as face shield, boots, apron, or full body suit will depend on the task.

Respiratory protection: Respiratory protection should be worn when there is a potential to exceed the exposure limit requirements or guidelines. If there are no applicable exposure limit requirements or guidelines, wear respiratory protection when adverse effects, such as respiratory irritation or discomfort have been experienced, or where indicated by your risk assessment process. For most conditions no respiratory protection should be needed; however, if discomfort is experienced, use an approved air-purifying respirator.

9. PHYSICAL AND CHEMICAL PROPERTIES

Appearance

Physical state	Grease
Color	white
Odor	slight
Odor Threshold	No data available
pH	Not applicable
Melting point/ range	No data available
Freezing point	No data available
Boiling point (760 mmHg)	Not applicable
Flash point	closed cup >101.1 °C (214.0 °F)
Evaporation Rate (Butyl Acetate = 1)	Not applicable
Flammability (solid, gas)	Not classified as a flammability hazard
Lower explosion limit	No data available
Upper explosion limit	No data available
Vapor Pressure	Not applicable
Relative Vapor Density (air = 1)	No data available
Relative Density (water = 1)	1.1
Water solubility	No data available

Partition coefficient: n-octanol/water	No data available
Auto-ignition temperature	No data available
Decomposition temperature	No data available
Dynamic Viscosity	Not applicable
Kinematic Viscosity	Not applicable
Explosive properties	Not explosive
Oxidizing properties	The substance or mixture is not classified as oxidizing.
Liquid Density	1.1 g/cm ³
Molecular weight	No data available
Particle size	No data available

NOTE: The physical data presented above are typical values and should not be construed as a specification.

10. STABILITY AND REACTIVITY

Reactivity: Not classified as a reactivity hazard.

Chemical stability: Stable under normal conditions.

Possibility of hazardous reactions: Can react with strong oxidizing agents.

Conditions to avoid: None known.

Incompatible materials: Oxidizing agents

Hazardous decomposition products: Benzene.

11. TOXICOLOGICAL INFORMATION

Toxicological information appears in this section when such data is available.

Acute toxicity

Acute oral toxicity

Product test data not available. Refer to component data.

Acute dermal toxicity

Product test data not available. Refer to component data.

Acute inhalation toxicity

Product test data not available. Refer to component data.

Skin corrosion/irritation

Product test data not available. Refer to component data.

Serious eye damage/eye irritation

Product test data not available. Refer to component data.

Sensitization

Product test data not available. Refer to component data.

Specific Target Organ Systemic Toxicity (Single Exposure)

Product test data not available. Refer to component data.

Specific Target Organ Systemic Toxicity (Repeated Exposure)

Product test data not available. Refer to component data.

Carcinogenicity

Product test data not available. Refer to component data.

Teratogenicity

Product test data not available. Refer to component data.

Reproductive toxicity

Product test data not available. Refer to component data.

Mutagenicity

Product test data not available. Refer to component data.

Aspiration Hazard

Product test data not available. Refer to component data.

COMPONENTS INFLUENCING TOXICOLOGY:

Lithium stearate

Acute oral toxicity

For similar material(s): LD50, Rat, > 5,000 mg/kg

Acute dermal toxicity

Based on data from similar materials LD50, Rat, > 2,000 mg/kg OECD Test Guideline 402

Acute inhalation toxicity

The LC50 has not been determined.

Skin corrosion/irritation

Brief contact is essentially nonirritating to skin.

Serious eye damage/eye irritation

May cause slight eye irritation.

Corneal injury is unlikely.

Sensitization

For skin sensitization:

For similar material(s):

Did not demonstrate the potential for contact allergy in mice.

For respiratory sensitization:
No relevant data found.

Specific Target Organ Systemic Toxicity (Single Exposure)

Evaluation of available data suggests that this material is not an STOT-SE toxicant.

Specific Target Organ Systemic Toxicity (Repeated Exposure)

For similar material(s):
Based on available data, repeated exposures are not anticipated to cause significant adverse effects.

Carcinogenicity

No relevant data found.

Teratogenicity

No relevant data found.

Reproductive toxicity

No relevant data found.

Mutagenicity

For similar material(s): In vitro genetic toxicity studies were negative.

Aspiration Hazard

Based on physical properties, not likely to be an aspiration hazard.

Octamethyl Cyclotetrasiloxane**Acute oral toxicity**

LD50, Rat, > 4,800 mg/kg OECD Test Guideline 401

Acute dermal toxicity

LD50, Rabbit, > 2,375 mg/kg OECD Test Guideline 402

Acute inhalation toxicity

LC50, Rat, 4 Hour, dust/mist, 36 mg/l

Skin corrosion/irritation

Brief contact is essentially nonirritating to skin.

Serious eye damage/eye irritation

May cause slight temporary eye irritation.

Sensitization

Did not cause allergic skin reactions when tested in guinea pigs.

Specific Target Organ Systemic Toxicity (Single Exposure)

The substance or mixture is not classified as specific target organ toxicant, single exposure.

Specific Target Organ Systemic Toxicity (Repeated Exposure)

Based on available data, repeated exposures are not anticipated to cause additional significant adverse effects.

Carcinogenicity

Animal testing did not show any carcinogenic effects.

Teratogenicity

Did not cause birth defects in laboratory animals.

Reproductive toxicity

In animal studies, has been shown to interfere with fertility.

Mutagenicity

In vitro genetic toxicity studies were negative. Animal genetic toxicity studies were negative.

Aspiration Hazard

May be harmful if swallowed and enters airways.

2,5-Furandione, dihydro-3-(tetrapropenyl)-

Acute oral toxicity

LD50, Rat, 1,875 mg/kg

Acute dermal toxicity

LD50, Rabbit, 2,006 mg/kg

Acute inhalation toxicity

For similar material(s): LC50, Rat, male and female, 4 Hour, dust/mist, 5.3 mg/l

Skin corrosion/irritation

Prolonged contact may cause slight skin irritation with local redness.

Repeated contact may cause slight skin irritation with local redness.

Serious eye damage/eye irritation

May cause moderate eye irritation.

Corneal injury is unlikely.

Sensitization

For similar material(s):

Has caused allergic skin reactions when tested in guinea pigs.

For respiratory sensitization:

No relevant data found.

Specific Target Organ Systemic Toxicity (Single Exposure)

Evaluation of available data suggests that this material is not an STOT-SE toxicant.

Specific Target Organ Systemic Toxicity (Repeated Exposure)

Based on available data, repeated exposures are not anticipated to cause significant adverse effects.

Carcinogenicity

No relevant data found.

Teratogenicity

For similar material(s): Did not cause birth defects or any other fetal effects in laboratory animals.

Reproductive toxicity

For similar material(s): In animal studies, did not interfere with reproduction.

Mutagenicity

For similar material(s): In vitro genetic toxicity studies were negative.

Aspiration Hazard

Based on physical properties, not likely to be an aspiration hazard.

12. ECOLOGICAL INFORMATION

Ecotoxicological information appears in this section when such data is available.

Toxicity**Lithium stearate****Acute toxicity to fish**

Material is practically non-toxic to aquatic organisms on an acute basis (LC50/EC50/EL50/LL50 >100 mg/L in the most sensitive species tested).

Based on data from similar materials

LL50, Oncorhynchus mykiss (rainbow trout), 96 Hour, > 100 mg/l, OECD Test Guideline 203

Acute toxicity to aquatic invertebrates

Based on data from similar materials

EL50, Daphnia magna (Water flea), 48 Hour, > 100 mg/l, OECD Test Guideline 202

Acute toxicity to algae/aquatic plants

Based on data from similar materials

EL50, Pseudokirchneriella subcapitata (green algae), 72 Hour, > 100 mg/l, OECD Test Guideline 201

Toxicity to bacteria

Based on data from similar materials

NOEC, activated sludge, static test, 28 d, 13 mg/l

Octamethyl Cyclotetrasiloxane**Acute toxicity to fish**

Not expected to be acutely toxic to aquatic organisms.

No toxicity at the limit of solubility

LC50, Oncorhynchus mykiss (rainbow trout), 96 Hour, > 0.022 mg/l

Acute toxicity to aquatic invertebrates

No toxicity at the limit of solubility

EC50, Daphnia magna (Water flea), 48 Hour, > 0.015 mg/l

Acute toxicity to algae/aquatic plants

No toxicity at the limit of solubility

EC50, Pseudokirchneriella subcapitata (green algae), 96 Hour, > 0.022 mg/l

EC10, Pseudokirchneriella subcapitata (green algae), 96 Hour, > 0.022 mg/l

Chronic toxicity to fish

No toxicity at the limit of solubility

NOEC, Oncorhynchus mykiss (rainbow trout), 93 d, 0.0044 mg/l

Chronic toxicity to aquatic invertebrates

No toxicity at the limit of solubility

NOEC, Daphnia magna (Water flea), 21 d, 0.015 mg/l

2,5-Furandione, dihydro-3-(tetrapropenyl)-**Acute toxicity to fish**

Material is practically non-toxic to aquatic organisms on an acute basis (LC50/EC50/EL50/LL50 >100 mg/L in the most sensitive species tested).

LC50, Oncorhynchus mykiss (rainbow trout), semi-static test, 96 Hour, > 100 mg/l, OECD Test Guideline 203 or Equivalent

Acute toxicity to aquatic invertebrates

For similar material(s):

EC50, Daphnia dubia (water flea), 48 Hour, > 100 mg/l, OECD Test Guideline 202

Acute toxicity to algae/aquatic plants

EC50, Pseudokirchneriella subcapitata (green algae), static test, 96 Hour, Growth rate, 110 mg/l

Toxicity to bacteria

EC50, activated sludge, static test, 3 Hour, Respiration rates., 800 mg/l, OECD Test Guideline 209

Persistence and degradability**Lithium stearate**

Biodegradability: Material is readily biodegradable. Passes OECD test(s) for ready biodegradability.

Based on data from similar materials 10-day Window: Not applicable

Biodegradation: 78 %

Exposure time: 28 d

Method: OECD Test Guideline 301C

Octamethyl Cyclotetrasiloxane

Biodegradability: Material is not readily biodegradable according to OECD/EEC guidelines.

Biodegradation: 3.7 %

Exposure time: 29 d

Method: OECD Test Guideline 310

Stability in Water (1/2-life)

Hydrolysis, DT50, 69.3 - 144 Hour, pH 7, Half-life Temperature 24.6 °C, OECD Test Guideline 111

Photodegradation

Atmospheric half-life: 16 d

Method: Estimated.

2,5-Furandione, dihydro-3-(tetrapropenyl)-

Biodegradability: Biodegradation under aerobic static laboratory conditions is low (BOD20 or BOD28/ThOD between 2.5 and 10%).

10-day Window: Fail

Biodegradation: 9.9 %
Exposure time: 28 d
Method: OECD Test Guideline 301D

Photodegradation
Sensitization: OH radicals
Atmospheric half-life: 1.7 - 1.9 Hour
Method: Estimated.
Photodegradation
Sensitization: Ozone.
Atmospheric half-life: 1.4 - 2.1 Hour
Method: Estimated.

Bioaccumulative potential

Lithium stearate

Bioaccumulation: Based on data from similar materials No relevant data found.
Bioconcentration factor (BCF): 0.12 Fish

Octamethyl Cyclotetrasiloxane

Bioaccumulation: Bioconcentration potential is high (BCF > 3000 or Log Pow between 5 and 7).
Partition coefficient: n-octanol/water(log Pow): 6.98 at 21.7 °C

2,5-Furandione, dihydro-3-(tetrapropenyl)-

Bioaccumulation: Bioconcentration potential is moderate (BCF between 100 and 3000 or Log Pow between 3 and 5).
Partition coefficient: n-octanol/water(log Pow): > 4.39 OECD Test Guideline 107

Mobility in soil

Lithium stearate

No relevant data found.

Octamethyl Cyclotetrasiloxane

Expected to be relatively immobile in soil (Koc > 5000).

2,5-Furandione, dihydro-3-(tetrapropenyl)-

Potential for mobility in soil is low (Koc between 500 and 2000).
Partition coefficient (Koc): 825 Measured

13. DISPOSAL CONSIDERATIONS

Disposal methods: DO NOT DUMP INTO ANY SEWERS, ON THE GROUND, OR INTO ANY BODY OF WATER. All disposal practices must be in compliance with all Federal, State/Provincial and local laws and regulations. Regulations may vary in different locations. Waste characterizations and compliance with applicable laws are the responsibility solely of the waste generator. AS YOUR SUPPLIER, WE HAVE NO CONTROL OVER THE MANAGEMENT PRACTICES OR MANUFACTURING PROCESSES OF PARTIES HANDLING OR USING THIS MATERIAL. THE INFORMATION PRESENTED HERE PERTAINS ONLY TO THE PRODUCT AS SHIPPED IN ITS

INTENDED CONDITION AS DESCRIBED IN MSDS SECTION: Composition Information. FOR UNUSED & UNCONTAMINATED PRODUCT, the preferred options include sending to a licensed, permitted: Incinerator or other thermal destruction device. For additional information, refer to: Handling & Storage Information, MSDS Section 7 Stability & Reactivity Information, MSDS Section 10 Regulatory Information, MSDS Section 15

Treatment and disposal methods of used packaging: Empty containers should be recycled or otherwise disposed of by an approved waste management facility. Waste characterizations and compliance with applicable laws are the responsibility solely of the waste generator. Do not re-use containers for any purpose.

14. TRANSPORT INFORMATION

DOT

Not regulated for transport

Classification for SEA transport (IMO-IMDG):

Transport in bulk
according to Annex I or II
of MARPOL 73/78 and the
IBC or IGC Code

Not regulated for transport
Consult IMO regulations before transporting ocean bulk

Classification for AIR transport (IATA/ICAO):

Not regulated for transport

This information is not intended to convey all specific regulatory or operational requirements/information relating to this product. Transportation classifications may vary by container volume and may be influenced by regional or country variations in regulations. Additional transportation system information can be obtained through an authorized sales or customer service representative. It is the responsibility of the transporting organization to follow all applicable laws, regulations and rules relating to the transportation of the material.

15. REGULATORY INFORMATION

Superfund Amendments and Reauthorization Act of 1986 Title III (Emergency Planning and Community Right-to-Know Act of 1986) Sections 311 and 312

Respiratory or skin sensitisation
Reproductive toxicity

Superfund Amendments and Reauthorization Act of 1986 Title III (Emergency Planning and Community Right-to-Know Act of 1986) Section 313

This material does not contain any chemical components with known CAS numbers that exceed the threshold (De Minimis) reporting levels established by SARA Title III, Section 313.

California Prop. 65

This product does not contain any chemicals known to State of California to cause cancer, birth defects, or any other reproductive harm.

United States TSCA Inventory (TSCA)

All components of this product are in compliance with the Active inventory listing requirements of the U.S. Toxic Substances Control Act (TSCA) Chemical Substance Inventory.

16. OTHER INFORMATION

Hazard Rating System**NFPA**

Health	Flammability	Instability
2	1	0

HMIS

Health	Flammability	Physical Hazard
2*	1	0

* = Chronic Effects (See Hazards Identification)

Revision

Identification Number: 4000034 / A776 / Issue Date: 08/13/2024 / Version: 6.1

Most recent revision(s) are noted by the bold, double bars in left-hand margin throughout this document.

Legend

ACGIH	USA. ACGIH Threshold Limit Values (TLV)
CAL PEL	California permissible exposure limits for chemical contaminants (Title 8, Article 107)
PEL	Permissible exposure limit
TWA	8-hr TWA
US WEEL	USA. Workplace Environmental Exposure Levels (WEEL)

Full text of other abbreviations

AIIC - Australian Inventory of Industrial Chemicals; ASTM - American Society for the Testing of Materials; bw - Body weight; CERCLA - Comprehensive Environmental Response, Compensation, and Liability Act; CMR - Carcinogen, Mutagen or Reproductive Toxicant; DIN - Standard of the German Institute for Standardisation; DOT - Department of Transportation; DSL - Domestic Substances List (Canada); ECx - Concentration associated with x% response; EHS - Extremely Hazardous Substance; ELx - Loading rate associated with x% response; EmS - Emergency Schedule; ENCS - Existing and New Chemical Substances (Japan); ErCx - Concentration associated with x% growth rate response; ERG - Emergency Response Guide; GHS - Globally Harmonized System; GLP - Good Laboratory Practice; HMIS - Hazardous Materials Identification System; IARC - International Agency for Research on Cancer; IATA - International Air Transport Association; IBC - International Code for the Construction and Equipment of Ships carrying Dangerous Chemicals in Bulk; IC50 - Half maximal inhibitory concentration; ICAO - International Civil Aviation Organization; IECSC - Inventory of Existing Chemical Substances in China; IMDG - International Maritime Dangerous Goods; IMO - International Maritime Organization; ISHL - Industrial Safety and Health Law (Japan); ISO - International Organisation for Standardization; KECI - Korea Existing Chemicals Inventory; LC50 - Lethal Concentration to 50 % of a test population; LD50 - Lethal Dose to 50% of a test population

(Median Lethal Dose); MARPOL - International Convention for the Prevention of Pollution from Ships; MSHA - Mine Safety and Health Administration; n.o.s. - Not Otherwise Specified; NFPA - National Fire Protection Association; NO(A)EC - No Observed (Adverse) Effect Concentration; NO(A)EL - No Observed (Adverse) Effect Level; NOELR - No Observable Effect Loading Rate; NTP - National Toxicology Program; NZIoC - New Zealand Inventory of Chemicals; OECD - Organization for Economic Co-operation and Development; OPPTS - Office of Chemical Safety and Pollution Prevention; PBT - Persistent, Bioaccumulative and Toxic substance; PICCS - Philippines Inventory of Chemicals and Chemical Substances; (Q)SAR - (Quantitative) Structure Activity Relationship; RCRA - Resource Conservation and Recovery Act; REACH - Regulation (EC) No 1907/2006 of the European Parliament and of the Council concerning the Registration, Evaluation, Authorisation and Restriction of Chemicals; RQ - Reportable Quantity; SADT - Self-Accelerating Decomposition Temperature; SARA - Superfund Amendments and Reauthorization Act; SDS - Safety Data Sheet; TCSI - Taiwan Chemical Substance Inventory; TECl - Thailand Existing Chemicals Inventory; TSCA - Toxic Substances Control Act (United States); UN - United Nations; UNRTDG - United Nations Recommendations on the Transport of Dangerous Goods; vPvB - Very Persistent and Very Bioaccumulative

Information Source and References

This SDS is prepared by Product Regulatory Services and Hazard Communications Groups from information supplied by internal references within our company.

DDP SPECIALTY ELECTRONIC MATERIALS US 9, LLC urges each customer or recipient of this (M)SDS to study it carefully and consult appropriate expertise, as necessary or appropriate, to become aware of and understand the data contained in this (M)SDS and any hazards associated with the product. The information herein is provided in good faith and believed to be accurate as of the effective date shown above. However, no warranty, express or implied, is given. Regulatory requirements are subject to change and may differ between various locations. It is the buyer's/user's responsibility to ensure that his activities comply with all federal, state, provincial or local laws. The information presented here pertains only to the product as shipped. Since conditions for use of the product are not under the control of the manufacturer, it is the buyer's/user's duty to determine the conditions necessary for the safe use of this product. Due to the proliferation of sources for information such as manufacturer-specific (M)SDSs, we are not and cannot be responsible for (M)SDSs obtained from any source other than ourselves. If you have obtained an (M)SDS from another source or if you are not sure that the (M)SDS you have is current, please contact us for the most current version.

US