



Revision Number: 009.0

Issue date: 03/22/2017

1. PRODUCT AND COMPANY IDENTIFICATION

Product name:	LOCTITE EA E-05CL known as Hysol E-05CL Epoxy ADH - Ultra	IDH number:	701962
Product type:	Epoxy Hardener	Item number:	29299_209527
Restriction of Use:	None identified	Region:	Canada
Company address:	Contact information: Telephone: +1 (905) 814-6511 MEDICAL EMERGENCY Phone: Poison Control Center 1-877-671-4608 (toll free) or 1-303-592-1711 TRANSPORT EMERGENCY Phone: CHEMTREC 1-800-424-9300 (toll free) or 1-703-527-3887 Internet: www.henkelna.com		

2. HAZARDS IDENTIFICATION

EMERGENCY OVERVIEW

DANGER: COMBUSTIBLE LIQUID.
 CAUSES SEVERE SKIN BURNS AND EYE DAMAGE.
 MAY CAUSE AN ALLERGIC SKIN REACTION.
 MAY CAUSE ALLERGY OR ASTHMA SYMPTOMS OR BREATHING DIFFICULTIES IF INHALED.

HAZARD CLASS	HAZARD CATEGORY
FLAMMABLE LIQUID	4
SKIN CORROSION	1B
SERIOUS EYE DAMAGE	1
RESPIRATORY SENSITIZATION	1
SKIN SENSITIZATION	1

PICTOGRAM(S)



Precautionary Statements

Prevention:	Keep away from heat, sparks, open flames, hot surfaces - no smoking. Avoid breathing vapors, mist, or spray. Wash affected area thoroughly after handling. Contaminated work clothing should not be allowed out of the workplace. Wear protective gloves, clothing, eye and face protection. In case of inadequate ventilation wear respiratory protection.
Response:	IF SWALLOWED: Rinse mouth. Do NOT induce vomiting. If on skin (or hair): Take off immediately all contaminated clothing. IF INHALED: Remove victim to fresh air and keep at rest in a position comfortable for breathing. Immediately call a POISON CENTER or physician. IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing. If skin irritation or rash occurs: Get medical attention. If experiencing respiratory symptoms: Call a poison center or physician. Wash contaminated clothing before reuse. In case of fire: Use foam, dry chemical or carbon dioxide to extinguish.
Storage:	Store in a well-ventilated place. Keep cool. Store locked up.
Disposal:	Dispose of contents and/or container according to Federal, State/Provincial and local governmental regulations.

IDH number: 701962

Product name: LOCTITE EA E-05CL known as Hysol E-05CL Epoxy ADH - Ultra

Classification complies with Canadian Hazardous Products Regulations (WHMIS 2015) and is consistent with the provision of the United Nations Globally Harmonized System of Classification and Labeling of Chemicals (GHS).

See Section 11 for additional toxicological information.

3. COMPOSITION / INFORMATION ON INGREDIENTS

Hazardous Component(s)	CAS Number	Weight %*
Poly[oxy(methyl-1,2-ethanediyl)], a-hydroxy-hydroxy-, ether with 2,2-bis(hydroxymethyl)-1,3-propanediol (4:1), 2-hydroxy-3-mercaptop	72244-98-5	80 - 90
Benzyltrimethylamine	103-83-3	5 - 10
Monoethanolamine	141-43-5	1 - 5

* Exact percentages may vary or are trade secret. Concentration range is provided to assist users in providing appropriate protections.

4. FIRST AID MEASURES

Inhalation:	Move to fresh air. If breathing is difficult, give oxygen. If not breathing, give artificial respiration. Get medical attention.
Skin contact:	Remove contaminated clothing and footwear. Immediately flush skin with plenty of water (using soap, if available). Get medical attention. Wash clothing before reuse. Thoroughly clean shoes before reuse.
Eye contact:	Immediately flush eyes with plenty of water for at least 15 minutes. Get medical attention.
Ingestion:	DO NOT induce vomiting unless directed to do so by medical personnel. Never give anything by mouth to an unconscious person. Get medical attention.
Symptoms:	See Section 11.

5. FIRE FIGHTING MEASURES

Extinguishing media:	Water spray (fog), foam, dry chemical or carbon dioxide.
Special firefighting procedures:	Wear self-contained breathing apparatus and full protective clothing, such as turn-out gear.
Unusual fire or explosion hazards:	In case of fire, keep containers cool with water spray.
Hazardous combustion products:	Oxides of carbon. Oxides of nitrogen. Oxides of sulfur. Hydrogen sulfide. Toxic fumes. Irritating vapors.

6. ACCIDENTAL RELEASE MEASURES

Use personal protection recommended in Section 8, isolate the hazard area and deny entry to unnecessary and unprotected personnel.

Environmental precautions:	Do not allow product to enter sewer or waterways.
Clean-up methods:	Remove all sources of ignition. Ensure adequate ventilation. Wear appropriate personal protective equipment. Refer to Section 8 "Exposure Controls / Personal Protection" prior to clean up. Soak up with inert absorbent material (e.g. sand, silica gel, acid binder, universal binder, sawdust). Scrape up spilled material and place in a closed container for disposal.

7. HANDLING AND STORAGE

Handling: Keep away from heat, spark and flame. Prevent contact with eyes, skin and clothing. Do not breathe vapor and mist. Wash thoroughly after handling. Use only with adequate ventilation. Keep container closed.

Storage: Keep container tightly closed and in a cool, well-ventilated place away from incompatible materials. Keep away from heat, spark and flame. Store in original container until ready to use.

Shelf Life Statement: Not available.

8. EXPOSURE CONTROLS / PERSONAL PROTECTION

Employers should complete an assessment of all workplaces to determine the need for, and selection of, proper exposure controls and protective equipment for each task performed.

Hazardous Component(s)	ACGIH TLV	OSHA PEL	AIHA WEEL	OTHER
Poly[oxy(methyl-1,2-ethanediyl)], a-hydro-w-hydroxy-, ether with 2,2-bis(hydroxymethyl)-1,3-propanediol (4:1), 2-hydroxy-3-mercaptan	None	None	None	None
Benzyltrimethylamine	None	None	None	None
Monoethanolamine	6 ppm STEL 3 ppm TWA	3 ppm (6 mg/m3) PEL	None	None

Engineering controls: Use local ventilation if general ventilation is insufficient to maintain vapor concentration below established exposure limits.

Respiratory protection: Use a NIOSH approved air-purifying respirator if the potential to exceed established exposure limits exists.

Eye/face protection: Safety goggles or safety glasses with side shields. Full face protection should be used if the potential for splashing or spraying of product exists.

Skin protection: Use chemical resistant, impermeable clothing including gloves and either an apron or body suit to prevent skin contact.

9. PHYSICAL AND CHEMICAL PROPERTIES

Physical state:	Liquid
Color:	Clear
Odor:	Mercaptan
Odor threshold:	Not available.
pH:	Not available.
Vapor pressure:	Not available.
Boiling point/range:	Not available.
Melting point/ range:	Not available.
Specific gravity:	1.12
Vapor density:	Not available.
Flash point:	78 °C (172.4 °F) Pensky Martens closed cup
Flammable/Explosive limits - lower:	Not available.
Flammable/Explosive limits - upper:	Not available.
Autoignition temperature:	Not available.
Flammability:	Not applicable
Evaporation rate:	Not available.
Solubility in water:	Not available.
Partition coefficient (n-octanol/water):	Not available.
VOC content:	< 1 %; < 10 g/l Estimated
Viscosity:	Not available.
Decomposition temperature:	Not available.

10. STABILITY AND REACTIVITY

Stability:	Stable under normal conditions of storage and use.
Hazardous reactions:	None under normal processing.
Hazardous decomposition products:	Oxides of carbon. Oxides of nitrogen. Oxides of sulfur. Hydrogen sulfide. Toxic fumes. Irritating vapors.
Incompatible materials:	Acids. Oxidizing agents. Halogenated compounds.
Reactivity:	Not available.
Conditions to avoid:	Keep away from heat, ignition sources and incompatible materials. Avoid moisture.

11. TOXICOLOGICAL INFORMATION

Relevant routes of exposure: Skin, Inhalation, Eyes, Ingestion

Potential Health Effects/Symptoms

Inhalation:	Mists, vapors or liquid may cause severe irritation or burns. May cause allergic respiratory reaction.
Skin contact:	Causes skin burns. May cause allergic skin reaction.
Eye contact:	Causes serious eye damage.
Ingestion:	May cause burns of mouth and throat if swallowed.

Hazardous Component(s)	LD50s and LC50s	Immediate and Delayed Health Effects
Poly[oxy(methyl-1,2-ethanediyl)], a-hydroxy-, ether with 2,2-bis(hydroxymethyl)-1,3-propanediol (4:1), 2-hydroxy-3-mercaptan	None	No Records
Benzyltrimethylamine	None	Irritant, Corrosive, Allergen, Respiratory
Monoethanolamine	Oral LD50 (Rat) = 10.2 g/kg Oral LD50 (Mouse) = 700 mg/kg Dermal LD50 (Rabbit) = 1,025 mg/kg	Irritant, Kidney, Liver, Corrosive, Respiratory, Developmental

Hazardous Component(s)	NTP Carcinogen	IARC Carcinogen	OSHA Carcinogen (Specifically Regulated)
Poly[oxy(methyl-1,2-ethanediyl)], a-hydroxy-, ether with 2,2-bis(hydroxymethyl)-1,3-propanediol (4:1), 2-hydroxy-3-mercaptan	No	No	No
Benzyltrimethylamine	No	No	No
Monoethanolamine	No	No	No

12. ECOLOGICAL INFORMATION

Ecological information: Not available.

13. DISPOSAL CONSIDERATIONS

Information provided is for unused product only.

Recommended method of disposal: Dispose of according to Federal, State and local governmental regulations.

14. TRANSPORT INFORMATION

The transport information provided in this section only applies to the material/formulation itself, and is not specific to any package/configuration.

Canada Transportation of Dangerous Goods - Ground

Proper shipping name: AMINES, LIQUID, CORROSIVE, N.O.S. (Aliphatic amines)
Hazard class or division: 8
Identification number: UN 2735
Packing group: III

International Air Transportation (ICAO/IATA)

Proper shipping name: Amines, liquid, corrosive, n.o.s. (Aliphatic amines)
Hazard class or division: 8
Identification number: UN 2735
Packing group: III

Water Transportation (IMO/IMDG)

Proper shipping name: AMINES, LIQUID, CORROSIVE, N.O.S. (Aliphatic amines)
Hazard class or division: 8
Identification number: UN 2735
Packing group: III

15. REGULATORY INFORMATION

Canada Regulatory Information

CEPA DSL/NDL Status: All components are listed on or are exempt from listing on the Canadian Domestic Substances List.

United States Regulatory Information

TSCA 8 (b) Inventory Status: All components are listed or are exempt from listing on the Toxic Substances Control Act Inventory.

16. OTHER INFORMATION

This safety data sheet contains changes from the previous version in sections: New Safety Data Sheet format.

Prepared by: Rebecca Coons, Regulatory Affairs Specialist

Issue date: 03/22/2017

DISCLAIMER: The data contained herein are furnished for information only and are believed to be reliable. However, Henkel Corporation and its affiliates ("Henkel") does not assume responsibility for any results obtained by persons over whose methods Henkel has no control. It is the user's responsibility to determine the suitability of Henkel's products or any production methods mentioned herein for a particular purpose, and to adopt such precautions as may be advisable for the protection of property and persons against any hazards that may be involved in the handling and use of any Henkel's products. In light of the foregoing, Henkel specifically disclaims all warranties, express or implied, including warranties of merchantability and fitness for a particular purpose, arising from sale or use of Henkel's products. Henkel further disclaims any liability for consequential or incidental damages of any kind, including lost profits.