

	Doc or ECO #:	ECO-THR-STR-KIT-001	Date:	08/10/2021	Author:	SL
	Rev. #:	A				
Engineering Change Order (ECO)	Engineering Approval:	aeg	Date:	08/10/2021	Quality Approval:	aeg

P/N #:	THR-STR-KIT	Effective Date:	August 10, 2021
Title:	Tether Strain Relief Replacement Kit Updates		

1.0 Purpose / Summary

- The purpose of this ECO is the Tether Strain Relief Replacement Kit up to current standard with what we are currently shipping on tethers

2.0 Parts Affected

Part Number	Notes	Removed	Added	Modified	REV
THR-STR-KIT	Top Level Kit	☐	☐	☒	B
517-5505	3/16" Adhesive Shrink Tubing	☒	☐	☐	COTS
PTN0.50BK	Increased Quantity From 6" to 30"	☐	☒	☐	COTS
7270K82	0.8" Adhesive Shrink Tubing	☐	☒	☐	COTS

3.0 Detail

- Due to the diameter increase of Falmat tether, the 3/16" Adhesive Shrink Tube **[517-5505]** has been changed to 0.8" Diameter **[7270K82]** which is backwards and forwards compatible as it has a minimum ID Shrink diameter down to 0.2".
- The Braided Mesh Sleeving **[PTN0.50BK]** had an incorrect length of 6" and has been corrected to a length of 30"

4.0 Disposition of Material

- Any Tether Strain Relief Kit **[THR-STR-KIT]** currently in stock should be upgraded to Revision B

5.0 Action Items

Action	Department	Acknowledgement Initials
Update Epicor	Engineering	SL

	Doc or ECO #:	ECO-THR-STR-KIT-001	Date:	08/10/2021	Author:	SL
	Rev. #:	A				
Engineering Change Order (ECO)	Engineering Approval:	aeg	Date:	08/10/2021	Quality Approval:	aeg

6.0 Modified / Referenced Documents:

Document	Current Revision

7.0 Revision History

Date Revised (mm-dd-yyyy)	Location of Change (section, paragraph no., step no., etc.)	Description of Change Made	Name of Person making the Change