

WETLabs ECO FLNTU

1. Device initialization performed by instrument service

Sets average per sample, samples per packet, packets per set, interval between packets, packet interval; enables or disables internal logging.

2. Device metadata returned in SIAM datastream

```
Ver FLNTUS 2.70
Ave 20 Pkt 5
Set 1
Rec 1
Int 00:00:05
Dat 03/17/06
Clk 04:10:32
Mem 3512
```

3. Instrument-specific service properties

```
/** Number of measurements in each sample ("save") */
int averageCount = 50;

/** Number of samples in a packet ("pkt"). */
int samplesPerPacket = 3;

/** Number of times to repeat packet ("set") */
int packetsPerSet = 1;

/** Interval between packets - must be expressed as hh:mm:ss */
String packetInterval = "0:0:0";

/** Enable or disable data logging to instrument FLASH. */
boolean logEnabled = true;
```

4. Initial service property values for this deployment

```
powerPolicy=ALWAYS
commPowerPolicy=SAMPLING
powerOnDelaySec=0
nominalCurrentMa=1000
currentLimitMa=1000
sampleSchedule=R */0 */10 */0 */0 * * * * GMT *
maxSampleTries=3
sampleTimeoutMsec=60000

packetsPerSet=1
serviceStatus=2
averageCount=20
startDelayMsec=2000
samplesPerPacket=5
```

logEnabled=true

5. Results of acceptance test procedures

OK

6. Known-service bugs/deficiencies

None