

0x0000 0x0003	Organization (4 bytes)
0x0004 0x0007	Type\Version (4 bytes)
0x0008 0x0017	UUID (16 bytes)
0x0018 0x0023	payload start address (4 bytes) payload end address (4 bytes) payload checksum crc32 (4 bytes)
0x0024	sensor data sheet -driver name (256 bytes) -ISI ID (8 bytes) -max current required (4 bytes) -etc. The format will be determined by the version and newer version will always be backward compatible with older versions.
start	driver and meta-data in jar file