EOM Cable Test Results Summary

Rev 1.0 10/8/03

Sample Description	Breaking Strength (lbs)	Break Strength after Flex Test (lbs)	Strain at 6000 lbs (%)	Torque at 6000 lbs (in-lbs)	Rotation at 6000 lbs (deg/ft)	Notes
SBC Deployed Cable Failure Analysis Tests						
1st Location where float was definitely located during deployment (C-I)	19660	----------	----------	----------	----------	Broke mid-span, away from socket.
2nd Location where float was definitely located during deployment (L-M)	19350	----------	----------	----------	----------	Broke mid-span, away from socket.
SBC Kevlar Cable: Section where float was not attached. (B2-C2)	18550	----------	----------	----------	----------	Clean mid-span break. There was some float movement so it's possible that a float had migrated to this location.
SBC Kevlar Cable: Anchor Termination	20480	----------	----------	----------	----------	Broke 4" from termination, inside bending strain relief.
SBC Kevlar Cable: Snubber Termination	10760	----------	----------	----------	----------	Broke at nose of bending strain relief. This BSR was obviously overly stiff.
SBC Kevlar Cable: Location below all floatation. (E-E1)	38270	----------	----------	----------	----------	Broke at resin socket, indicating little reduction in strength of cable.
SBC Kevlar Cable: Fish-bite transition point (R-S)	16350	----------	----------	----------	----------	Broke right at end of steel braid layer.
Tests on New Cable Segments						
SBC Kevlar Cable	42500	9750	0.7	-20	-0.5	Pull to failure after flex tests broke at edge of float attaced, i.e. the high-bend point.
SBC Vectran Cable						
JDR Vectran Cable Design 1A						
JDR Vectran Cable Design 1B						
Corland CSM Cable						
Rochester CSM Cable						