

P1

P2

P1 Pin	P2 Pin	Size (AWG)	Color	Description
1	3	24	white/orange	TX+
2	6	24	orange/white	TX-
3	1	24	white/green	RX+
4	7	24	blue/white	--
5	8	24	white/blue	--
6	2	24	green/white	RX-
7	4	24	white/brown	--
8	5	24	brown/white	--

P1

P2



Ref.Des.	Mfgr.	Mfgr P/N	Description
P1	ASSMAN	AT-AG-8/8	Connector, Modular 8 pin CAT5
P2	ASSMAN	AT-AG-8/8	Connector, Modular 8 pin CAT5
CUT	ALPHA	9504C SL021	CAT5 Ethernet Cable

Notes (unless otherwise specified):

Config	L	Description
-xxx -001	x" ??	SideKICK to SideARM MOOS Engr. Dep.

Copyright © 2002 MBARI

All information herein is considered proprietary and may not be copied, duplicated, or transmitted without the express permission of Monterey Bay Aquarium Research Institute

Monterey Bay Aquarium Research Institute
7700 Sandholdt Rd. Moss Landing, CA 95039-9644

Cable, MOOS Ethernet Crossover
SideKICK - SideARM

Drawn By: Lance McBride

DOC #: 1001555

REV. A

Date: 6/20/02

Sheet: 1 of 1