



```

**DOES NOT HAVE TO MEET RDS GUIDELINES.
**BOARD OUTLINE SENT TO 0.001". PLEASE CUT OUTSIDE THAT LINE IN ORDER TO HOLD BOARD DIMENSIONS.
**CERAMIC MOUNTING HOLES ARE PROBABLY A BIT OFF THE BOARD.
TRACE/SPACE: 0.008"/0.007"
SMALLEST HOLE SIZE: 0.010"
LAYER ORIENTATION:
    -TOP
    -IN1
    -END
    -PAR
    -BOT
DIMENSIONS: 9.813" X 9.000"
BOARD THICKNESS: 0.063"
COPPER WEIGHT: CUT/INNER = 2oz/2oz
FINISH: HOT AIR SOLDER LEVEL
SILK SCREEN: BOTH SIDES
SOLDER MASK: BOTH SIDES
SOLDERMASK COLOR: RED

```