


NOTE: TX AND RX REFER TO THE AQUADOPP.

Pin No.	Wire colour	Purpose
3	black	RS232 Tx
4	white	RS232 Rx
5	black	RS232 Gnd
6	white/purple	Power output
7	black	Analogue ch 2
8	white/orange	Analogue ch 1
1	black	Power Gnd
2	white	Power +
screen	bare	Gnd


IMPULSE OR SUBCONN



LPMIL-8-MP

NOTE: CONFIRM LPMIL WHIP COLOR CODES, MAY BE DIFFERENT THAN SPECIFIED. PIN NUMBERS TAKE PRECENDENCE.

48 INCH TOTAL LENGTH
MINIMUM



MMC BACKPLANE
DPA CONNECTOR



REVISION HISTORY
1.0 14FEB06 FIRST RELEASE.

NORTEK "AQUADOPP" PROFILER TEST CABLE

MARK CHAFFEY 831 775 1708 chma@mbari.org	MBARI 7700 SANDHOLDT ROAD MOOS LANDING, CALIFORNIA 95039 (831) 775 - 1708 www.mbari.org			
	MTM4 NORTEK "AQUADOPP" TEST CABLE			
Size C	CAGE Code <Cage Code>	DWG NO 1003043SCH-1.0	Rev 1.0	
Monday, March 12, 2007	Scale	Sheet 1 of 1		