



MATERIALS

BODY	BRASS NICKEL PLATED
CONTACT	GOLD PLATED
INSULATOR	PTFE



STRIPPING DIMENSIONS

ASSEMBLY PROCEDURES

1. STRIP CABLE AS SHOWN & TIN CENTER CONDUCTOR. SLIDE FERRULE OVER CABLE.
2. INSTALL CABLE INTO BODY OF CONNECTOR & SOFT SOLDER CENTER CONDUCTOR IN PLACE.
3. CRIMP FERRULE & PRESS CAP DOWN.

CRIMP SIZE REQUIRED

FERRULE: .213" HEX CRIMP TOOL

NOTES:

1. UNLESS OTHERWISE SPECIFIED ALL DIMENSIONS ARE NOMINAL
2. ALL SPECIFICATION ARE SUBJECT TO CHANGE WITHOUT NOTICE AT ANY TIME.

PE PASTERNAK ENTERPRISES
P.O. BOX 16759, IRVINE, CA. 92623
PHONE (949) 261-1920 FAX (949) 261-7451

DWG TITLE

PE4882

SIZE A	FSCM NO. 53919	DES. MCX PLUG RIGHT ANGLE FOR CABLE ATTACHMENT, CRIMP FOR RG58	
SCALE N/A	CAD FILE 082200	SHEET 1 OF 1	127