

ST-750

900 MHz FLEX SYNTHESIZED

FEATURES

- 30 Message Memory
- 15 Locked Messages
- Date & Time Display
- Message Full Indicator
- Vibrator/Chirp/Silent
- Selective Erase
- Unread Message Indicator
- Reflective Backlighting
- Auto On / Off Timer
- Time Display When Power Off
- User Selectable 8 Melody Alert, 4 Beep Tones
- Receiving Time Stamping
- Alarm
- Erase All
- Duplicate Message Indication
- Memory Retention When Power Off
- Low Battery Alarm
- 12 Programmable 12-Digit Canned Messages



SPECIFICATIONS

- Frequency Band 900 MHz
- Baud Availability 1600, 3200, 6400 FLEX
- Code Format FLEX
- Paging Sensitivity:
 - FLEX 1600 BPS -106dBm
 - FLEX 3200 BPS -104dBm
 - FLEX 6400 BPS -103dBm
- Selectivity 55 db @ + 25 kHz
- Spurious Rejection 40 db @ below Carrier
- Frequency Stability + 5 ppm
- Channel Spacing + 25 kHz
- Receiver Type Synthesized
- Address 8 CAPcodes
- Frequency Deviation + 4.8 kHz
- Memory Capacity 30 memory X 20Ch=600 Ch memory
- Alert Tone 75 db @ 12 in 2960 Hz at Standard Alert
- Operating Temperature 0-50 degrees Celsius
- Power Supply One 1.5 V, AAA-size alkaline battery
- Battery Life (Typical) 120 days (assumes battery cycle 4)
- Low Battery Level 1.1 Volts
- Weight with Battery 40 grams
- Dimensions 42 X 61 X 19.6 mm