



VICOR CONFIDENTIAL


THIS DOCUMENT AND THE DATA DISCLOSED
HEREIN OR HEREWITH IS NOT TO BE REPRODUCED,
USED, OR DISCLOSED IN WHOLE OR IN PART
TO ANYONE WITHOUT PERMISSION OF VICOR CORP.

REV.	DESCRIPTION	DATE	APPROVED
#1	DRAWN FOR DEVELOPMENT	DPK 05/27/04	AC



ELECTRICAL SPECIFICATIONS

CAPACITANCE 1KHz, 1VAC	.01uF
CAPACITANCE TOLERANCE	±10%
VOLTAGE	500V
CAPACITOR TYPE	X7R
DISSIPATION FACTOR — 2.5% MAX AT 1KHz, 1VAC	
INSULATION RESISTANCE	10 MEGOHMS
DIELECTRIC WITHOLDING VOLTAGE	200% RATED VOLTAGE FOR 5 SEC WITH 50mA MAX CHARGING CURRENT

DRAWN BY D.P. KELLY	DATE 05/04			
UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES— TOLERANCES ARE: FRACTIONS DECIMALS ANGLES ±1/64 .XX= .01 ±1° .XXX= .005		CAPACITOR, X7R .01uF ± 10%, 500V		
THIRD ANGLE PROJECTION 	SIZE B	FSCM NO. 67131	DWG NO 28054	REV # 1
DO NOT SCALE DRAWING	SCALE NONE	SHEET 1 OF 1		