

An Integrated Approach to Ocean Observatory Data Acquisition/Management and Infrastructure Control Using Web Services

Bill St. Arnaud

CANARIE, Inc., Ottawa, Ontario, K1P 5M9 Canada

Alan D. Chave and Andrew R. Maffei

Woods Hole Oceanographic Institution, Woods Hole, MA 02543

Edward Lazowska

Computer Science and Engineering, University of Washington, Seattle, WA
98195

Larry Smarr

Computer Science and Engineering, University of California, San Diego, La Jolla,
CA 92093

Ganesh Gopalan

College of Oceanic and Atmospheric Sciences, Oregon State University, Corvallis,
OR 97331

ABSTRACT

The proliferation of ocean observatories in the absence of agreed-upon standards for instrument and user interfaces and observatory control functions will constrain interoperability and cross-linking of disparate datasets. This will in turn limit the scientific impact of ocean observatories and increase their operating costs. Devising hardware-based standards will be difficult given the different internal architectures of existing and planned ocean observatories. This paper proposes that instrument, data, and observatory control processes be wrapped with standard web services which will provide a global software standard for these observatory functions. In addition to facilitating interoperability, state-full web services with workflow bindings for observatory instrument and data processes will enable dynamic user control of observatory configuration and the creation of multiple virtual instrument networks within one or more ocean observatories. These concepts are defined and illustrated through a number of use scenarios.

1. Introduction

Since the 1800's, oceanographers have mapped and sampled across two-thirds of Earth primarily using ships as observational platforms. This has yielded a series of snapshot views of the oceans which have limited resolution in time. Measurements and models from this exploratory phase of oceanography have resulted in growing recognition of the diversity and complexity of, and the linkages between, processes that operate above, within and beneath the oceans. The questions posed from these efforts increasingly cannot be answered using only the tools of the present, in large part because of a limited ability to resolve episodicity and temporal change. For this and other reasons, the ocean sciences are beginning a new phase in which scientists will enter the ocean environment, adaptively observe the earth-ocean system, and conduct *in situ* perturbation experiments. Routine, long term access to episodic oceanic processes is crucial to continued growth in the understanding and prognostic modeling of complex natural phenomena that span an enormous range in space and time.

The ubiquity of the Internet and other communication technologies coupled with the decreasing cost and size, and increasing capability, of diverse sensors and communications systems, is resulting in a major paradigm shift in environmental science and engineering. Increasingly, spatially extended, intelligent, interacting sensor webs are seen as the appropriate tools for studying complex real-world systems. In the ocean sciences, this paradigm change is being implemented around innovative facilities called ocean observatories which provide unprecedented levels of power and communication to access and manipulate real-time sensor networks deployed within the ocean basins. These facilities, their real time information flow, and the data repositories associated with them, will empower entirely new approaches to science. In addition, ocean observatories will enable educational-outreach capabilities that can dramatically impact understanding of, and public attitudes toward, the ocean sciences.

The crucial role ocean observatories will play in 21st century oceanography has received

international recognition, and early programs are underway around the world (e.g., Momma et al., 1998; Glenn et al., 2000; Delaney et al., 2000; Favali et al., 2002; Chave et al., 2002; Schofield et al., 2002; Hirata et al., 2002; Austin et al., 2002; Petitt et al., 2002; Beranzoli et al., 2003). Major ocean observatory infrastructure programs exist in Canada (NEPTUNE Canada), and are under consideration in Japan (Advanced Real-Time Earth monitoring Network in the Area or ARENA), Europe (The European Seafloor Observatory Network or ESONET), and the United States (Ocean Research Interactive Observatory Networks or ORION).

Ocean observatories can be implemented using either submarine telecommunications cables to deliver large amounts of power and bandwidth to the seafloor or with moored buoys to link more limited surface power and satellite bandwidth to the ocean bottom. In either case, the major functional ocean observatory subsystems required to provide instrument services, infrastructure power and communications, and observatory management, including data archiving services, are similar. Existing ocean observatory designs are typically unique, one-up designs, and no generally accepted standards exist for either the instrument or shore interfaces or the links to infrastructure control systems. As ocean observatories proliferate and scientists make increasing use of data from diverse facilities, the lack of standards will limit ocean observatory utility and hinder wide use of the associated data archives. At the same time, as the success of the Internet has shown, well-designed standards provide substantially greater flexibility to the end user, whether an instrument, a scientist, or a numerical model.

The purpose of this paper is to propose a unified solution to all of these issues using web or Grid services distributed throughout the subsystems comprising an ocean observatory. Section 2 outlines the physical subsystems of a generic ocean observatory, noting some significant differences between cabled and buoyed implementations. It also describes the functional processes required to link the major subsystems into a coherent whole, and illustrates their purpose through selected use scenarios. Section 3 defines web and Grid services and the layered architecture used to

implement them. Section 4 describes a distributed web services architecture for ocean observatories. The flexibility of the ensuing network recursive architecture is outlined through a few use scenarios and by contrasting it with a conventional stovepipe architecture. Section 5 reviews some remaining issues, including the impact that a web services architecture will have on the design of the major ocean observatory subsystems and facilitation of instrument and observatory interoperability.

2. Components of an Ocean Observatory

Figure 1 is a physical block diagram showing the key hardware subsystems of an ocean observatory science node. The discussion here is brief; a more complete one may be found in Chave et al. (this volume). Copies of these subsystems appear both in other science nodes and in the shore station, either of which should be viewed as a peer. While the figure is directly pertinent to a cabled observatory, the same subsystems will appear in a moored installation except that the submarine cable to other nodes or a shore station is replaced by a buoy-to-satellite communications link and an autonomous power source in the buoy. The remaining subsystems will still be present in the seafloor science node, although their power and bandwidth capability may be more limited. For example, separate high and low voltage power converters may not be required, and the optical transport may not need to support as high a data rate.

The major components of an ocean observatory science node consist of power, data communications, node control, time distribution, and instrument interface subsystems. The power subsystem transforms high voltage DC carried by the single conductor (with seawater return) present in standard submarine fiber optic cable to lower levels usable by both the node infrastructure and science users. This usually will be handled in two stages, with the backbone power stage converting the line voltage to a medium level (e.g., 400 VDC) and the user power stage providing isolated standard voltages (e.g., 48 VDC) to user loads. The data communications subsystem may consist of an access (e.g., layer 2 Ethernet) switch which aggregates IP streams

from a diverse set of instruments and transfers them to a backbone (operating at layer 2 or 3, depending on the observatory topology) router. An optical transport physical layer in the core subsystem could utilize either high speed Ethernet or SONET protocols. The backbone router also handles data streams arriving from or going to adjacent science nodes, if present. The optical transport in the backbone communications subsystem interfaces to the backbone fiber optic cable, and may utilize dense wavelength division multiplex (DWDM) transmission. Both the power and data communications systems are typically redundant in the interest of reliability.

The node control subsystem (NCS; Figure 1) provides high reliability oversight of all node functions, including telemetry of critical data and master control of key subsystems. It will communicate using a combination of in-band and high reliability out-of-band channels. The NCS may be distributed among the other node subsystems or centralized, depending on the implementation. The time distribution system serves synoptic, high accuracy (e.g., 1 μ s or better) time corrected for latency to science users. This can be implemented using precision quartz clocks in each node which are synchronized to standard time at regular intervals over a low-latency non-IP channel. The conventional IP protocol used for time synchronization across the Internet, Network Time Protocol (NTP), cannot operate at this precision. Finally, instruments may be directly attached to underwater-mateable ports or indirectly linked via short-range, real-time acoustic or optical modems. The instrument interface subsystem (IIS) provides power, communications, and time services to instruments and sensors, and may be physically distributed between the science node and individual instruments. The instrument interface also provides critical data management functions such as storage and service of metadata, and contains part of the seafloor component of the data management subsystem (DMS) which is logically distributed throughout the observatory. The remainder of DMS is contained in the shore station or other terrestrial sites and in the NCS, as will become apparent through some use scenarios.

Figure 2 is a functional block diagram showing the key processes required to construct an ocean

observatory that comprise the observatory management system (OMS), which encompasses the NCS, IIS, and DMS. This figure emphasizes interfaces, and the required processes will typically be implemented in software with associated hardware elements.

An *instrument process* resides logically between the instrument and the access data and user power connections at the node. Some of its functions include: monitoring and control of power to the instrument; instrument ground fault detection; bi-directional transmission of data to/from other instruments, other nodes, and the shore station; storage and forwarding of instrument metadata to users or data repositories as required; and acquisition and processing of accurate, synoptic time from the infrastructure for use in the instrument. The instrument process may physically reside in the instrument itself, in the node between the wet-mateable user port and the node data/power hardware, or even in proxy mode on shore or in a buoy, depending on how the software implementing the user process has to interact with the hardware making up the system.

The *node control process* may interact both with hundreds of instrument processes and with several shore-based processes. A partial list of the node control process functions includes: monitoring and control of the node power busses; monitoring and control of the node access and backbone layer data communications hardware; and collection and transmission of node engineering data to shore. The node control process may reside physically in the node or on shore/in a buoy.

An ocean observatory operations center on shore contains all of the processes to monitor, maintain, control, and manage the myriad components of an ocean observatory. The operations center connects to a set of distributed data archives which are probably not co-located. There are four main types of shore-side processes: the *communications control process*, the *power control process*, the *data buffering process*, and the *data archive process*.

The *communications* and *power control processes* are used by ocean observatory operators or

users to control various node, instrument, and sensor functions, and may interact with both the node control and instrument processes. A partial list of their functions includes: monitoring and control of system-wide power usage and availability; monitoring and management of system-wide data bandwidth usage and availability; ensuring that instrument data and power usage lies within prescribed limits; and creation and elimination of connections between instruments or nodes and other processes.

The *data buffering process* gathers real-time data (and instrument metadata) from all instruments, as well as engineering data from the nodes, and stores them temporarily. This process will always be located at each shore station, and serves to provide a short term buffer in the event that connectivity to the Internet and distributed data repositories is interrupted for any reason. In ordinary operation, it simply serves a pass-through function.

The *data archive processes* gather and receive data and/or metadata from specified instrument processes via the data buffering processes. Different repositories may receive and process data from different types of instruments. A partial list of the data archive process functions includes: extraction of instrument metadata from the instrument processes as required; acquisition and post-processing of data streams from instrument processes; and possibly provision for national security control over data access.

The different classes of processes--instrument, node, and shore--interact in sometimes complex ways which are best understood through construction of a wide set of use scenarios. The following examples illustrate some of the issues.

Scenario #1: Assume that an instrument at one node on a multi-node ocean observatory needs to turn on a light. The associated instrument process cannot be allowed to do this directly because if insufficient power is available at the node, then other instruments, the node, and potentially the entire observatory could be affected. The instrument process queries the node control process for

the node to which it is attached. The node control process checks the request against the available power, rejecting it if the reserve is known to be insufficient and approving it if possible. The node control process is itself in regular contact with the shore-based power control process which maintains a constantly-updated, system-wide model of power availability. This is necessary because the power system comprises a complex set of distributed voltage drops at discrete power converters located along long runs of submarine cable, and hence local changes in power consumption can have wide-ranging effects which must be constantly monitored and evaluated. Thus, the simple action of turning on a light requires interaction of three types of processes distributed widely around the observatory.

Scenario #2: Assume that a high density television (HDTV) camera is being used at a node where a rapidly evolving event is occurring. HDTV generates data at a rate of over 1 Gb/s uncompressed and as little as 20 Mb/s compressed (depending on the compression algorithm used), with the latter inevitably imposing loss of scene resolution which might be significant in some applications. An important event may require uncompressed HDTV transmission. In this instance, the HDTV instrument process will request a large allocation of bandwidth, or even a dedicated wavelength on the DWDM optical transport, from the node control process in the node to which it is attached. This node control process will in turn query the shore-based communications control process which keeps track of available bandwidth throughout the ocean observatory. The communications control process can construct an appropriate priority data path for the HDTV stream by altering quality of service allocations throughout the observatory. A quality of service priority list will indicate which scientific instruments can be reduced in priority or even shed in order to accommodate the HDTV requirement. The communications control process will order many node control processes to carry this out, and then set up a pipeline for the HDTV data stream. It may also provide additional bandwidth to data archive process to accommodate the high bandwidth data. At this point, HDTV transmission can proceed. Once this bandwidth-intensive application is complete, the communications control process will release observatory

resources throughout the system.

Scenario #3: Assume that a data assimilation model running at a user's institution is interacting with a subset of the instruments at one or more nodes on one or more ocean observatories. The model is capable of altering the data collection protocols in a semi-automatic fashion, and hence has to interact directly with the associated instrument processes. It also has to interact directly with the data archive processes on shore. For example, if the modeling program alters instrument parameters, then the associated metadata will be updated in the data archive, and this information will have to be inserted into the model. Deeper levels of interaction can also be envisioned; changes in instrument demands for power or bandwidth may involve the communications and power control processes, as well as many node control processes.

Both the process definitions and use scenarios delineate the complexity of the control and interface services needed to operate an ocean observatory. This complexity increases with the size of the installation, and is certainly greater for a multi-node observatory than for a single mooring or single cabled node because of the requirement to coordinate services across the entire facility. While many of the processes could be implemented in hardware, a key characteristic they share is the need for repetitive, automatic inter-service communication and the concomitant exchange of data or commands. In addition, it is likely that the processes needed to operate an ocean observatory will evolve over time as unforeseen modes of operation develop and experience is gained by both users and operators. This argues strongly for a design which places hardware interfaces at primitive levels in the subsystems and implements the inter-process links and their control in software which can be modified as required. This is especially true for a remote seafloor installation where changes of hardware are extremely expensive and where hardware standardization is virtually non-existent. Finally, as ocean observatories proliferate, the need for interoperability will become increasingly important. This is especially true at the sensor and user interfaces where standardization will be essential to wide use of instruments and data from diverse installations. However, interoperability

at the internal levels of ocean observatories will also lead to a substantial reduction in operating costs as the community-wide experience base grows.

As an illustration of a comparatively inflexible ocean observatory design, Figure 3 depicts the data system for a “stovepipe” observatory architecture which was typical of thinking in the recent past. Comparable designs appear in other large science systems centered on autonomous data collection. A common characteristic is that once the design is committed to, it is fixed and permanent for the lifetime of the project without a major re-design and re-build which typically involves basic architectural changes. In Figure 3, the data path consists of a single line from a seafloor instrument, through the node communications subsystem, to the shore station and onto the Internet, terminating at a shore-based data archive. Processes and services are largely fixed and unchangeable throughout the wet and dry parts of the system, and hence there is limited flexibility in managing the observatory. Recursive modes of operation such as that given in the third use scenario above cannot be implemented with this architecture because the required processes cannot be linked dynamically. In addition, distributed observatory processes cannot easily be added to such an architecture after construction without extensive retrofitting of the wet plant. Instead, a comprehensive strategy for ocean observatory interface and control services has to be devised early in the design phase.

3. Web and Grid Services

Web services is an emerging distributed computing paradigm which integrates the description of software components with a means to access them and discovery methods to find them using simple Internet standards. Web services function across hardware platforms, operating systems, or programming languages. While existing web protocols are largely designed to interface computer-based text and graphics to a human user through a web browser, web services extend this functionality to standardized, direct, computer-to-computer communication and software execution. Web services originated in the eBusiness world to enable the seamless integration of legacy

software with new interfaces offered through the web. Web services can operate in either a message-oriented or a procedure-oriented mode. For an overview of the topic, see Newcomer (2002). Web services specifications are being defined within standards bodies and are spawning new industry initiatives (e.g., Microsoft's .NET and Sun's Sun ONE).

Figure 4 defines a simplified top-level architecture for web services implemented using the Extensible Markup Language (XML). Unlike the familiar Hypertext Markup Language (HTML) employed with conventional web browsers, XML separates the document instance, which constitutes the data or message, from the schema, which describes the data structure, enables transformation of the data into alternate forms, and can carry instructions associated with the data. This allows content creation and management to be dynamic and readily adaptable to different applications. A key element of web services is a mechanism to exchange both a data instance and schema, which guarantees that data or instructions will be interpreted identically by all parties, regardless of platform, operating system, or programming language heterogeneity. In addition, the web services XML framework is extensible and hence adaptable to new situations.

For web services, an XML document is implemented using the Web Services Description Language (WSDL), which provides an overarching framework to describe web services as endpoints operating on messages containing either documents or procedure calls. WSDL defines the abstract transformations necessary to send and receive data or commands to underlying, wrapped software, and in turn binds them to network protocols to define the endpoints. WSDL contains three main parts. The data definitions component specifies the structure of the data. The transformation component determines any operations to be performed. Finally, the service bindings component specifies the network transport and ports that will be used to transfer the result to a destination computer.

The Simple Object Access Protocol (SOAP) is the emerging dominant messaging framework

for web services communication, enabling the one-way transmission of a message from source to destination computer. The SOAP standard specifies a minimum level of complexity required to send a message, but is extensible to more elaborate applications and protocols. SOAP is mappable onto standard IP transports like HTTP or FTP.

The final component of the web services architecture is a web services registry and discovery system which publishes and serves pointers to web services interfaces. This is facilitated through Web Services Inspection Language (WSIL) documents which contain service descriptions (i.e., URLs to WSDL documents) and links to other archives of service description. Service descriptions may also be entries into Universal Description, Discovery, and Integration (UDDI) catalogs of web services, although this business-oriented discovery mechanism is often inadequate in a research environment. A more comprehensive Web Service Discovery Architecture (WSDA) is described by Hoschek (2003).

As a use example, a program or process presents information to a web service with an associated WSDL schema. The WSDL may be obtained from a registry or may be derived locally. In either case, it defines the transformation from the underlying source format to one recognizable by the web service, and also specifies a reverse transformation at the destination which may result in a different format than the original one. The sending SOAP processor performs the actual transformation from native to web services format and sends the result over the Internet. The receiving SOAP processor transforms the document into the format required at the destination computer which is specified in the WSDL schema, and transfers it to an underlying process for information or execution.

Web services is not dependent on a byte-wise protocol that is difficult to interpret and impossible to read. Since web services use an XML schema, it is possible for non-technical users to inspect and debug messages. The other important feature of a text-based schema rather than a byte-wise protocol is that it allows for loose coupling between applications. There does not have to

be a direct mapping (or binding) between schemas, but instead schema components can be made up of globally referenced parts contained within a given schema much as URLs are frequently embedded within web pages. The major disadvantage of text based, loosely coupled, schemas is that the associated overhead and processing can be quite significant. As such, web services are generally not efficient for high volume interactive applications, but are extremely valuable for isolated computer-to-computer interactions (as occur in eBusiness applications) or repetitive process monitoring and control applications (as occur in ocean observatories).

The initial early application for web services was linking legacy transaction business applications and document processing with the Internet. Transaction interaction implies that no state is maintained after a process is completed. For example, when a web service system processes a purchase order, all the information that is needed to understand the purchase order is included as part of the WSDL schema describing the transaction. However, researchers recognized that web services could be useful in state-full applications. This was first identified by the global Grid community, who wanted to use web services to enable sharing of high performance computers among a distributed user base. They defined Grid services, which are an extension of web services that includes management of state, identification, session, and lifetime, along with a notification capability. When sharing a computer, or in other long time duration applications, state must be maintained until use of the resource or application is completed. This requirement led the Global Grid Forum to develop the Open Grid Services Architecture (OGSA; see <http://www.ogsa.org>) which provided for state-full web or Grid services (Foster et al., 2003a,b). This class of web services has now been fully encompassed by the new Web Services Resource Framework (WSRF) standard. The addition of state-full web services allows the web services paradigm to be applied to a whole set of new applications beyond those originally conceived for eBusiness. State-full web services allow the web services paradigm to be applied to instruments and other physical resources in addition to software processes.

The final and most recent development in web services is workflow tools that allow users to construct complex web services from a set of simpler ones; in essence, the user orchestrates the dynamic interconnection of diverse web services. Workflow tools also evolved from the eBusiness world where organizations needed the capability to interconnect various legacy and new processes to provide new applications, or to interconnect their processes with those of their customers or suppliers. The recently introduced Web Services Flow Language (WSFL) promises to standardize workflow. This has significant application in allowing the creation of schemas to describe the workflow between web services. In fact, WSFL is often referred to as a critical part of emerging distributed computing environments, and captures the linkage of constituent services together to build larger composite services.

4. A Web Services Architecture for Ocean Observatories

Ocean observatories are a classic multidisciplinary research infrastructure which encompasses both legacy and new installations ranging from individual moored buoys to multi-node regional cabled laboratories. To date, there has been very little hardware or software commonality among existing or planned systems. Each has its own unique external sensor and control protocols, internal power and communications subsystems, and data archive capabilities. Interoperability is limited; instruments typically have to be re-interfaced to move between observatories, and custom software is often required to access data from different observatories. However, it is becoming widely recognized that maximizing the science value of ocean observatories requires commonality in both software and hardware systems so that scientists from diverse disciplines can share instruments, data, and ultimately ideas. This reflects an increasing global trend for large science projects to build an overarching cyberinfrastructure to make data collection and analysis feasible for a broad user community.

We propose a novel approach in which state-less and state-full web services and web services workflow tools are used to create a cyberinfrastructure facility for ocean observatories. This vision

encompasses the main elements of data management and archive processes, observatory management processes, and instrument interface processes, and substantially transcends any one of these taken alone. As a consequence, rather than having each ocean observatory construct a single central data archive to collect all sensor and instrument data, as depicted in the stovepipe architecture of Figure 3, multiple distributed data processes would be created using web services as the common interface technology. Perhaps more significantly, this architecture enables and unifies DMS-NCS-IIS interactions in a flexible and extensible manner.

In the proposed architecture, instrument web services may be exposed as a single service, or they may be a collection of services aligned with disciplinary groupings of instruments, or a collection of services aligned with a multidisciplinary experiment. Multiple web services can be associated with single instruments, and hence multiple virtual observatories within an ocean observatory can be established or removed dynamically. Each independent web service is made up of one or more science instruments, network connection(s), data management system(s), and a distributed observatory management system. Aggregations of web services can also be re-advertised as new composite web services.

For legacy instruments not explicitly designed for the proposed style of observatory operation, proxy web services can substitute for embedded web services. With proxy web services, the actual interface is hosted at a shore station, but to the science user communication appears to be directly with the instrument. Alternately, a standard science instrument interface that goes between a legacy sensor and the node instrument interface and which incorporates embedded web services could be provided by the observatory operator. For either embedded or proxy users, instead of defining the bindings and interfaces between the various ocean observatory components *a priori* at the design

stage, this is left to be defined by the scientific user and observatory management team at the operational stage using WSFL. The proxy model can also be implemented on shore to minimize bandwidth utilization and power requirements where required (such as in buoyed installations).

In the proposed architecture, all science instruments, data management services, and some observatory management services will be implemented as independent, unique, state-full web services. In most instances, observatory management services will be state-less; an instrument or a shore control process will request some operation and disconnect once it is completed. The scientific user binds the different state-full processes together at operational run time using web service work flow tools based on WSFL. State-less control connections are established and removed automatically as needed. This provides the greatest architectural flexibility and easily allows changes to be made to incorporate new experiments without affecting the data flow from existing experiments. In essence, the web workflow approach allows users to bind processes together as required for particular applications largely independent of (but perhaps limited in the end by) the original design and implementation.

A state-full web services compliant scientific instrument and data management service (whether as a proxy or embedded) would have WSDL descriptors and service handle implementation for a number of service ports including:

- (a) Ocean observatory staff management, monitoring and data archiving
- (b) National security authority monitoring and management
- (c) User management and monitoring (may support multiple ports for multiple users)
- (d) User(s) data flow
- (e) Calibration data flow

Ocean observatory state-full web services could include network services (IP, port, multicast, virtual private network (VPN) or lightpath), data logging services, calibration logging services, data archiving services, video scene change detection service, Video MPEG 7 encoding services, metadata cataloging services, and many others.

When a scientific user wishes to set up an experiment, they will use a standard web services workflow tool based on WSFL to bind together a number of instruments and services to create a complete data system for that specific experiment. For example if a scientific user needed a live video feed from a specific camera, they would discover the appropriate web services-compliant video instrument service, bind (using WSFL) that to an advertised ocean observatory network service (e.g. a VPN with appropriate quality of service), in turn bind that to a shore station data archiving service to capture and store the raw data feed, then bind that to a lambda-switched lightpath service across a dedicated terrestrial scientific network, then bind that to an MPEG 7 encoding service, and finally bind that service to a scientific user's own web services-compliant data assimilation model somewhere else in the world. The data stream could also be bound to an education portal so that the general public in classrooms and living rooms can view the video stream.

Figure 5 illustrates the web services approach outlined in this paper. Every network element, sensor, instrument and control process is exposed and registered as web services (either state-full or state-less, depending on their nature). There is no attempt to pre-define the linkages between the various elements. Instead, the science users, their instruments or models, and the observatory operator through the shore control processes, have the freedom and flexibility to link or bind these various services together either automatically or using WSFL. Different science users can

simultaneously bind disparate services together in different ways.

For example, in Figure 5, the red science user can bind a specific instrument with a specific local area network service which in turn is bound to a specific network service which is finally bound to a set of Internet services to deliver the data to a remote high performance computer.

Simultaneously, the green user can utilize the same technologies to create a different set of linkages using the same or different instruments, network services and software processes. The black user can simultaneously use other instruments and observatory services to carry out a different experiment.

Web services also serve as the integrating technology to seamlessly connect disparate ocean observatories together into coherent virtual ocean observatories (VOOs). To carry this out, individual ocean observatory operators need to wrap existing proprietary instrument, control, and data handling processes with standard web services and advertise the results. A user can then bind instruments at multiple ocean observatories into a VOO. A simple use scenario where this would be scientifically enabling is the transit of a major storm system up the eastern seaboard of North America, during which it would cross a series of coastal ocean observatories. By binding these observatories together into a VOO, the growth and decay phases of the ocean's response to an extreme atmospheric forcing event could be continuously studied and/or used for predictive purposes. The concept could readily be extended to provide a web services wrapper for CODAR or weather radar so that these data types could be incorporated into an experiment.

5. Discussion

A prototype example of the architecture described for ocean observatories is the CA*net 4 User

Controlled LightPath (UCLP; St. Arnaud et al., 2003; Boutaba et al., 2004a,b), which provides user switching of dedicated wavelengths on a long haul research network. UCLP is based on the Globus Toolkit 3.0 (<http://www-unix.globus.org/toolkit/>) implementation of OGSA state-full web services. Although the Globus Toolkit 3.0 was originally designed for sharing high performance computer resources, it quickly became recognized that the technology could equally be applied to network devices and services. With UCLP, individual research users can link together various network elements in any way they want to create their own private network topology. The ocean observatory architecture is an extension of this concept to cover a more complete set of services where not only network elements, but also instruments, sensors, and control processes, can be linked together into complete systems.

One of the biggest challenges for projects like ocean observatories is the great degree of uncertainty in the design requirements for the access and core networks and the power system to provide services that must be useful for decades. It is very difficult to predict what new services and facilities will be needed or what instrumentation will be deployed in coming years. The use of state-full web services and WSFL for observatory functions that users interact directly with, and state-less web services for background services, allows researchers and operators to think of the ocean observatory infrastructure as a set of simple building blocks. In the past, hardware and software engineers would spend years designing a detailed architecture to support this type of scientific research, as is implicit to the architecture in Figure 3. With web services and WSFL the infrastructure can be reconfigured at any time to meet the needs of future researchers, or to incorporate lessons learned. This argues strongly for the simplest possible, modular design for the access and core networks to maximize their adaptability to future needs. In particular, a mesh network topology and the use of lambda switching technology is recommended, while complex

topologies which require the interaction of widely distributed subsystems are not.

In principle, extending the web services concept to a flexible facility like an ocean observatory is straightforward. The complexity will arise in meshing diverse state-full and state-less web services into a coherent whole on a scale that has not previously been attempted, but even this task is simpler than building a reliable, fixed system such as that in Figure 3 which will serve science needs for long periods of time. A key distinction is recognition that, for the first time, the architecture of a research infrastructure will be dynamic and in the hands of the science users for the life of the project rather than being locked in place years before it starts by software and hardware engineers who cannot be expected to foresee science applications decades into the future.

Foster (2002) proposed a three point checklist to determine when a system is a Grid, building on earlier definitions. According to these criteria, a Grid is a system which:

1. coordinates resources that are not subject to centralized control
2. using standard, open, general purpose protocols and interfaces
3. to deliver nontrivial qualities of service.

An ocean observatory with a web services architecture which allows a science user to dynamically bind instruments and services together fits this definition, and can be considered a type of science or sensor Grid.

References

- Austin, T.C., J.B. Edson, W.R. McGillis, M. Purcell, R.A. Petitt, Jr., M.K. McElroy, C.W. Grant, J. Ware, and S.K. Hurst, A network-based telemetry architecture developed for the Martha's Vineyard Coastal Observatory, *IEEE J. Ocean. Eng.*, 27, 228-234, 2002.
- Beranzoli, L., T. Braun, M. Calcara, P. Casale, A. De Santis, G. D'Anna, D. Di Mauro, G. Etiope, P. Favali, J.-L. Fuda, F. Frugoni, F. Gamberi, M. Marani, C. Millot, C. Montuori, and G. Smriglio, Mission results from the first GEOSTAR observatory (Adriatic Sea, 1998), *Earth, Planets and Space*, 55, 361-374, 2003.
- Boutaba, R., W. Golab, Y. Iraqi, and B. St-Arnaud, Lightpaths on Demand: A Web Services Based Management System and Case Study, *IEEE Comm. Mag.*, in press, 2004a.
- Boutaba, R., W. Golab, Y. Iraqi, T. Li, and B. St. Arnaud, Grid-Controlled Lightpaths for High Performance Grid Applications, *J. Grid Comp.*, in press, 2004b.
- Chave, A.D., F.K. Duennebiele, R. Butler, R.A. Petitt, Jr., F.B. Wooding, D. Harris, J.W. Bailey, E. Hobart, J. Jolly, A.D. Bowen, and D.R. Yoerger, H2O: The Hawaii-2 Observatory, in *Science-Technology Synergy for Research in the Marine Environment: Challenges for the XXI Century*, edited by L. Beranzoli, P. Favali, and G. Smriglio (Amsterdam: Elsevier), pp. 83-92, 2002.
- Delaney, J.R., G.R. Heath, B.M. Howe, A.D. Chave, and H. Kirkham, NEPTUNE: Real-time ocean and earth sciences at the scale of a tectonic plate, *Oceanogr.*, 13, 71-83, 2000.
- Favali, P., G. Smriglio, L. Beranzoli, T. Braun, M. Calcara, G. D'Anna, A. De Santis, D. Di Mauro, G. Etiope, F. Frugoni, V. Iafolla, S. Monna, C. Montuori, S. Nozzoli, P. Palangio, and G. Romeo, Towards a permanent deep sea observatory: the GEOSTAR European experiment, in *Science-Technology Synergy for Research in the Marine Environment: Challenges for the XXI Century*, edited by L. Beranzoli, P. Favali, and G. Smriglio (Amsterdam: Elsevier), pp. 111-120, 2002.
- Foster, I., What is the Grid? A three point checklist, *Grid Today*, 1 (6), <http://www.gridtoday.com/02/0722/100136.html>, 2002.

- Foster, I., C. Kesselman, and S. Tuecke, The anatomy of the Grid, in F. Berman, G.C. Fox, and A.J.G. Hey (eds.), Grid Computing: Making the Global Infrastructure a Reality, John Wiley, pp. 171-198, 2003a.
- Foster, I., C. Kesselman, J.M. Nick, and S. Tuecke, The physiology of the Grid, in F. Berman, G.C. Fox, and A.J.G. Hey (eds.), Grid Computing: Making the Global Infrastructure a Reality, John Wiley, pp. 217-250, 2003b.
- Glenn, S.M., T.D. Dickey B. Parker, and W. Boicourt, Long-term real-time coastal ocean observation networks, *Oceanogr.*, 13, 24-34, 2000.
- Hirata, K., M. Aoyagi, H. Mikada, K. Kawaguchi, Y. Kaiho, R. Iwase, S. Morita, I. Fujisawa, H. Sugioka, K. Mitsuzawa, K. Suyehiro, H. Kinoshita, and N. Fujiawara, Real-time geophysical measurements on the deep seafloor using submarine cable in the southern Kurile subduction zone, *IEEE J. Ocean Eng.*, 27, 170-181, 2002.
- Hoschek, W., Peer-to-peer Grid databases for Web service discovery, in F. Berman, G.C. Fox, and A.J.G. Hey (eds.), Grid Computing: Making the Global Infrastructure a Reality, John Wiley, pp. 491-542, 2003.
- Momma, H., R. Iwase, K. Mitsuzawa, Y. Kaiho, and Y. Fujiwara, Preliminary results of a three-year continuous observation by a deep seafloor observatory in Sagami Bay, central Japan, *Phys. E. Pl. Int.*, 108, 263-274, 1998.
- Newcomer, E., *Understanding Web Services*, (Boston: Addison-Wesley), 332 pp., 2002.
- Petitt, R.A., Jr., F. B. Wooding, D. Harris, J.W. Bailey, E. Hobart, J. Jolly, A.D. Chave, F.K. Duennebie, and R. Butler, The Hawaii-2 Observatory, *IEEE J. Ocean Eng.*, 27, 245-253, 2002.
- Schofield, O., T. Bergmann, P. Bissett, J.F. Grassle, D.B. Haidvogel, J. Kohut, M. Moline, and S.M. Glenn, The Long-term Ecosystem Observatory: An integrated coastal observatory, *IEEE J. Ocean Eng.*, 27, 146-154, 2002.
- St. Arnaud, Bill, J. Wu, and B. Kalali, Customer-controlled and managed optical networks, *J. Lightwave Tech.*, 21 (11), 2791-2803, 2003.

Figure Captions

Figure 1. Top level block diagram showing the major hardware subsystems and their linkages for a generic ocean observatory node. There may be multiple seafloor nodes linked together and to one or more shore stations.

Figure 2. Interface block diagram showing the major classes of software/hardware processes distributed throughout an ocean observatory that must operate in an integrated manner for the proper functioning of an ocean observatory. See text for discussion.

Figure 3. Architectural block diagram showing a traditional stovepipe design for an ocean observatory, in which most instrument, control, and data management and archiving services are hardwired and operate linearly.

Figure 4. Block diagram illustrating the major components and interactions of web services.

Figure 5. Architectural block diagram illustrating the components of a flexible ocean observatory design utilizing a web services architecture with workflow bindings, as proposed in this paper.









