




Power Sonic Lead-Acid batteries
Temperature compensation at cyclic use:
-At 50C, CV charge at 2.30+/-0.05V/cell or 13.80 +/- 0.3V
-At 40C, CV charge at 2.36+/-0.05V/cell or 14.16 +/- 0.3V
-At 30C, CV charge at 2.42+/-0.05V/cell or 14.52 +/- 0.3V
-At 25C, CV charge at 2.45+/-0.05V/cell or 14.7 +/- 0.3V
-At 20C, CV charge at 2.48+/-0.05V/cell or 14.88 +/- 0.3V
-At 10C, CV charge at 2.54+/-0.05V/cell or 15.24 +/- 0.3V
-At 0C, CV charge at 2.60+/-0.05V/cell or 15.6 +/- 0.3V

Temperature compensation for float:
-At 50C, float at 2.225+/-0.025V/cell or 13.35 +/- 0.15V
-At 40C, float at 2.245+/-0.025V/cell or 13.47 +/- 0.15V
-At 30C, float at 2.265+/-0.025V/cell or 13.59 +/- 0.15V
-At 25C, float at 2.275+/-0.025V/cell or 13.65 +/- 0.15V
-At 20C, float at 2.285+/-0.025V/cell or 13.71 +/- 0.15V
-At 10C, float at 2.305+/-0.025V/cell or 13.83 +/- 0.15V
-At 0C, float at 2.325+/-0.025V/cell or 13.95 +/- 0.15V

		Monterey Bay Aquarium Research Institute 7700 Sandholdt Rd, Moss landing CA 95076	
Engineer Klimov		Page Title Battery Status Board	Project: 901400
831-775-1914			
Size B	Doc. or Part Number <Doc>	File Name (auto) 11021167-BSB1	Rev *
Page Modify Date (auto): Thursday, June 25, 2015		Sheet:	
Design Modify Date (auto): Thursday, June 25, 2015		1	of 1
Full path (auto): U:\ORCAD PROJECTS\POWER-BUOY\11021167-BSB1.DSN			