

THIS DOCUMENT IS ISSUED IN STRICT CONFIDENCE
ON CONDITION THAT IT IS NOT COPIED REPRINTED
OR DISCLOSED TO A THIRD PARTY EITHER WHOLLY
OR IN PART WITHOUT THE PRIOR WRITTEN CONSENT
OF SOUTH BAY CABLE CORPORATION.

REVISION		
DESCRIPTION	DATE	APPROVAL

TWISTED QUAD-1 UNIT

Awg No. 28(7x0.005")B/C
DC Resistance @ 20° C ≤ 69.1 Ohms/1000 Ft
Polypropylene Insulation
Voltage rating: 300 V
Four conductors twisted
Color code sequence: Wht-Blk-Wht-Blk
Polyethylene Belt (natural color)


STRENGTH MEMBER

9/16" (3x19) Galvanized Wire Rope

POWER CONDUCTORS - 2 UNITS

Awg No. 14(19x0.0142") B/C
DC Resistance @ 20° C ≤ 3.1 Ohms/1000 Ft
HD Polyethylene Insulation
Voltage rating: 600 V
Color: White & Black
Nylon Insulation Jacket
Color: Clear

INTERSTICES WATERBLOCKED



ESTIMATED VALUES

Nominal O.D.----- 0.750"
Weight in Air----- 640 Lb/1000 Ft.
Weight in Seawater----- 444 Lb/1000 Ft.
Min. Bend Diameter----- 24 Inches.



**South Bay
Cable**

**S
B
C**

Drawn	OL	7/24/14	Approval	
Checked			Approval	

E-M Cable

SB-48626