





THIS DOCUMENT CONTAINS INFORMATION THAT IS CONFIDENTIAL AND PROPRIETARY TO PARKER HANNIFIN CORPORATION. GENERAL VALVE DIVISION HAS FURNISHED THIS DOCUMENT TO THE UNDERTANDING THAT THE DOCUMENT AND THE INFORMATION IT CONTAINS WILL NOT BE COPIED OR DISCLOSED TO OTHERS EXCEPT WITH THE WRITTEN CONSENT OF PARKER. WILL NOT BE USED FOR ANY PURPOSE OTHER THAN CONDUCTING BUSINESS WITH PARKER, AND WILL BE RETURNED AND ALL FURTHER USE DISCONTINUED UPON REQUEST BY PARKER. COPYRIGHT PARKER, YEAR OF COPYRIGHT IS FIRST YEAR INDICATED ON THIS DOCUMENT. ALL RIGHTS RESERVED.

REVISIONS			
LTR	DESCRIPTION	DATE	APPD
A	ORIFICE WAS .062, REMOVED KALREZ FROM MATERIALS CONTACTING MEDIA	8-19-96	GRK



- VALVE SPECIFICATIONS:
- 1) OPERATING MEDIA LIQUIDS & GASES
 - 2) OPERATING PRESSURE VACUUM TO 1250 PSI
 - 3) OPERATING TEMPERATURE 0 TO 220°C
 - 4) LEAK RATE < 1 X 10E-9 CC/SEC/ATM HELIUM
 - 5) ORIFICE031 DIA
 - 6) OPERATING VOLTAGE 500 MILLIAMPS @ 24 VDC
 - 7) MATERIALS CONTACTING MEDIA PASSIVATED STAINLESS STEEL, TEFLON(r) PEEK, AND PPS



#	QTY	SIMILAR TO

UNLESS OTHERWISE SPECIFIED			DATE	MARCH 15 1996	PARKER HANNIFIN CORPORATION	
FRACTIONS	DECIMALS	ANGLES	DRAWN	PAP	GENERAL VALVE OPERATION	
±1/32	.XXX = ±.020	±2°	CHECKED		19 GLORIA LANE	
	.XXX = ±.010		NE APPD		FAIRFIELD, NEW JERSEY 07004 USA	
	.XXX = ±.0050				TITLE:	
METRIC DIMENSIONS:					2 WAY N.C. SOLENOID	
X.0 = ±0.77 mm					1/4" VACUSEAL(r) FITTINGS	
X.1 = ±0.51 mm					SIZE	SALES
X.2 = ±0.26 mm					C	S
SURFACE TEXTURE TO BE 63					SCALE	2 : 1
DIMENSIONS AND TOLERANCES APPLY BEFORE FINISH TREATMENT					WEIGHT	
DO NOT SCALE DRAWING					99-45	
					SHEET 1 OF 1	