


D15S Series

Full port 316SS ball valve with electric actuator, NEMA 4, 120VAC

(150 lb. flanged end connection, 2 piece valve body)



Size	A	B	C	D	E	F	G	H	I	J	K	M	Actuator (Speed)	Cv	Wt (lbs.)	Model No.
1/2" (C)	4.25	5.63	6.73	4.00	1.85	3.50	2.38	0.51	0.63	1.38	0.06	2.31	R4B2FO3 (2 sec)	16	8.0	CD15SE4
3/4" (D)	4.63	6.88	7.98	4.25	2.10	3.88	2.75	0.79	0.63	1.69	0.06	2.43	SD4B5FO5 (5 sec)	40	12.0	DD15SE4
1" (E)	5.00	6.88	8.13	4.25	2.25	4.25	3.12	1.00	0.63	2.00	0.06	2.43	SD4B5FO5 (5 sec)	72	14.0	ED15SE4
1 1/2" (G)	6.50	7.00	11.15	7.00	3.15	5.00	3.88	1.57	0.63	2.87	0.06	2.38	SH4B10F07 (10 sec)	250	26.0	GD15SE4
2" (H)	7.00	7.00	11.45	7.00	3.45	6.00	4.75	1.97	0.75	3.62	0.06	2.38	SH4B10F07 (10 sec)	420	31.0	HD15SE4

D15S Valve Specifications

Valve:

Full port 316SS body & ball
Blow out proof stem
Anti-static device
Investment cast body
RPTFE seats & seals
150 lb. RF flanged end connection
ANSI 16.10 face-to-face dimensions
ANSI 16.50 flange dimension
Mounting pad for direct mount actuator

Actuators

Electric Actuators:

Electric, 120VAC, NEMA 4
NEMA 7 available (explosion proof)
120 VAC (other voltages available)
25% duty cycle
Universal mounting
Manual override
Visual position indicator
Permanent lubrication
Temperature: -40°F to 150°F (heater recommended below 0°F)