

NarrowBand Self-Contained Technical Manual

The current revision of the NarrowBand Self-Contained Technical Manual is September 1992. If you have an older revision of the manual, you may visit our web site at www.rdinstruments.com and download a new version of the manual.

The NarrowBand Self-Contained Technical Manual is available in the following formats.

- Adobe Acrobat® pdf file

Interim Changes as of 29 July, 1999

These are the most-recent corrections to the NarrowBand Self-Contained Technical Manual.

Rev	Page	Correction
SEP92	5-12	Add the following note to section 5-14: A backup o-ring has been added to the 3000 and 6000-m high pressure ADCPs manufactured after 01JUN95 (except 75-kHz systems). The bore o-ring groove was increased from 4.81 mm (0.189 in) to 5.28 mm (0.208 in) to accommodate the backup o-ring. The backup o-ring is installed in addition to the 2-258 bore o-ring on both the end-cap and transducer head assemblies. Install the backup o-ring with the cupped side facing the 2-258 bore seal o-ring.

New or Changed Commands Brought About By Firmware Changes

Version	Description
17.10	Manual not affected by changes.

How to Contact RD Instruments

Please report any documentation problems or errors to our Customer Service department:

E-mail: rdifs@rdinstruments.com

Phone : +1 858-693-1178

Fax : +1 858-578-4016