



The Professional's Source

The World's Largest Dealer of Imaging Equipment at Discount Prices

[Print](#) | [Close](#)

Horita SCT-50 Character Generator, Time/Date Stamp, Serial Control



Mfg Catalog # SCT50
B&H Catalog # HOSCT50

List Price: \$329.00

Our Price: **\$294.95**

Availability: **Out of Stock**

Product Information

The **SCT-50** is a Character Generator that operates either Stand-Alone or with a computer to Title, Caption, or Time-Date Stamp Video from cameras, VCRs, computers, etc. Insert up to 9 lines of 20 characters each into a video image to add source ID, to show camera number and location for security, Video data collection, or other Video monitoring systems. The internal clock calendar can be used to add a Time/Date Stamp to Video images.

Features

- A Unique "**Split Screen**" mode splits the 9 line display into 5 lines at the very top and 4 lines at the very bottom of the Video image. The topmost line can be positioned completely within the vertical interval so that it can only be viewed on a Video monitor that has a "Pulse-Cross" display. The next two lines at the top and bottom can usually be viewed only on a monitor that has an "Underscan" mode.
- Uses standard **DB-9** connectors for serial port with RS-232 Loop-through. Up to 99 SCT-50s can be daisy chained. They can be addressed by a PC, individually or as a group.
- A **Front Panel Switch** is included to control the SCT-50 as a stand-alone unit. Simple two letter commands from a computer control:
 - Character Selection
 - Location
 - Size
 - Background
 - Flashing
 - Black or White
 - Horizontal Position
 - Vertical Position
- Built in **Time-Code Captioning Software** allows the SCT-50 to operate with Horita PC Time-Code products and the **PC-LOG** software to automatically caption Video images with comments from PC-LOG files according to their Time-Code match.
- Other computer data can be added to the video images using custom programs written in

Basic or C.

*(Programming examples in **Basic** and **C** are included)*

- Built in **Time-Code Captioning Software** allows the SCT-50 to operate with Horita PC Time-Code products and the **PC-LOG** software to automatically caption Video images with comments from PC-LOG files according to their Time-Code match.
- SCT.EXE program controls from 1 to 99 SCT-50s using only a single RS-232 port on a PC. Automatically stores 99 individual SCT-50 screens, any of which can quickly be selected and sent to an individual SCT-50 or multiple SCT-50s. Includes a **SCT.EXE** "pop-up" TSR text editor and control program for PCs. Text tools include:
 - Auto Centering
 - Copy
 - Move
 - Delete
 - Full Screen

[Back to top](#)