


XTREME GREENTM CAT 5e

FALMAT'S ALL NEW
Underwater Network Data/Power Cables



UNDERWATER NETWORK DATA/POWER CABLES

Applications: Homeland Security, Oceanographic, Observation, and other extreme marine environments.

P/N	DESK.	Data Comp	Break Strength	Diameter	Wgt/1000'
FMXCAT51205K24	5C- 12AWG	Cat 5e -24awg (7)	2400 lbs	.700"	256 lbs
FMXCAT51207K24	7C- 12AWG	Cat 5e -24awg (7)	2400 lbs	.700"	297 lbs
FMXCAT51606K24	6C- 16AWG	Cat 5e -24awg (7)	2400 lbs	.564"	157 lbs
FMXCAT51610K24	10C-16AWG	Cat 5e -24awg (7)	2400 lbs	.564"	191 lbs
FMXCAT51812K12	12C-18AWG	Cat 5e -24awg (7)	1200 lbs	.500"	143 lbs
FMXCAT51806K12	6C- 18AWG	Cat 5e -24awg (7)	1200 lbs	.500"	110 lbs
FMXCAT52218K12	18C-22AWG	Cat 5e -24awg (7)	1200 lbs	.447"	120 lbs
FMXCAT52218	18C-22AWG	Cat 5e -24awg (7)	0	.433"	117 lbs
FMXCAT52824K8	24C-28AWG	Cat 5e -24awg (7)	800 lbs	.415"	90 lbs
FMXCAT52824	24C-28AWG	Cat 5e -24awg (7)	0	.400"	88 lbs
FMXCAT50000 *	N/A	Cat 5e -24awg (7)	0	.325"	47 lbs
FMXCAT50000K12 *	N/A	Cat 5e -24awg (7)	1200 lbs	.340"	52 lbs

* Cat 5 cable only, with rugged Xtreme-Green Polyurethane, no power conductors, or water-block.

Data Network/Power Composite Cables featuring:

- Extreme ruggedness, yet flexible water-blocked construction.
- Designed for underwater use with high-speed network data, video, and sensor equipment.
- Cables can be used for bottom-laid, vertical deployment, winch systems, and ROV applications.
- Our Cat 5e 4 pair stranded conductors meets or exceeds TIA 568-B. Suitable for 10Base-T and 100Base-T.
- Custom variations of these listed cables can be supplied with added breaking strengths, steel armor package, additional jackets, or neutrally buoyant constructions.

Xtreme-Green Cat Cables are designed to maintain their flexibility in harsh and challenging environments. These cables feature Falmat's specially formulated "Xtreme-grade" polyurethane jacket for easier payout, tighter bends, and better tractor control with extremely low coefficient of friction. The Xtreme Green Cat cables with reduced diameter offer even smaller bend radius for tighter bends and smaller, portable handling systems.



1873 DIAMOND STREET SAN MARCOS, CA 92078 U.S.A.
TEL: (760) 471-5400 FAX: (760) 471-4970 WEB: WWW.FALMAT.COM