

CAxxxx Cables

CA0001



For: LWC-L Battery (UBBL01)

Battery Connector: LEMO FGG 0B 305 CLA

Cable Length: 61 cm (24 in) nominal

Cable Type: 2 Conductor; 22 AWG; red positive, black negative

Insulation: Foil shielded black PVC

CA0002



For: UBI-2590 Battery (UBBL02)

Cable Length: 61 cm (24 in) nominal

Cable : 4 Conductor; 18 AWG

Pin/Wire Color Key: Pin 1: Black; Pin 2: White; Pin 4: Red; Pin 5: Green

Insulation: Black type SJOOW rubber

CA0005



For: UBBL03


Battery Connector: JBXFN1G05MCSDSMR

Cable Length: 61 cm (24 in) nominal

Cable : 5 Conductor; 20 AWG

Pin/Wire Color Key: Pin 1: Red; Pin 2: Green; Pin 3: White; Pin 4: Black; Pin 5 Blue

Insulation: Foil shielded black PVC



CA0006 24V



For: UBI-2590 (UBBL02) and BA-5390/U (UB0001)

Cable Length: 61 cm (24 in) nominal

Cable: 24V, 2 Conductor; 18 AWG; white positive (pin 4)
black negative (pin 2)

Insulation: Black type SJ rubber

CA0007 12V



For: UBI-2590 (UBBL02) and BA-5390/U (UB0001)

Cable Length: 61 cm (24 in) nominal

Cable: 12V, 2 Conductor; 18 AWG; white positive (pins 4 & 5)
black negative (pins 1 & 2)

Insulation: Black type SJ rubber

CA0008 12/24V



B	Black	PIN 1
W	White	PIN 2
R	Red	PIN 4
G	Gray	PIN 5

For: UBI-2590 (UBBL02) and BA-5390/U (UB0001)

Cable Length: 61 cm (24 in) nominal

Cable: 12/24V, 4 Conductor; 18 AWG; black pin 1, white pin 2,
red pin 4, gray pin 5

Insulation: Black type SJ rubber