

Product Specifications

STANDARD IQeye FEATURES

Megapixel+ Resolution	Ultra-Low Power Consumption
LIGHTGRABBER™ Low-Light 0.3 Lux Performance	12-24 VDC or 24 VAC Ready
Digital Pan/Tilt/Zoom	Power-Over-Ethernet Ready
Multi-Zone Motion Detection	Captive Screw Power Connector
Image Cropping	1/2" CS Format Lens Mount
Backlight Compensation	Cron Script Support
Hi-Speed Electronic Shutter	Java and Active X Controls
Advanced Bandwidth Management Tools	Text Overlay
Digital Exposure Window	MJPEG/JPEG Compression
Multi-Level Password Protection	Protocols - SMTP email, DHCP, BOOTP, FTP, SNMP, Telnet, TFTP, NTP, UDP, TCP, IP
Multi-Zone Privacy Masking	FTP File Server and HTTP Web Server
MD5 Password Encryption	

COMPARISON MATRIX

	IQeye501	IQeye301/302/303	IQeye601/602/603
Max Resolution	1280 x 1024	1280 x 1024 / 1600 x 1200 / 2048 x 1536	
Frame Rate at D1 (704 x 480)	30+	6	100+
Frame Rate at Max Resolution	15	1.5 / 1.0 / 0.5	30 / 20 / 12
IR/Monochrome	N/A	Optional / N/A / N/A	Optional / N/A / N/A
IQrecorder™ NVR Software	Optional - Q1,2006	Standard	
802.11b Wi-Fi Support	N/A	Optional	N/A
On Camera Storage	N/A	Optional, up to 4GB	N/A
Typical File Size at Max Resolution	80KB	80KB / 140KB / 200KB	
Output	Up to 12Mbit/sec	Up to 1.9Mbit/sec	Up to 19Mbit/sec
Multiple Independent Stream	N/A	Standard	N/A
Relay Control Alarm Interface	N/A	Standard	
Optional Smart Video Algorithms	N/A	People Counting Face Finding NightLight Fast Boot	N/A
SDK/Image Customization	N/A	Optional	N/A
Slot for Wi-Fi/Storage	N/A	Optional	N/A
Flash Memory	4MB	4MB, 8MB Optional	4MB
RAM Memory	16MB	16MB, 64MB Optional	16MB
Co-Processor	N/A	Optional	N/A
RS-232	N/A	Standard	
Relay Output	N/A	Standard	
Trigger Input	N/A	Standard	
12VDC Out	N/A	Standard	
Operating Temperature Range	0° - 40°C	-10° - 50°C	
Power over Ethernet	IEEE 802.3af ready	IQpoet ready - Requires IQpoet module	



3005 S. El Camino Real
San Clemente, CA 92672 USA
phone 1.949.369.8100 fax 1.949.369.8105

www.iqeye.com

product specifications


Product Specifications (*cont'd.*)

MODEL NUMBER	DESCRIPTION
IQ501	IQeye501 1.3 Mpix Low-Profile DPTZ IP Camera Module
IQ501D	IQeye501D 1.3 Mpix Low-Profile DPTZ IP Dome Module
IQ301	IQeye301 1.3 Mpix DPTZ Smart IP Camera Module
IQ301m	IQeye301m 1.3 Mpix DPTZ Smart IP Camera Module, Monochrome
IQ301w	IQeye301w 1.3 Mpix DPTZ Smart IP Camera Module, PC Card Slot
IQ302	IQeye302 2.0 Mpix DPTZ Smart IP Camera Module
IQ302w	IQeye302w 2.0 Mpix DPTZ Smart IP Camera Module, PC Card Slot
IQ303	IQeye303 3.1 Mpix DPTZ Smart IP Camera Module
IQ303w	IQeye303w 3.1 Mpix DPTZ Smart IP Camera Module, PC Card Slot
IQ601	IQeye601 1.3 Mpix DPTZ Hi-Speed Camera Module
IQ601m	IQeye601m 1.3 Mpix DPTZ Hi-Speed Camera Module, Monochrome
IQ602	IQeye602 2.0 Mpix DPTZ Hi-Speed Camera Module
IQ603	IQeye603 3.1 Mpix DPTZ Hi-Speed Camera Module

IQeye501

IQeye501 Camera weight (without lens) 6oz (160g)

For shipping weight information, please contact IQinVision.



IQeye300/600

IQeye300/600 camera weight (without lens) 20oz (567g)

For shipping weight information, please contact IQinVision.

