

## Smart Power High-Side-Switch

### Features

- Overload protection
- Current limitation
- Short circuit protection
- Thermal shutdown with restart
- Overvoltage protection (including load dump)
- Fast demagnetization of inductive loads
- Reverse battery protection with external resistor
- CMOS compatible input
- Loss of GND and loss of  $V_{bb}$  protection
- ESD - Protection
- Very low standby current

### Product Summary

|                        |              |        |            |
|------------------------|--------------|--------|------------|
| Overvoltage protection | $V_{bb(AZ)}$ | 62     | V          |
| Operating voltage      | $V_{bb(on)}$ | 6...52 | V          |
| On-state resistance    | $R_{ON}$     | 200    | m $\Omega$ |
| Nominal load current   | $I_{L(nom)}$ | 1.3    | A          |



**P-DSO-8**


### Application

- All types of resistive, inductive and capacitive loads
- $\mu$ C compatible power switch for 12 V, 24 V and 42 V DC applications
- Replaces electromechanical relays and discrete circuits

### General Description


N channel vertical power FET with charge pump, ground referenced CMOS compatible input, monolithically integrated in Smart SIPMOS technology. Fully protected by embedded protection functions.

## Block Diagram



| Pin | Symbol | Function                                                       |
|-----|--------|----------------------------------------------------------------|
| 1   | GND    | Logic ground                                                   |
| 2   | IN     | Input, activates the power switch in case of logic high signal |
| 3   | OUT    | Output to the load                                             |
| 4   | NC     | not connected                                                  |
| 5   | Vbb    | Positive power supply voltage                                  |
| 6   | Vbb    | Positive power supply voltage                                  |
| 7   | Vbb    | Positive power supply voltage                                  |
| 8   | Vbb    | Positive power supply voltage                                  |

## Pin configuration



**Maximum Ratings at  $T_j = 25^\circ\text{C}$ , unless otherwise specified**

| Parameter                                                                                                                                                                                                     | Symbol         | Value              | Unit             |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------|--------------------|------------------|
| Supply voltage                                                                                                                                                                                                | $V_{bb}$       | 52                 | V                |
| Supply voltage for full short circuit protection                                                                                                                                                              | $V_{bb(SC)}$   | 50                 |                  |
| Continuous input voltage                                                                                                                                                                                      | $V_{IN}$       | -10 ... +16        |                  |
| Load current (Short - circuit current, see page 5)                                                                                                                                                            | $I_L$          | self limited       | A                |
| Current through input pin (DC)                                                                                                                                                                                | $I_{IN}$       | $\pm 5$            | mA               |
| Operating temperature                                                                                                                                                                                         | $T_j$          | -40 ... +150       | $^\circ\text{C}$ |
| Storage temperature                                                                                                                                                                                           | $T_{stg}$      | -55 ... +150       |                  |
| Power dissipation <sup>1)</sup>                                                                                                                                                                               | $P_{tot}$      | 1.5                | W                |
| Inductive load switch-off energy dissipation <sup>1)2)</sup><br>single pulse, (see page 8)<br>$T_j = 150^\circ\text{C}$ , $I_L = 1\text{ A}$                                                                  | $E_{AS}$       | 125                | mJ               |
| Load dump protection <sup>2)</sup> $V_{LoadDump}^{3)} = V_A + V_S$<br>$R_I = 2\Omega$ , $t_d = 400\text{ms}$ , $V_{IN} = \text{low or high}$ , $V_A = 13.5\text{V}$<br>$R_L = 13.5\Omega$<br>$R_L = 27\Omega$ | $V_{LoadDump}$ | 73.5<br>83.5       | V                |
| <b>Electrostatic discharge voltage (Human Body Model)</b><br>according to ANSI EOS/ESD - S5.1 - 1993<br>ESD STM5.1 - 1998<br>Input pin<br>all other pins                                                      | $V_{ESD}$      | $\pm 1$<br>$\pm 5$ | kV               |

**Thermal Characteristics**

|                                                                   |              |   |    |    |     |
|-------------------------------------------------------------------|--------------|---|----|----|-----|
| Thermal resistance @ min. footprint                               | $R_{th(JA)}$ | - | 95 | -  | K/W |
| Thermal resistance @ 6 cm <sup>2</sup> cooling area <sup>1)</sup> | $R_{th(JA)}$ | - | 70 | 83 |     |

<sup>1)</sup> Device on 50mm\*50mm\*1.5mm epoxy PCB FR4 with 6 cm<sup>2</sup> (one layer, 70µm thick) copper area for drain connection. PCB is vertical without blown air. (see page 16)

<sup>2)</sup> not subject to production test, specified by design

<sup>3)</sup>  $V_{LoadDump}$  is setup without the DUT connected to the generator per ISO 7637-1 and DIN 40839 .

Supply voltages higher than  $V_{bb(AZ)}$  require an external current limit for the GND pin, e.g. with a 150Ω resistor in GND connection. A resistor for the protection of the input is integrated.

## Electrical Characteristics

| Parameter and Conditions<br>at $T_j = -40...+150^{\circ}\text{C}$ , $V_{bb} = 12..42\text{V}$ , unless otherwise specified | Symbol | Values |      |      | Unit |
|----------------------------------------------------------------------------------------------------------------------------|--------|--------|------|------|------|
|                                                                                                                            |        | min.   | typ. | max. |      |

## Load Switching Capabilities and Characteristics

|                                                                                                                                  |                |        |            |            |                        |
|----------------------------------------------------------------------------------------------------------------------------------|----------------|--------|------------|------------|------------------------|
| On-state resistance<br>$T_j = 25^{\circ}\text{C}$ , $I_L = 1\text{A}$ , $V_{bb} = 9...52\text{V}$<br>$T_j = 150^{\circ}\text{C}$ | $R_{ON}$       | -<br>- | 150<br>270 | 200<br>380 | $\text{m}\Omega$       |
| Nominal load current; Device on PCB <sup>1)</sup><br>$T_C = 85^{\circ}\text{C}$ , $T_j \leq 150^{\circ}\text{C}$                 | $I_{L(nom)}$   | 1.3    | 1.7        | -          | A                      |
| Turn-on time to 90% $V_{OUT}$<br>$R_L = 47\ \Omega$                                                                              | $t_{on}$       | -      | 80         | 180        | $\mu\text{s}$          |
| Turn-off time to 10% $V_{OUT}$<br>$R_L = 47\ \Omega$                                                                             | $t_{off}$      | -      | 80         | 200        |                        |
| Slew rate on 10 to 30% $V_{OUT}$ ,<br>$R_L = 47\ \Omega$ , $V_{bb} = 13.5\text{V}$                                               | $dV/dt_{on}$   | -      | 0.7        | 2          | $\text{V}/\mu\text{s}$ |
| Slew rate off 70 to 40% $V_{OUT}$ ,<br>$R_L = 47\ \Omega$ , $V_{bb} = 13.5\text{V}$                                              | $-dV/dt_{off}$ | -      | 0.9        | 2          |                        |

## Operating Parameters

|                                                                                                                                           |                 |        |        |          |               |
|-------------------------------------------------------------------------------------------------------------------------------------------|-----------------|--------|--------|----------|---------------|
| Operating voltage                                                                                                                         | $V_{bb(on)}$    | 6      | -      | 52       | V             |
| Undervoltage shutdown of charge pump<br>$T_j = -40...+85^{\circ}\text{C}$<br>$T_j = 150^{\circ}\text{C}$                                  | $V_{bb(under)}$ | -<br>- | -<br>- | 4<br>5.5 |               |
| Undervoltage restart of charge pump                                                                                                       | $V_{bb(u\ cp)}$ | -      | 4      | 5.5      |               |
| Standby current<br>$T_j = -40...+85^{\circ}\text{C}$ , $V_{IN} = \text{low}$<br>$T_j = +150^{\circ}\text{C}^{2)}$ , $V_{IN} = \text{low}$ | $I_{bb(off)}$   | -<br>- | -<br>- | 15<br>18 | $\mu\text{A}$ |
| Leakage output current (included in $I_{bb(off)}$ )<br>$V_{IN} = \text{low}$                                                              | $I_{L(off)}$    | -      | -      | 5        |               |
| Operating current<br>$V_{IN} = \text{high}$                                                                                               | $I_{GND}$       | -      | 0.8    | 2        | $\text{mA}$   |

<sup>1</sup>Device on 50mm\*50mm\*1.5mm epoxy PCB FR4 with 6 cm<sup>2</sup> (one layer, 70μm thick) copper area for drain connection. PCB is vertical without blown air. (see page 16)

<sup>2</sup>higher current due temperature sensor

## Electrical Characteristics

| Parameter and Conditions                                                                                                                                                                                                                                                                                                     | Symbol                     | Values           |                                  |                  | Unit               |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|------------------|----------------------------------|------------------|--------------------|
|                                                                                                                                                                                                                                                                                                                              |                            | min.             | typ.                             | max.             |                    |
| at $T_j = -40...+150^{\circ}\text{C}$ , $V_{bb} = 12..42\text{V}$ , unless otherwise specified                                                                                                                                                                                                                               |                            |                  |                                  |                  |                    |
| Protection Functions <sup>1)</sup>                                                                                                                                                                                                                                                                                           |                            |                  |                                  |                  |                    |
| Initial peak short circuit current limit (pin 5 to 3)<br>$T_j = -40\text{ }^{\circ}\text{C}$ , $V_{bb} = 20\text{ V}$ , $t_m = 150\text{ }\mu\text{s}$<br>$T_j = 25\text{ }^{\circ}\text{C}$<br>$T_j = 150\text{ }^{\circ}\text{C}$<br>$T_j = -40...+150\text{ }^{\circ}\text{C}$ , $V_{bb} > 40\text{ V}$ , ( see page 11 ) | $I_{L(\text{SCp})}$        | -<br>-<br>4<br>- | -<br>6.5<br>-<br>5 <sup>2)</sup> | 9<br>-<br>-<br>- | A                  |
| Repetitive short circuit current limit<br>$T_j = T_{jt}$ (see timing diagrams)<br>$V_{bb} < 40\text{ V}$<br>$V_{bb} > 40\text{ V}$                                                                                                                                                                                           | $I_{L(\text{SCr})}$        | -<br>-           | 6<br>4.5                         | -<br>-           |                    |
| Output clamp (inductive load switch off)<br>at $V_{\text{OUT}} = V_{bb} - V_{\text{ON}(\text{CL})}$ ,<br>$I_{bb} = 4\text{ mA}$                                                                                                                                                                                              | $V_{\text{ON}(\text{CL})}$ | 59               | 63                               | -                | V                  |
| Overvoltage protection <sup>3)</sup><br>$I_{bb} = 4\text{ mA}$                                                                                                                                                                                                                                                               | $V_{bb(\text{AZ})}$        | 62               | -                                | -                |                    |
| Thermal overload trip temperature                                                                                                                                                                                                                                                                                            | $T_{jt}$                   | 150              | -                                | -                | $^{\circ}\text{C}$ |
| Thermal hysteresis                                                                                                                                                                                                                                                                                                           | $\Delta T_{jt}$            | -                | 10                               | -                | K                  |

## Reverse Battery

|                                                                                  |           |   |     |    |    |
|----------------------------------------------------------------------------------|-----------|---|-----|----|----|
| Reverse battery <sup>4)</sup>                                                    | $-V_{bb}$ | - | -   | 52 | V  |
| Drain-source diode voltage ( $V_{OUT} > V_{bb}$ )<br>$T_j = 150^{\circ}\text{C}$ | $-V_{ON}$ | - | 600 | -  | mV |

<sup>1)</sup>Integrated protection functions are designed to prevent IC destruction under fault conditions described in the data sheet. Fault conditions are considered as "outside" normal operating range. Protection functions are not designed for continuous repetitive operation.

<sup>2)</sup>not subject to production test, specified by design


<sup>3)</sup> see also  $V_{ON(CL)}$  in circuit diagram on page 7

<sup>4)</sup>Requires a  $150\text{ }\Omega$  resistor in GND connection. The reverse load current through the intrinsic drain-source diode has to be limited by the connected load. Power dissipation is higher compared to normal operating conditions due to the voltage drop across the drain-source diode. The temperature protection is not active during reverse current operation! Input current has to be limited (see max. ratings page 3).


**Electrical Characteristics**

| Parameter and Conditions<br>at $T_j = -40...+150^{\circ}\text{C}$ , $V_{bb} = 12..42\text{V}$ , unless otherwise specified | Symbol                    | Values |      |      | Unit             |
|----------------------------------------------------------------------------------------------------------------------------|---------------------------|--------|------|------|------------------|
|                                                                                                                            |                           | min.   | typ. | max. |                  |
| Input                                                                                                                      |                           |        |      |      |                  |
| Input turn-on threshold voltage                                                                                            | $V_{\text{IN(T+)}}$       | -      | -    | 2.2  | V                |
| Input turn-off threshold voltage                                                                                           | $V_{\text{IN(T-)}}$       | 0.8    | -    | -    |                  |
| Input threshold hysteresis                                                                                                 | $\Delta V_{\text{IN(T)}}$ | -      | 0.4  | -    |                  |
| Off state input current<br>$V_{\text{IN}} = 0.7\text{ V}$                                                                  | $I_{\text{IN(off)}}$      | 1      | -    | 25   | $\mu\text{A}$    |
| On state input current<br>$V_{\text{IN}} = 5\text{ V}$                                                                     | $I_{\text{IN(on)}}$       | 3      | -    | 25   |                  |
| Input resistance (see page 7)                                                                                              | $R_{\text{I}}$            | 2      | 3.5  | 5    | $\text{k}\Omega$ |

## Terms




## Inductive and overvoltage output clamp




$V_{ON}$  clamped to 59V min.

## Input circuit (ESD protection)




The use of ESD zener diodes as voltage clamp at DC conditions is not recommended

## Overvoltage protection of logic part




$V_{Z1}=6.1V$  typ.,  $V_{Z2}=V_{bb(AZ)}=62V$  min.,  
 $R_I=3.5\text{ k}\Omega$  typ.,  $R_{GND}=150\Omega$

## Reverse battery protection




$R_{GND}=150\Omega$ ,  $R_I=3.5\text{ k}\Omega$  typ.,  
 Temperature protection is not active during inverse current

## Internal output pull down




$R_O = 200\text{ k}\Omega$  typ.


### GND disconnect




### GND disconnect with GND pull up



### V<sub>bb</sub> disconnect with charged inductive load



### Inductive Load switch-off energy dissipation



Energy stored in load inductance:  $E_L = \frac{1}{2} * L * I_L^2$

While demagnetizing load inductance,  
the energy dissipated in PROFET is

$E_{AS} = E_{bb} + E_L - E_R = V_{ON(CL)} * i_L(t) dt$ ,  
with an approximate solution for  $R_L > 0\Omega$ :


$$E_{AS} = \frac{I_L * L}{2 * R_L} * (V_{bb} + |V_{OUT(CL)}|) * \ln(1 + \frac{I_L * R_L}{|V_{OUT(CL)}|})$$



**Typ. transient thermal impedance**

$Z_{thJA}=f(t_p)$  @ 6cm<sup>2</sup> heatsink area


Parameter:  $D=t_p/T$



**Typ. transient thermal impedance**


$Z_{thJC}=f(t_p)$  @ min. footprint

Parameter:  $D=t_p/T$




**Typ. on-state resistance**

$R_{ON} = f(T_j)$  ;  $V_{bb} = 13,5V$  ;  $V_{in} = \text{high}$




**Typ. on-state resistance**

$R_{ON} = f(V_{bb})$  ;  $I_L = 1 A$  ;  $V_{in} = \text{high}$




**Typ. turn on time**

$$t_{on} = f(T_j); R_L = 47\Omega$$




**Typ. turn off time**

$$t_{off} = f(T_j); R_L = 47\Omega$$




**Typ. slew rate on**

$$dV/dt_{on} = f(T_j); R_L = 47\Omega$$




**Typ. slew rate off**

$$dV/dt_{off} = f(T_j); R_L = 47\Omega$$




**Typ. standby current**

$$I_{bb(off)} = f(T_j) ; V_{bb} = 42V ; V_{IN} = \text{low}$$




**Typ. leakage current**

$$I_{L(off)} = f(T_j) ; V_{bb} = 42V ; V_{IN} = \text{low}$$




**Typ. initial peak short circuit current limit**

$$I_{L(SCp)} = f(V_{bb})$$



**Typ. initial short circuit shutdown time**


$$t_{off(SC)} = f(T_{j,start}) ; V_{bb} = 20V$$



### Typ. input current


$I_{IN(on/off)} = f(T_j)$ ;  $V_{bb} = 13,5V$ ;  $V_{IN} = \text{low/high}$

$V_{INlow} \leq 0,7V$ ;  $V_{INhigh} = 5V$




### Typ. input threshold voltage

$V_{IN(th)} = f(T_j)$ ;  $V_{bb} = 13,5V$




### Typ. input current

$I_{IN} = f(V_{IN})$ ;  $V_{bb} = 13.5V$




### Typ. input threshold voltage

$V_{IN(th)} = f(V_{bb})$ ;  $T_j = 25^{\circ}C$




### Maximum allowable load inductance for a single switch off

$L = f(I_L)$ ;  $T_{jstart}=150^{\circ}\text{C}$ ,  $R_L=0\Omega$




### Maximum allowable inductive switch-off energy, single pulse

$E_{AS} = f(I_L)$ ;  $T_{jstart} = 150^{\circ}\text{C}$ ,  $V_{bb} = 13,5\text{V}$




## Timing diagrams


**Figure 1a:** V<sub>bb</sub> turn on:




**Figure 2b:** Switching a lamp,




**Figure 2a:** Switching a resistive load, turn-on/off time and slew rate definition



**Figure 2c:** Switching an inductive load




**Figure 3a:** Turn on into short circuit, shut down by overtemperature, restart by cooling




Heating up of the chip may require several milliseconds, depending on external conditions.

**Figure 4:** Overtemperature:  
Reset if  $T_j < T_{jt}$



**Figure 5:** Undervoltage restart of charge pump



## Package and ordering code


all dimensions in mm

Package:

Ordering code:

P-DSO-8-6

Q67060-S7307



Published by  
**Infineon Technologies AG,**  
 St.-Martin-Strasse 53,  
 D-81669 München  
 © Infineon Technologies AG 2001  
 All Rights Reserved.

### Attention please!

The information herein is given to describe certain components and shall not be considered as a guarantee of characteristics.

Terms of delivery and rights to technical change reserved.

We hereby disclaim any and all warranties, including but not limited to warranties of non-infringement, regarding circuits, descriptions and charts stated herein.

Infineon Technologies is an approved CECC manufacturer.


### Information

For further information on technology, delivery terms and conditions and prices please contact your nearest Infineon Technologies Office in Germany or our Infineon Technologies Representatives worldwide (see address list).

### Warnings

Due to technical requirements components may contain dangerous substances. For information on the types in question please contact your nearest Infineon Technologies Office.

Infineon Technologies Components may only be used in life-support devices or systems with the express written approval of Infineon Technologies, if a failure of such components can reasonably be expected to cause the failure of that life-support device or system, or to affect the safety or effectiveness of that device or system. Life support devices or systems are intended to be implanted in the human body, or to support and/or maintain and sustain and/or protect human life. If they fail, it is reasonable to assume that the health of the user or other persons may be endangered.



Printed circuit board (FR4, 1.5mm thick, one layer 70µm, 6cm<sup>2</sup> active heatsink area) as a reference for max. power dissipation  $P_{tot}$  nominal load current  $I_{L(nom)}$  and thermal resistance  $R_{thja}$