



Ref. Des.	Mfgr.	Mfgr. P/N	Description
P1	Seacon	MINK-10L-CCP	Mini-Con 10-Pin 2 #14/8 #20 (10 #20) Cable Connector Plug
P2	Subconn	MCIL8M	Micro In-Line 8-pin Male Circular
--	Seacon	???	Stock 10-conductor 20AWG S0 cable
--	Subconn	MCDLSF	Delrin Locking Sleeve for P2

1. Conductors to meet or exceed 300VDC isolation
2. Part number: 1003157
3. Cable splice joint may be located anywhere along cable length
4. All lengths are +2.0" - 0.5"
5. All dimensions are in inches unless otherwise noted.
6. Mark part number, current rev letter and config (i.e. 1003013A-001)
7. Mark cable end reference designator
8. Mark cable end reference designator

A	05/10/2006	Initial Release
Rev.	Date	Description
Monterey Bay Aquarium Research Institute 7700 Sandholdt Rd., Moss Landing, CA 95039-9644		
Title Cable, Docking AUV USBL to FAU Payload Unit		
Size B	Document Number 1003158	Rev A
Date:	Wednesday, May 10, 2006	Sheet 1 of 1

Copyright © 2006 MBARI

All information herein is considered proprietary and may not be copied, duplicated, or transmitted without the express permission of Monterey Bay Aquarium Research Institute.