

To Battery
Sphere

1	Burnwire1 +	18 AWG	RED
2		24 AWG CAT5	BRN
3		24 AWG CAT5	WHT/BRN
4		24 AWG CAT5	BLU
5		24 AWG CAT5	WHT/BLU
6		24 AWG CAT5	GRN
7		24 AWG CAT5	WHT/GRN
8		18 AWG	BLU
9		18 AWG	WHT
10	Seawater GND	18 AWG	BLK

Falmat FMXCAT51806K12 Green PU Jacket Cable

Seacon
MINK10L CCP Ti
Female



Seacon
MINK10
CCPL Ti

Falmat FMXCAT51806
Green PU Jacket Cable
0.5" diameter

Title		
Benthic Rover: LF Modem Burnwire Cable		
Size A	Document Number <Doc>	Rev <RevCo>
Date:	Monday, March 08, 2010	Sheet 1 of 1