

J3 - Serial Connector

Connector: 7-pin socket strip: 0.025" square pins on 0.1" centers.
(SAMTEC TSW-107-07-SS)

Mating Connectors: SAMTEC SSW-107-01-SS for providing connections for one add-on board.

SAMTEC SSQ-107-03-GS will mate with J3 and provide a new socket strip matching J3 on the opposite side of an add on board (for stackable add-on boards)

Connections:	E	connection from pin 'to E' on J2
	RSPOW	power input to RS-232 drivers
	(-5)	-5 volts (if +5 applied to RSPOW)
	'1'	spare RS-232 driver output when RSPOW tied to +5
	'2'	spare RS-232 receiver input when RSPOW tied to +5
	'3'	spare RS-232 receiver out when RSPOW tied to +5
	'4'	spare RS-232 driver input when RSPOW tied to +5

See Also: "UART" for details on the connections made to this connector.