



J2-3
MINK-19-CCP



CCP FACE VIEW

- 1 TP 20AWG ORG
- 2 TP 20AWG BLU
- 3 20AWG GRN
- 4 COAX#1 SHLD
- 5 TP 20AWG GRY
- 6 TINNED CU DRAIN
- 7 TRIAD 22AWG RED
- 8 COAX#1 CORE
- 9 COAX#2 SHLD
- 10 TP 20AWG BRN
- 11 TRIAD 22AWG BLK & TRIAD SHLD
- 12 TRIAD 22AWG WHT
- 13 COAX#2 CORE
- 14 COAX#3 SHLD
- 15 COAX#4 SHLD
- 16 COAX#5 SHLD
- 17 COAX#3 CORE
- 18 COAX#4 CORE
- 19 COAX#5 CORE

INSITE DIGITAL STILL
MINK-19-CCP



CCP FACE VIEW

USE 17 FT MBARI SUPPLIED CABLE
FALMAT FM072-895 REV A
BLUE PU JACKET
SEE ATTACHED SPECIFICATION

NOTE: TRIAD IS ACTUALLY SHIELDED,
ATTACH TO PIN 11 WITH TRIAD BLACK

MBARI - Moss Landing, CA - (831) 775-1700			
Title		JB2-3 WET CABLE ASSEMBLY (INSITE SCORPIO STILL CAMERA)	
Size A	Document Number DR0020	Rev 2	
Date:	Friday, January 21, 2011	Sheet	1 of 1