

PSU 203

Adjustable Voltage Twin Rail Power Supply

The PSU 203 is a compact, split 'open' mains power supply unit designed primarily for OEM use. The linear regulator ICs used have over-current and over-temperature protection.


- Simple Screw-terminal Connection
- Low Profile
- Isolated Mains Transformer
- Positive and Negative Adjustable Rails
- 20-Turn Trimmers For Accurate Setting



Standard Unit				Stock Number
Specification				PSU 203
		Min.	Typ.	Max.
Load regulation				1 %
Line regulation				1 %
Ripple				0.5 mV
Operating temperature		0		70 °C
Output				
Positive	V	5		15 V
	I			150 mA
Negative	V	-5		-15 V
	I			-150 mA
Input (50-60Hz)		110	120	125 VAC
- link selectable		220	240	250


Derating Curve

The hotter the unit becomes the lower the current that may be taken from it. Enclosures should be adequately ventilated if necessary and power supplies should not be mounted upside down.



Selecting Mains I/P Voltage


The unit is normally supplied connected for 240V operation. For 120V operation remove 240V link and insert BOTH 120V links.



Safety

For safe operation, the unit must be installed in an enclosure which prevents accidental contact with hazardous voltages, by providing appropriate insulation or guarding. If the enclosure is made of a conducting material or the internal surfaces have a conductive coating, ensure that no part of the power supply will come into contact with it, and maintain an air gap clearance of minimum 10mm. Two terminals (E) are provided as anchorage for earth leads. The mains lead to the unit must be fused with either 1A (240V operation) or 2A (120V operation) fuse. In general, it is the responsibility of the user to ensure that the incorporation of the power supply unit into the OEM equipment conforms to the relevant sections of EN 60742, in accordance with the Low Voltage Directive (LVD 93/68/EEC).

IF IN DOUBT CONTACT AN APPLICATIONS ENGINEER.



Specifications liable to change without prior warning

PSU 203

Issue 5

August/1997

M.C.

Applies to PSU 203/4



LASCAR ELECTRONICS LTD.
MODULE HOUSE, WHITEPARISH,
WILTSHIRE, SP5 2SJ UK
TEL: ++44 (1794) 884567

FAX: ++44 (1794) 884616

LASCAR ELECTRONICS INC.
PO BOX 8204, SAVANNAH,
GA 31412 USA
TEL: ++1 (912) 234 2048

FAX: ++1 (912) 234 2049