

ITEM=INCAND LT, CONNECTOR= IMPULSE, IL-3-FS, QTY=1

PIN # CABLE=YEL POLY (P/N FM051-597-A)

|   |        |      |
|---|--------|------|
| 1 | 110VAC | BLUE |
| 2 | 110VAC | YEL  |
| 3 | FRAME  | GRN  |

ITEM=DVL, CONNECTOR= IMPULSE, LPMIL-7-FS, QTY=1

PIN # CABLE=ORG POLY (P/N FM102-495C REVB)

|   |         |      |
|---|---------|------|
| 1 | 232 RX  | GRY  |
| 2 | 232 TX  | BLUE |
| 3 | +48VDC  | RED  |
| 4 | 232 COM | YEL  |
| 5 |         | N/C  |
| 6 |         | N/C  |
| 7 | 0V      | BLK  |

ITEM=SCHILLING T2, CONNECTOR= IMPULSE, LPIL-9-FS, QTY=1

PIN # CABLE=ORG POLY (P/N FM102-495C REVB)

|   |         |      |
|---|---------|------|
| 1 | +48VDC  | RED  |
| 2 |         | N/C  |
| 3 | 0V      | BLK  |
| 4 | 232 TX  | BLUE |
| 5 | 232 RX  | GRY  |
| 6 | 232 COM | YEL  |
| 7 |         | N/C  |
| 8 |         | N/C  |
| 9 |         | N/C  |

ITEM=HMI LT/BAL, CONNECTOR= IMPULSE, LPIL-3-FS TO

LPIL-3-MP, QTY=4 CABLE=YEL POLY (P/N FM051-597-A)

PIN #

|   |  |   |      |
|---|--|---|------|
| 1 |  | 1 | BLUE |
| 2 |  | 2 | YEL  |
| 3 |  | 3 | GRN  |

ITEM=HMI BALLAST, CONNECTOR= IMPULSE, LPIL-5-FS , QTY=4

PIN # CABLE=YEL POLY (P/N FM051-597-A)

|   |  |      |
|---|--|------|
| 1 |  | BLUE |
| 2 |  | YEL  |
| 3 |  | GRN  |
| 4 |  | RED  |
| 5 |  | BLK  |