

ITEM=OCTANS, CONNECTOR= SUBCON, MCIL16, QTY=1
 PIN # CABLE=ORG POLY (P/N FM102-495C REV B)

1	_____	+24VDC	RED
2	_____	0V	BLK
12	_____	SIG COM	YEL
14	_____	232 TX	BLUE
15	_____	232 RX	GRY
16	_____	GND	

ITEM=RESPONDER, CONNECTOR= SUBCON, MCIL5F, QTY=1
 PIN # CABLE=ORG POLY (P/N FM102-495C REV B)

1	_____	TRIGGER	BLUE
2	_____	0V	BLK
3	_____		GRY
4	_____	EXT +24VDC	RED
5	_____		N/C

ITEM=CTD, CONNECTOR= SUBCON, MCIL4F, QTY=1
 PIN # CABLE=ORG POLY (P/N FM102-495C REV B)

1	_____	COM	BLK
2	_____	232 RX	GRY
3	_____	232 TX	BLUE
4	_____	+24VDC	RED

ITEM=MODEM, CONNECTOR= SUBCON, MCIL6F, QTY=1
 PIN # CABLE=ORG POLY (P/N FM102-495C REV B)

1	_____	0V	BLK
2	_____	+24VDC	RED
3	_____	232 COM	YEL
4	_____	232 RX	GRY
5	_____	232 TX	BLUE
6	_____		N/C

ITEM=OXYGEN SEN, CONNECTOR= SUBCON, MCIL4F, QTY=1
 PIN # CABLE=ORG POLY (P/N FM102-495C REV B)

1	_____	+12VDC	ORG
2	_____	232 TX	BLUE
3	_____	232 RX	GRY
4	_____	0V	BLK