



1873 Diamond Street
San Marcos, CA 92069 U.S.A.
Tel: (760) 471-5400 (800) 848-4257
Fax: (760) 471-4970
Website: www.falmat.com

Technical Data Sheet

PART NUMBER: FM102-495C REV B **ISSUED ON:** 6/1/2007

DESCRIPTION: Custom Cable

CUSTOMER: **Monterey Bay Aquarium**

SCOPE: The cable consists of 7ea. 20awg conductors, Water Blocked, An overall Tinned Copper Braid Shield, and Polyurethane Jacket.

CONDUCTORS: 20awg, Stranded Silver Plated Copper.

INSULATION: Teflon

COMPONENTS: 7ea. #20awg conductors cabled together with Water Block in all interstices.

BINDER: An overall Clear Tape.

SHIELD: Tinned Copper Braid, 85% min. coverage.

JACKET: 0.065" wall Orange Polyurethane Jacket.
Surface Printing: "MFD BY FALMAT INC. FOR MBARI (TIBURON) P/N FM102-495C REV B"

OD: 0.325" nominal.

This document contains proprietary information and can not be copied or reproduced in part or in whole nor information disclosed to others for manufacturing or other purposes except as specifically authorized in writing by Falmat, Inc.