


RF-700C1 Combo	
COMBO	Specifications
PRODUCTS	Transmitter Power: 100 MW R.F. Output
	Transmitter Output Signal: Pulsed 1 KHZ FM
	Transmitter Duty Cycle: Approx. 13%, 2 sec. on, 15 sec. off
	Harmonics: -37 db.
	Frequency Range: 4 channels, 154.585, 159.480, 160.725, 160.785 MHZ
	Transmitter Range: 3 to 6 miles to a vessel, up to 15 miles to an aircraft
	FCC Identification: FOX4ZLR700C
	Antenna: Low profile dome
	Flash Tube: Replaceable - rated for 6 X 10^6 flashes
	Intensity: 15 candelas
Overview	Range (flasher): Approx. 2 nm.
	Flash Rate: 40/minute
	Daylight Off Switch: Turns flasher ON @ 55 LUX Turns flasher OFF @ 65 LUX
	Batteries: 4 "D" cell alkaline
	Battery Life (4 cell case): Approx. 8 days @ 4° C
	Operating Temperature Range: -40°C to +60°C
	Ocean Depth Rating: Approx. 2,000 ft. (600 m)
	Materials:
	Case: Anodized Aluminum 6061-T6
	Cap: Polycarbonate
Dimensions	Flotation Collar: High Density Foam
	Weight with Batteries: 3.3 lb. (1.5 Kg)
Uses	
• Ocean current studies • Locate moored or drifting oceanographic equipment • Datum marker in search and rescue applications • Locate fishing gear, crab pots, long lines • Study drift patterns of surface pollution • Locate fuel depots in Artic or Antarctic • Archaeological exploration	



[HOME](#)
[NEWS](#)

[Agents](#)
[Xenon Flashers](#)

[Manuals](#)
[Radio Beacons](#)

[Contact Us](#)
[D. F. Receiver](#)



NOVATECH DESIGNS LTD.

271 Brownlow Ave. Dartmouth, N.S., Canada B3B 1W6

[email:sales@novatechdesigns.com](mailto:sales@novatechdesigns.com)

Tel: (902) 468-7275 Fax: (902) 481-5538

Toll Free: (877) 772-3389 Toll Free: (877) 981-4123