

DESCRIPTION	Job #
Ethernet Cable - consists of 4 ea. twisted pairs 24 AWG, Water Block overall, Aluminum Mylar, Tinned Copper Braid, Adhesive Clear Tape, and PUR jacket, Jacket - 0.055" wall press extrude black polyurethane jacket, Finished OD - 0.410" +/- .010" Color Code: #1 TP = Brown + White/ Brown Stripe with Lay 0.500" #2 TP = Blue + White/Blue Stripe with Lay 0.600" #3 T = Orange + White/Orange Stripe with Lay 0.700" #4 TP = Green + White/Green Stripe with Lay 0.800" Replaces Fishbowl 4401	
	Total