

BIAUV Interface Board- April 19, 2011

Matchport I/O Assignments

Pin Name	I/O	Controls	Active State
CP0	output	Shutter trigger	Active low
CP1	output	nothing	
CP2	output	laser disable	Active high
CP3	input	humidity (HI = above 50%)	
CP4	output	Camera Vicor disable	Active high
CP5	output	Strobe Vicor disable	Active high
CP6	output	NC	
CP7	NC	NC	