

Microreader with 85mm Disk Antenna



Tag	Read Range
12mm wedge transponder	3 in.
23mm glass transponder	4 in.
32mm glass transponder	5.5 in.
24mm circular inlay	6 in.
30mm disk transponder	7 in.
Card transponder	7 in.
85mm disk transponder	11.5 in.
120mm cylindrical transponder	13 in.

Microreader with 30mm disk antenna



Tag	Read Range
12mm wedge transponder	1.5 in.
23mm glass transponder	2.75 in.
32mm glass transponder	3.25 in.
24mm circular inlay	3.25 in.
30mm disk transponder	4 in.
Card transponder	4 in.
85mm disk transponder	6.5 in.
120mm cylindrical transponder	7 in.