




GigaBlox

Small 5 port Gigabit Ethernet Switch

Applies to:

MPN: BB-GGB-C-1

MPN: BB-GGB-C-CO1

MPN: BB-GGB-C-CO2

Datasheet

May 2024

Board revision C

Contents

Contents	2
1 General Information	3
1.1 Functionality and Features of GigaBlox	3
1.2 Safety Information	4
1.3 Block Diagram	5
1.4 Included Equipment	5
1.5 RoHS Certification of Compliance	5
2 Hardware Interfaces	6
2.1 Board Map	6
2.2 Connectors and Pinouts	7
2.2 Other Interfaces	10
3 Software Interfaces	11
4 Device Configuration	11
4.1 Unmanaged Switch	11
4.2 Managed Switch	11
5 Device Characteristics	12
5.1 Operating Conditions	12
6 Known Hardware Bugs	13
6.1 Bug BB-GGB-C-CO1:0001	13
7 Datasheet Changelog	14
8 Contact	14
9 Declaration of Conformity	15

1 General Information

1.1 Functionality and Features of GigaBlox

The BotBlox GigaBlox is a small form factor 5 port 10/100/1000Mbps (10BASE-T/100BASE-TX/1000BASE-T) layer 2 unmanaged ethernet switch. It has a non-blocking fabric, meaning that 1000Mbps speed can be achieved simultaneously on all ports.

It runs from a wide input voltage range of 5.1 to 60V allowing integration into a wide range of applications.

1.1.1 Features

- 5 x 10/100/1000M (10BASE-T/100BASE-TX/1000BASE-T) ethernet ports
- Input voltage range from 5.1 to 60V
- 45mm x 45mm board size
- Molex Picoblade connectors for power and ports
- Automatic MDI-X crossover
- Auto-negotiation with connected devices to achieve maximum speed
- Unmanaged (out-the-box) functionality

1.1.2 General Information

Voltage Input	5.1V to 60V DC (65V absolute max)
Supported Protocols	10BASE-T, 100BASE-TX, 1000BASE-T
Power Consumption	260mW (idle) to 1100mW (full switching)
Weight	18 grams
Size	45mm x 45mm x 15.98mm
Operating Temperature	-20°C to +85°C
Storage Temperature	-40°C to +100°C

Table 1: General Information

1.1.3 General Operating Instructions

GigaBlox is designed for use in commercial and industrial environments, operating from a nominal supply voltage of 24V, but with the ability to operate from as low as 5.1V and as high as 60V.

GigaBlox can be operated immediately by following the steps below.

- 1) Apply a voltage between 5.1V to 60V to the voltage input terminals.
- 2) Connect external devices to the ethernet ports using RJ45 to Picoblade cables.
- 3) GigaBlox will automatically begin auto negotiation with connected devices and begin receiving and forwarding packets to/from all connected devices.

There is no managed mode on GigaBlox, it can only operate as an unmanaged switch.

1.2 Safety Information

- This device can operate on voltages near and above 60V. Please read this manual before operating.
- This device is provided “as is”. In-application testing prior to integration is recommended.
- This device is provided as an electronic circuit board, and requires integration into chassis for full ingress protection.
- Do not use this product in wet environments without integrating into a chassis.
- Do not operate this product beyond the rated temperature and voltages.

1.3 Block Diagram




Figure 1: GigaBlox Block Diagram

1.4 Included Equipment

The product includes the following:

- 1 x GigaBlox board
- 5 x Molex Picoblade to RJ45 8-way Unshielded Twisted Pair cables (300mm)
- 1 x Molex Picoblade to bare, tinned leads (300mm)

1.5 RoHS Certification of Compliance

The BotBlox GigaBlox complies with the RoHS (Restriction of Hazardous Substances Directive) Certificate of Compliance.

2 Hardware Interfaces

2.1 Board Map




Figure 2: GigaBlox Board Map (front)




Figure 3: GigaBlox Board Map (back)

2.2 Connectors and Pinouts

2.1.1 Voltage Input

The bottom left connector is the voltage input terminal. A four pin connector is used to allow the input voltage to be easily daisy chained between boards (two wires per power rail).

The voltage input has the following features:

- Voltage input can range from 5 to 60V
- Maximum allowable voltage of 65V

The pinout of the voltage input connector is shown in figure 4 below.




Figure 4: Voltage input header pinout

Connector part numbers

Connector on board	Mating header	Crimp used	Wire used
530470410	0510210400	500798000	UL1061, 28AWG

Table 2: Voltage input connector pinout and part numbers

Cable pinout




Figure 5: Voltage input cable pinout (red = V+, black = GND)

2.1.2 Ethernet Ports

There are five ethernet connectors on GigaBlox. Each connector has eight pins corresponding to the four signals required for 1000BASE-T which are A+, A-, B+, B-, C+, C-, D+ and D-. The pin mapping of all five connectors is identical.



Figure 6: Ethernet port pinout

Connector on board	Mating header	Crimp used	Wire used
530470810	0510210800	500798000	UL1061, 28AWG

Table 3: Ethernet connector pinout and part numbers

Cable pinout

Cable 1
8p Picoblade to RJ-45 300mm




Figure 7: Ethernet cable pinout

Compatibility with SwitchBlox Cables

GigaBlox can be used with 4 pin SwitchBlox cables at 10/100M speed by plugging the SwitchBlox cables into the right-hand side of the 8 pin connector.

This is because the right-most signals on the GigaBlox 8 pin headers are the A- (Tx-), A+ (Tx+), B- (RX-) and B+ (RX+) signals, which are all that are needed for 10/100Mbps.

2.1.3 LED Header

GigaBlox has a header on the back of the board that allows the port activity indication signals to be broken out to power external LEDs. This connector contains 5 LED port activity signals, 3.3V and GND. The pinout is shown below.




Figure 8: LED connector Pinout

75Ω resistors are integrated directly into the board in series with the LED signals. This means using external LEDs without resistors is possible with most standard LEDs. The current in each LED in this case is 44mA ($3.3V \div 75\Omega$). External resistors can be placed in series with the Px LED signals to further reduce current flow.

The LED signals for ports 1,3 and 5 pull low on link activity, meaning they must be connected to the cathode of the external LED. Conversely the LED signals for ports 2 and 4 pull high on link activity, meaning they must be connected to the anode of the external LED. Below is an example connection diagram.




Figure 9: External LED connections

All five external LEDs can be connected in this way.

The table below shows the MPN of the connector used on the board and the associated information for the mating header.

Connector on board	Mating header	Crimp used	Wire used
0532610771	0510210700	500798000	UL1061, 28AWG

Table 4: Ethernet connector pinout and part numbers

For the avoidance of doubt, the diagram below shows the pinout used on a cable that would mate with the external LED connector; LEDs could then be soldered directly to the tinned leads of this cable. The internal part number of this cable is BB-PBTL1-7-0.4.




Figure 10: Example external cable showing LED connector pinout.

2.2 Other Interfaces

2.2.1 Onboard LEDs

There are 6 LEDs on GigaBlox in total.

The 3V3 Power Indicator LED (**Green**) indicates that voltage is present on the 3V3 line. It should be solid green in normal operation.

Each Port Activity LED (**Red/Green**) corresponds to a specific port. They indicate activity on each port and will blink when there is traffic on a port. The color of the LED indicates the link speed, with **Red** meaning 10/100M speed, and **Green** meaning 1G speed. They should be solid off when a port is not connected to any device, and they should blink under normal operation. A solid LED indicates either constant traffic, or a fault with the port.

3 Software Interfaces

There is currently no software interface on GigaBlox. It functions solely as an unmanaged switch.

4 Device Configuration

4.1 Unmanaged Switch

To use GigaBlox in an unmanaged application requires no configuration. Simply connect a voltage to the voltage input and connect downstream devices.

4.2 Managed Switch

Operating GigaBlox as a managed switch is not possible at present.

5 Device Characteristics

5.1 Operating Conditions

5.1.1 Absolute Maximum Ratings

Operating in these ranges will reduce the lifetime of the device.

Voltage Input Maximum	65V
Storage Temperature	-40°C +100°C
Operating Temperature	-20°C to 85°C

Table 5: Operating Conditions

6 Known Hardware Bugs

6.1 Bug BB-GGB-C-CO1:0001

6.1.1 Affected boards

GigaBlox, all revisions

6.1.2 Description

Identical ports on two GigaBlox that are powered on at the same time will not establish a link.

6.1.3 Reproduction steps

Power on two GigaBlox at the same time and use an interconnect cable to connect two identical ports on each GigaBlox to each other (e.g. port 1 to port 1 or port 2 to port 2, etc). The ports will not connect. This only occurs when two GigaBlox are powered on at the same time. If the GigaBlox are powered on at different times, the ports will establish a connection.

6.1.4 Solution/Workaround

When connecting two GigaBlox together directly, use different ports on each GigaBlox.

7 Datasheet Changelog

Date	Datasheet Version	Author	Notes
04/01/2021	C_A	Josh Elijah	Initial release
03/06/2021	C_B	Josh Elijah	Added bug sections - Auto Negotiation on identical ports bug added
25/06/2022	C_C	Josh Elijah	Added external LED breakout header information
10/03/2023	C_D	Josh Elijah	Updated operating temperature range from 70°C to 85°C
25/10/2023	C_E	Jaclyn Li	Table 1.1.2 General Information and Table 5.1.1 Operating Conditions updated to be correct values.
01/05/2024	C_F	Jaclyn Li	Updated operating temperature range from 0°C to -20°C
08/14/2024	C_G	Anj Rojo	Updated MPN to BB-GGB-C-CO1
11/12/2024	C_H	Josh Elijah	Added support for previous versions of GigaBlox

8 Contact

If you have any questions regarding this product, please contact us:

info@botblox.org

4 Pavilion Court 600 Pavilion Drive,
Northampton Business Park,
Northampton,
England
NN4 7SL

9 Certificate of Conformity

The full text of the Certificate of Conformity of this product is available at the following web address. <https://botblox.io/documentation/>