

To
Electronics Bottle

Mates with:
Impulse
BH-4-FS SS (w/ DLSA-F)

P1
Impulse IL-4-MP (w/ DLSA-M)

1	COMMON
2	ANODE
3	CATHODE
4	TRIGGER

SO4 Cable
Length = 8' (Verify)


COMMON
ANODE
CATHODE
TRIGGER

P2
Impulse LPIL-4-FS

1	COMMON
2	ANODE
3	CATHODE
4	TRIGGER

To
Flash Head

Mates with:
Impulse
LPBH-4-MP SS w/ 0.5" thread



Schematic Name: OI - LASS				
Page Title: W16 - Strobe #3 Cable			Engineer: Chad Key	
Project Name: Ocean Imaging	Group Name: OceanImagingLASSROV		Designer: Chad Key	
System: <System>	Subsystem: <Subsystem>		Last Updated By: ckey	
Drawing Number: 100222132	Release: A	Version: 2	Status: Active	Size: B
Page Modify Date: Tuesday, January 30, 2024	Check In Date: 1/30/2024 2:22:36 PM		Sheet 1 of 1	