

P04
MNK10 CCP

- 1 ROT1 RS485A
- 2 ROT1 RS485B
- 3 ROT GND
- 4
- 5 ROT 24V
- 6 ROT2 RS485A
- 7
- 8
- 9
- 10 ROT2 RS485B

J25
LPIL4F

- 1 ROT GND
- 2 ROT 24V
- 3 ROT1 RS485A
- 4 ROT1 RS485B

J26
LPIL4F

- 1 ROT GND
- 2 ROT 24V
- 3 ROT2 RS485A
- 4 ROT2 RS485B

MOLDED JUNCTION

MOLDED JUNCTION

MOLDED JUNCTION

ORANGE FALMAT CABLE

BLACK 2 TWISTED PAIR CABLE

24" WHIP, LPIL5F, 18/4 SOOW



Schematic Name: Power Can v2 - Kecy					
Page Title: 07a Rotator Breakout			Engineer: Eric Martin		
Project Name: Ocean Imaging			Designer: N/A		
Group Name: Ocean Imaging		System: Low Altitude Survey System		Subsystem: Power Can	
Drawing Number: 100221827		Release: A		Version: 6	
Page Modify Date: Friday, August 05, 2022		Check In Date: 11/18/2020 4:20:33 PM		Status: Active	
		Sheet 6		of 10	
				Size: B	