



- 30 A per power blade and 1 A per signal pin
- Low 7.5 mm profile design (right-angle) for improved system airflow and space savings
- Double-stacked power blades per bank for increased density and power
- Ideal for coplanar and perpendicular applications
- 2, 4, 6, 8, or 10 total power blades on 12.00 mm (.472") pitch
- 16, 20, 24 or 32 total signal pins on .050" (1.27 mm) pitch
- Rugged guide posts are standard for blind mating assistance
- Socket available as vertical with press-fit tails and right-angle through-hole
- Terminal available as right-angle through-hole
- Socket and terminal mating or socket mates with standard .062" (1.60 mm) and (2.36 mm) .093" PCB cards
- Dual sourced by Molex®



© JANUARY 2023, SAMTEC, INC.