

P1
MCIL8M

Length = 1m, 2m, or 3m

P2
MCIL8F

1	BATT_POS	20 AWG	BLACK	BLACK	20 AWG	BATT_POS	1
2	BATT_POS	20 AWG	WHITE	WHITE	20 AWG	BATT_POS	2
3	BATT_NEG	20 AWG	RED	RED	20 AWG	BATT_NEG	3
4	BATT_NEG	20 AWG	GREEN	GREEN	20 AWG	BATT_NEG	4
5	COMM_A	20 AWG	ORANGE	ORANGE	20 AWG	COMM_A	5
6	COMM_B	20 AWG	BLUE	BLUE	20 AWG	COMM_B	6
7	TRIG_OUT	20 AWG	WHITE / BLACK	WHITE / BLACK	20 AWG	TRIG_OUT	7
8	TRIG_IN	20 AWG	RED / BLACK	RED / BLACK	20 AWG	TRIG_IN	8

MONTEREY BAY AQUARIUM RESEARCH INSTITUTE

7700 SANDHOLDT ROAD

MOSS LANDING, CA 95039

(831) 775-1700 www.mbari.org

Copyright MBARI 2000



Title**SeeStar Intermodule Cable**

Number <Doc>

Size**B**

Engineer**Chad Key**

Layout <Layout Eng.>

Filename <Filename>

Rev**B**

Date: Thursday, August 07, 2014

Sheet 9 of 9